F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2021-922PT.1-AC	COOK	460	12
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62693

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	URBAN QUANTITY	90% FED. 10% STATE URBAN ROADWAY IDOT J000-2A	100% STATE URBAN ROADWAY J000	90% FEDERAL / 10% STATE RETAINING WALLS 016-W882 Y007	016-W886 Y007	016-W894 016-W964 Y007	016-W901 Y007	016-W903 016-W906 Y007	016-W907 Y007	016-W887 016-W965 Y007	016-WWRR Y007	100% STATE CORNER GARDENS Y007	90% FED./10% STATE SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	SIGNALS Y031-1F
•	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8															8	
•	X0320080	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	FOOT	1,683																1,683
	X0320772	WATER MAIN REMOVAL 12"	FOOT	183		183														
*	X0322124	STORM SEWERS (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	390		390														
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	294		294														
	X0323314	MANHOLE, TYPE A, CITY OF CHICAGO	EACH	7		7														
	X0323315	MANHOLE, TYPE B, CITY OF CHICAGO	EACH	4		4														
	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	374	146	228														
•	X0323768	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID	EACH	7																7
	X0323814	SANITARY SEWER REMOVAL, 18"	FOOT	322		322														
•	X0323900	CONCRETE FOUNDATION, TYPE 1	FOOT	4															4	
•	X0323907	COMMUNICATIONS VAULT	EACH	4															4	
	X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	58,280				22,660	8,680		10,280		16,482		178					
	X0324112	BARRIER BASE	FOOT	466	466															
	X0324159	WHITEWASHING FOR CONCRETE PAVEMENT	SQ YD	9,257	9,257															
*	X0324165	COMBINED SEWERS, ESVCP, TYPE 2, 12"	FOOT	10		10														
*	X0324166	COMBINED SEWERS, ESVCP, TYPE 2, 15"	FOOT	35		35														
*	X0324347	COMBINED SEWERS, RCCP, TYPE 2, 24"	FOOT	1,509		1,509														
*	X0324350	COMBINED SEWERS, ESVCP, TYPE 2, 18"	FOOT	329		329														
•	X0324354	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	2,492																2,492
•	X0324415	CONDUIT ENCASED, REINFORCED CONCRETE, 1-4" DIA., CNC	FOOT	107														21	86	
•	X0324420	PVC CONDUIT IN TRENCH, 4" DIA. (SCHEDULE 40)	FOOT	3,936																3,936
•	X0324421	RACKING CABLES IN MANHOLE OR HANDHOLE	EACH	9																9
•	X0324424	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SOIL	FOOT	74																74
	X0324433	LIGHT TOWER SERVICE PAD, 6"	SQ FT	105														105		
•	X0324435	CLEAN EXISTING MANHOLE OR HANDHOLE	EACH	4															2	2
•	X0324469	CONDUIT ENCASED, REINFORCED CONCRETE, 2-4" DIA., CNC	FOOT	258														251	7	
•	X0324470	CONDUIT ENCASED, REINFORCED CONCRETE, 3-4" DIA., CNC	FOOT	30														10	20	
•	X0324471	CONDUIT ENCASED, REINFORCED CONCRETE, 4-4" DIA., CNC	FOOT	421														40	381	
•	X0324472	CONDUIT ENCASED, REINFORCED CONCRETE, 5-4" DIA., CNC	FOOT	72														29	43	

* DENOTES SPECIALTY ITEMS

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5212. PHONE: (312) 938-0300

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SUMMARY OF QUANTITIES

SCALE: NONE — DRAWN BY: AMM
DATE: October 29, 2004 — CHECKED BY: RMC

11/29/2004 9:23:55 AM

m:\p40468\civil\14-civil\90\str\general\sq090007.pss.str