F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2021-922PT.1-AC	COOK	460	15
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62693

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	QUANTITY	90% FED 10% STATE / 100% STATE	90% FEDERAL / 10% STATE											
				URBAN	URBAN ROADWAY		RETAINING WALLS								SIGNING	SAFETY	LIGHTING	SURVEILLANCE	SIGNALS
					IDOT		016-W882	016-W886	016-W894 016-W964	016-W901	016-W903 016-W906	016-W907	016-W887 016-W965	016-WWRR					
					J000-2A	J000	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007		Y002-1C	SFTY-3N	Y030-1E	Y032-1F	Y031-1F
•	X0324871	CONDUIT IN TRENCH, 4" DIA., COILABLE NON-METALLIC	FOOT	10														10	
•	X8101300	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL, PVC COATED	FOOT	132														132	
•	X0324515	ELECTRICAL HANDHOLE, 36", 30" FRAME AND LID	EACH	2															2
*	X0324793	LIGHT TOWER SERVICE PAD, SPECIAL	SQ FT	959														959	
*	X0324791	UTILITY TRANSFORMER PAD, 4"	EACH	1														1	
*	X0324872	CAST IN PLACE TACTILE/DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES	SQ FT	83		83													
•	X0324873	CONDUIT ENCASED, REINFORCED CONCRETE, 7-4" DIA., CNC	FOOT	155														66	89
•	X0324874	CONDUIT ENCASED, REINFORCED CONCRETE, 3-2" DIA., RGC & 2-4" DIA., CNC	FOOT	3														1	2
•	X0324501	CONDUIT ENCASED, REINFORCED CONCRETE, 3-2" DIA., RGC & 3-4" DIA., CNC	FOOT	83														28	55
•	X0324875	DRILL EXISTING RETAINING WALL	EACH	2														2	

• DENOTES SPECIALTY ITEMS

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO, ILLINOIS 60601-5210, PHONE: (312) 938-0300

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SUMMARY OF QUANTITIES

SCALE: NONE
DRAWN BY: NJH
DATE: October 29, 2004
CHECKED BY: RMG

MAY-4-04 9:53:48 AM 11/29/2004 MAY-4-04 C:\WIN4F-Chi-95\SN\General\SS05800102.ASHT