

CURB AND GUTTER SCHEDULE

MEDIAN SCHEDULE

STATION TO STATION	SHEET	CDOT			RAMPS AND MAINLINE			CORNER GARDEN	CDOT			RAMPS AND MAINLINE					
		COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12 (MODIFIED)	COMBINATION CONCRETE CURB & GUTTER, TYPE B-V.12	COMBINATION CONCRETE CURB & GUTTER, (SPECIAL)	COMBINATION CONCRETE CURB & GUTTER, TYPE M-2.12	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.12	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.24	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.48 (MODIFIED)	CONCRETE CURB, TYPE B (SPECIAL)	CONCRETE MEDIAN TYPE SB 6.12	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	AGGREGATE BASE COURSE, TYPE B 4"	BITUMINOUS SHOULDERS, 1 1/2"	BITUMINOUS SHOULDERS, SUPERPAVE, 6"	SAND BACKFILL	CONCRETE MEDIAN SURFACE, 6"	CONCRETE MEDIAN SURFACE 6" (SPECIAL)
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	SO FT	SO YD	SO YD	SO YD	CU YD	SO FT	SO FT	
WENTWORTH AVENUE																	
99+99.22 TO 103+00.00	1	0	602	0	0	0	0	0	0	1,812	0	0	0	0	0	0	
103+00.00 TO 108+00.00	2	270	588	3	266	35	0	50	0	494	128	128	228	0	0	0	
108+00.00 TO 113+00.00	3	417	504	25	0	500	0	423	0	525	137	137	16	0	0	0	
113+00.00 TO 118+00.00	4	500	430	0	0	172	149	352	0	1,500	0	0	0	0	0	0	
118+00.00 TO 123+00.00	5	500	500	0	0	53	23	479	0	1,500	0	0	0	0	0	214	
123+00.00 TO 128+00.00	6	511	486	0	109	381	0	403	0	808	0	0	49	0	0	231	
128+00.00 TO 133+00.00	7	327	427	0	185	157	0	0	0	657	0	0	104	0	0	0	
SUB-TOTALS		2,525	3,537	28	560	1,298	172	1,657	50	7,296	265	265	397	0	0	445	
WELLS STREET																	
506+92.81 TO 511+50.00	8	373	480	0	0	0	0	60	28	516	24	114	114	0	0	0	
511+50.00 TO 516+50.00	9	500	500	0	0	121	0	501	0	822	93	93	0	39	1,138	390	
516+50.00 TO 521+75.00	10	525	506	0	0	0	223	302	0	1,225	0	0	0	0	0	0	
521+75.00 TO 526+75.00	11	500	453	0	0	339	0	501	0	1,500	0	0	0	0	0	0	
526+75.00 TO 531+75.00	12	529	502	0	15	487	0	182	0	1,273	0	0	9	0	0	0	
531+75.00 TO 536+75.00	13	323	341	0	225	81	0	0	0	1,229	0	0	82	0	0	323	
SUB-TOTALS		2,750	2,782	0	240	1,028	223	1,546	28	516	6,073	207	207	91	39	1,138	713
TOTALS		5,275	6,319	28	800	2,326	395	3,203	78	516	13,369	472	472	488	39	1,138	1,158



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SCHEDULE OF QUANTITIES

SCALE: NONE
 DATE: October 29, 2004

DRAWN BY: AMM
 CHECKED BY: RMG

11/29/2004 9:24:57 AM