

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	(1R)TS	KANKAKEE	22	5
STA.	TO STA.			
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				

CONTRACT NO. 66416

EARTHWORK QUANTITIES				
LOCATION	THEORETICAL		FURNISHED EXCAVATION SHORTAGE (-) OR EXCESS (+)	REMARKS
	CUT	FILL		
	CU YD	CU YD	CU YD	
			[(A)0.75]-(B)	
	(A)	(B)	(C)	
IL RTE 17	379	394	-110	
LOWE ROAD	66	17	32	
TOTAL	445	411	-78	
	PAY ITEM	INFO ONLY	PAY ITEM	

PAVED SHOULDER REMOVAL	
LOCATION	SQ YD
RT. STA. 52+43.05 TO LOWE ROAD	730.2
MEDIAN STA. 57+74.88 TO LOWE ROAD	26.5
RT. LOWE ROAD TO STA. 60+11.72	134.8
MEDIAN LOWE ROAD TO STA. 65+00	264.1
TOTAL	1156

PAVEMENT SCHEDULE															
LOCATION (STA. TO STA.)	STABILIZED SUB-BASE, 4"	AGGREGATE SURFACE COURSE, TYPE A 6"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE PRIME COAT	MIXTURE FOR CRACKS, JOINTS, & FLANGWAYS	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	AGGREGATE SHOULDERS TYPE A 6"	AGGREGATE SHOULDERS TYPE B	BITUMINOUS SHOULDERS SUPERPAVE 6"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	BITUMINOUS BASE COURSE SUPERPAVE 5 1/2"	BITUMINOUS BASE COURSE SUPERPAVE 12"	LEVELING BINDER (MACHINE METHOD) SUPERPAVE, N70
	SQ YD	SQ YD	GAL	TON	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD	TON	SQ YD	SQ YD	SQ YD	SQ YD
LOWE ROAD RT. STA. 1+21 TO STA. 2+37.26	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---
LOWE ROAD LT. STA. 1+21 TO STA. 2+37.26	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---
RT. STA. 52+43.05 TO LOWE ROAD STA. 1+21	824.7	---	---	---	---	---	---	---	---	319.3	---	---	---	---	720.8
MEDIAN STA. 57+74.88 TO LOWE ROAD	92.5	---	---	---	---	---	---	---	---	---	---	---	---	---	70.0
RT. LOWE ROAD TO STA. 60+11.72	186.8	---	---	---	---	---	---	---	---	---	---	---	---	---	163.0
MEDIAN LOWE ROAD TO STA. 65+00	771.4	---	---	---	---	---	---	---	---	236.2	---	---	---	---	668.2
STA. 51+96.34 TO STA. 65+50	---	---	1049	20	3.2	---	---	---	135	---	1101	---	---	---	644
LT. & RT. STA. 51+96.34	---	---	---	---	---	495.5	26.7	---	---	---	---	---	---	---	---
LT. & RT. STA. 65+50	---	---	---	---	---	482.5	26.7	---	---	---	---	---	---	---	---
LT. STA. 1+04 (LOWE ROAD)	---	---	---	---	---	55.0	17.5	---	---	---	---	---	---	---	---
LT. STA. 1+87 (LOWE ROAD)	---	---	---	---	---	---	15.4	---	---	---	---	---	---	---	---
LOWE ROAD STA. 2+37.26	---	---	---	---	---	241.4	16.0	---	---	---	---	---	---	---	---
LOWE ROAD RT. STA. 1+21 TO STA. 2+37.26	---	---	---	---	---	---	---	41.1	---	---	---	---	---	---	---
MEDIAN STA. 64+13.42 TO STA. 65+00	---	---	---	---	---	---	---	19.2	---	---	---	---	---	---	---
DRIVEWAY RT. STA. 1+13	---	53	---	---	---	---	---	---	---	---	---	---	---	---	---
TOTAL	1875.4	53	1049	20	3.2	1274	102	60.3	135	555.5	1101	125	74	1622	644

THERMOPLASTIC PAVEMENT MARKING AND TEMPORARY PAVEMENT MARKING						
LOCATION	4" WHITE	4" YELLOW	6" WHITE	8" WHITE	24" WHITE	LETTERS & SYMBOLS
	FOOT	FOOT	FOOT	FOOT	FOOT	SQ. FT.
FUNDING TYPE	①	①	①	①	①	①
EDGE LINES						
STA. 51+96.34 TO STA. 65+50	2865	2604	---	---	---	---
LOWE ROAD		371				
DASHED CENTERLINE						
STA. 51+96.34 TO STA. 65+50	---	---	680	---	---	---
TURN LANES						
STA. 51+96.34 TO STA. 65+50	---	---	---	637	---	---
STOP BARS						
STA. 51+96.34 TO STA. 65+50	---	---	---	---	125	---
LETTERS & SYMBOLS						
STA. 51+96.34 TO STA. 65+50	---	---	---	---	---	156
TOTAL	2865	2975	680	637	125	156

STORM SEWER AND PIPE CULVERT SCHEDULE					
LOCATION	PIPE CULVERT TYPE 1		END SECTION	PRECAST REINFORCED CONCRETE FLARED END SECTION	INLET TYPE A
	CLASS A	CLASS D			
	18"	18"	18"	18"	TYPE 8 GRATE
RT. STA. 59+50	62				
RT. STA. 0+80.2 TO STA. 0+84.7		25			
LT. STA. 0+67.4 TO STA. 0+68.0		3			
RT. STA. 0+99.8 TO STA. 1+31.2		38			
STA. 0+66.0, 40.3' LT.			1		
STA. 0+85.1, 65.3' RT.			1		
STA. 0+98.0, 62.4' RT.			1		
STA. 1+32.9, 35.6' RT.			1		
STA. 59+50, 68' RT.				1	
STA. 59+50, 0' RT.					1
TOTAL	62	66	4	1	1

IL ROUTE 17  
AND CH 38 / LOWE ROAD  
SUMMARY OF QUANTITIES  
FAP ROUTE 330, FAU ROUTE 6209  
SEC. NO. (1R)TS  
KANKAKEE COUNTY