

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
117	PA BRIDGE REP.	PEORIA	14	3
STA. 409+99.08		TO STA. 414+72.02		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

# SUMMARY OF QUANTITIES

## 100% STATE SAFETY - 2A PEORIA COUNTY

CODE NO.	ITEM	UNIT	RURAL	TOTAL
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ. YD.	1516	1516
50102400	CONCRETE REMOVAL	CU. YD.	23	23
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	23	23
50800205	REINFORCEMENT BARS, EPOXY COATED	POUNDS	3655	3655
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ. YD.	1516	1516
67000400	ENGINEER'S FIELD OFFICE , TYPE A	CAL. MO.	2.0	2.0
67100100	MOBILIZATION	L. SUM	1.0	1.0
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1.0	1.0
70100307	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	EACH	1.0	1.0
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	3330	3330
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	240	240
70400100	TEMPORARY CONCRETE BARRIER	FOOT	624	624
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	624	624
78000200	THERMOPLASTIC PAVEMENT MARKING LINE, 4"	FOOT	1440	1440
78000400	THERMOPLASTIC PAVEMENT MARKING LINE, 6"	FOOT	36	36

PLOT DATE = 05/18/04  
 FILE NAME = 4P11E14  
 PLOT SCALE = 1/8"=1'-0"  
 REFERENCE = 08E11

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SUMMARY OF QUANTITIES

SCALE: VERT.      DRAWN BY CEJ  
 HORIZ.              CHECKED BY  
 DATE 05-18-2004