

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	04 BRIDGE REF.	PEORIA	14	6
STA. 499+99.08		TO STA. 514+72.02		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

SCHEDULE OF QUANTITIES

PAVEMENT MARKING TAPE, TYPE III, 4"

JOBSITE BRIDGE DECK = 3330 FOOT

CONCRETE SUPERSTRUCTURE

PARAPET WALLS & PIER 3 = 8.7 CU. YD.
 N. ABUT. & DECK STA. 409+99.35 = 7.15 CU. YD.
 S. ABUT. & DECK STA. 413+50.23 = 7.15 CU. YD.
 TOTAL = 23.0 CU. YD.

WATERPROOFING MEMBRANE SYSTEM

JOBSITE BRIDGE DECK = 1516 SQ. YDS.

BIT. SURF. CRSE, SUPERPAVE, N50, 1 3/8"

JOBSITE BRIDGE DECK = 119 TON

ENGINEERS FIELD OFFICE, TYPE A

JOBSITE = 2.0 CAL. MO.

MOBILIZATION

JOBSITE = 1.0 LSUM

THERMOPLASTIC PAVEMENT MARKING LINE, 4"

JOBSITE BRIDGE DECK = 1440 FOOT

THERMOPLASTIC PAVEMENT MARKING LINE, 6"

JOBSITE BRIDGE DECK = 36 FOOT

DATE * * * * *
 FILE NAME * * * * *
 PLOT SCALE * * * * *
 REFERENCE * * * * *

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY CEJ
 HORIZ. CHECKED BY
 DATE 01-13-2004