

FAU RTE 2652 - SOUTH VILLA AVENUE
 FROM ROOSEVELT ROAD TO MADISON STREET
 SECTION 00-00069-00-PV

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00069-00-PV	DUPAGE	146	7
STA. 10+70.70		TO STA. 66+16.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 83781				

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	H23 ROADWAY 1000-2A	Q40 SIDEWALK 1000-1B	H23 LIGHTING Y030-1E	PARTICIPATING QUANTITY		07C NON-PART. QUANTITY
							STP QUANTITY	CMAQ QUANTITY	
X2800100	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	40	40			40		Y060
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	20,461	20,461			20,461		
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	310	310			310		
X4066424	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX "D", N50	TON	1,754	1,754			1,754		
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	2,925	2,925			2,925		
XX002161	ABANDON EXISTING WATER MAIN	EACH	2						2
XX002895	SANITARY MANHOLES TO BE RECONSTRUCTED WITH NEW FRAME & LID	EACH	5	5			5		
XX002982	GATE VALVES 6"	EACH	2						2
XX004208	SEWER SERVICE LATERAL REPAIR, 6" POLYVINYL CHLORIDE	FOOT	360	360			360		
XX004592	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	5	5			5		
XX005084	LIGHTING CONTROLLER FOUNDATION	EACH	2			2	2		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	23,495	23,495			23,495		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			1		
Z0076600	TRAINEES	HOUR	1,500	1,500			1,500		
XX006107	LIGHT POLE, ALUMINUM, 30 FT. M.H., 8 FT. MAST ARM, BREAKAWAY BASE	EACH	48			48	48		
XX006108	UNIT DUCT, WITH 4-1/C NO. 6 AND 2-1/C NO. 8 GROUND, 600V (XLP-TYPE USE), 1/2" DIA., POLYETHYLENE	FOOT	1,661			1,661	1,661		
XX006109	UNIT DUCT, WITH 4-1/C NO. 4 AND 2-1/C NO. 8 GROUND, 600V (XLP-TYPE USE), 1/2" DIA., POLYETHYLENE	FOOT	3,069			3,069	3,069		
XX006110	UNIT DUCT, WITH 2-1/C NO. 4 AND 1/C NO. 8 GROUND, 600V (XLP-TYPE USE), 1" DIA., POLYETHYLENE	FOOT	178			178	178		
XX006111	WATER SERVICE RECONNECTION, WITH NEW BUFFALO BOX, LONG SIDE 1"(Minimum)	EACH	16						16
XX006112	WATER SERVICE RECONNECTION, WITH NEW BUFFALO BOX, SHORT SIDE 1" (Minimum)	EACH	12						12
XX006113	REMOVE EXISTING FIRE HYDRANTS	EACH	5						5
XX006114	NON-PRESSURE CONNECTION, 3"	EACH	1						1
XX006115	NON-PRESSURE CONNECTION, 6"	EACH	2						2
XX006116	NON-PRESSURE CONNECTION, 10"	EACH	1						1
XX006117	CASING PIPE IN TRENCH	FOOT	25						25
XX006118	DUCTILE IRON WATER MAIN IN STEEL CASING (DIRECTIONL BORED)	FOOT	72						72

Δ - Y080

REVISIONS	
NAME	DATE



VILLAGE OF VILLA PARK, ILLINOIS
SOUTH VILLA AVENUE
SUMMARY OF QUANTITIES
SHEET 5 OF 5
 SCALE: NONE
 DATE: 11-NOV-2004
 DRAWN BY: E.D.
 CHECKED BY: J.T.C.

PLAN
 DATE: _____
 BY: _____
 CHECKED: _____
 DATE: _____
 NO. _____

PROFILE
 DATE: _____
 BY: _____
 CHECKED: _____
 DATE: _____
 NO. _____