

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
619	70 RS-5 & I	LASALLE	214	4
STA.		TO STA.		

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FEDERAL 20% STATE ROADWAY 0005	80% FEDERAL 20% STATE CULVERT 0040	80% FEDERAL 20% STATE CULVERT 0040
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	313	313		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2		
54215550	METAL END SECTIONS 15"	EACH	44	44		
54215553	METAL END SECTIONS 18"	EACH	20	20		
54215985	REINFORCED CONCRETE PIPE ELBOW 30"	EACH	1	1		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	850	850		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	338	338		
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	36	36		
55100500	STORM SEWER REMOVAL 12"	FOOT	36	36		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60218700	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 5 FRAME, OPEN LID	EACH	2	2		
60218800	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 5 FRAME, CLOSED LID	EACH	2	2		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	7	7		
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4	4		
60237000	INLETS, TYPE A, TYPE 15 FRAME AND LID	EACH	1	1		
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	1	1		
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	3	3		
60240320	INLETS, TYPE B, TYPE 15 FRAME AND LID	EACH	1	1		
60240327	INLETS, TYPE B, TYPE 23 FRAME AND GRATE	EACH	1	1		
60263100	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	1	1		
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	5	5		
60500060	REMOVING INLETS	EACH	6	6		
60500305	FILLING INLETS	EACH	1	1		
60600605	CONCRETE CURB, TYPE B	FOOT	128	128		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3345	3345		
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	74	74		
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	220	220		
60615400	PAVED DITCH, TYPE A-15	FOOT	402	402		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	564	564		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
63200310	GUARDRAIL REMOVAL	FOOT	2854	2854		
63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	13	13		
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	51	51		
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	260	260		
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1		
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		

*SPECIALTY ITEM

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FEDERAL 20% STATE ROADWAY 0005	80% FEDERAL 20% STATE CULVERT 0040	80% FEDERAL 20% STATE CULVERT 0040
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	3	3		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	45		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5366	5366		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	718	718		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	78611	78611		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5619	5619		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	5227	5227		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2973	2973		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	673	673		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17257	17257		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	179	179		
* 73000100	WOOD SIGN SUPPORT	FOOT	368	368		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	276	276		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	36560	36560		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2759	2759		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2315	2315		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1269	1269		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	313	313		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	353	353		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	346	346		
* 70056008	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	119	119		
70034105	MATERIAL TRANSFER DEVICE	TON	3958	3958		
X5011100	FOUNDATION REMOVAL	EACH	1	1		
Z0054400	ROCK FILL	CU YD	205		205	
† Z0076600	TRAINEES	Hour	1000	1000		

† CONSTRUCTION TYPE CODE 0042

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SUMMARY OF QUANTITIES</p> <p>FAP ROUTE 619 (IL ROUTE 71 /351) SECTION NO. 70 RS-5 & I LASALLE COUNTY</p> <p>SCALE: VERT. DRAWN BY BANDY HORIZ. CHECKED BY STEUART DATE</p>

PLT DATE = Oct 05, 2010 - 11:30:36 AM
 FILE SCALE = 500000
 USER NAME = bergantano.je