

SUMMARY OF QUANTITIES

				ADAMS COUNTY 80% FEDERAL 20% STATE IL 61/94	HANCOCK COUNTY 80% FEDERAL 20% STATE IL 61/94					ADAMS COUNTY 80% FEDERAL 20% STATE IL 61/94	HANCOCK COUNTY 80% FEDERAL 20% STATE IL 61/94
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005	CONSTRUCTION TYPE CODE 0005	SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0005	CONSTRUCTION TYPE CODE 0005
CODE NO.	ITEM	UNIT	TOT. QUAN.			CODE NO.	ITEM	UNIT	TOT. QUAN.		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	132,115	61,525	70,590	*78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	42		42
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	53	15	38	*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	715	268	447
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	56	24	32	*78200420	GUARDRAIL MARKERS, TYPE B	EACH	4		4
40600300	AGGREGATE (PRIME COAT)	TON	278	124	154	*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	18	4	14
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	5,531	2,565	2,966	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	518	94	424
40600895	CONSTRUCTING TEST STRIP	EACH	1		1						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	3,260	638	2,622						
40600990	TEMPORARY RAMP	SO YD	87	43	44						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	13,691	5,150	8,541						
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	444	124	320						
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	2,926		2,926						
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	376		376						
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	675	270	405						
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	425	170	255						
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SO YD	180	72	108						
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,893	1,587	2,306						
48203100	HOT-MIX ASPHALT SHOULDERS	TON	67	50	17						
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6' ^{FOOT} POSTS	FOOT	25		25						
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	18	4	14						
63200310	GUARDRAIL REMOVAL	FOOT	890	200	690						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1.6	2.4						
67100100	MOBILIZATION	L SUM	1	0.4	0.6						
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.4	0.6						
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.4	0.6						
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1						
70300100	SHORT TERM PAVEMENT MARKING	FOOT	15,387	5,788	9,599						
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	135,233	52,749	82,484						
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	42		42						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1,710	643	1,067						
*72000100	SIGN PANEL - TYPE 1	SO FT	9	9							
*72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	14	14							
*78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	135,233	52,749	82,484						

**Specialty Items*