

CONTRACT 60157
TEMPORARY INFORMATION SIGNING - STAGE 1

SIGN NO.	STATION	LEGEND/DESCRIPTION	PANEL		PANEL
			COVER DIMENSIONS		COVER AREA
			WIDTH (FT)	HEIGHT (FT)	(SQ FT)
N/A	N/A	IL 64 EAST TRUCKS - 290 20 - CHICAGO	2.0	2.0	4.0
WB-TR-29	296+60	EXIT 12 - 20 WEST YORK ROAD - IL 64 DETOUR	11.0	7.0	80.0
WB-TR-29	296+60	EXIT 12 - 20 WEST YORK ROAD - RIGHT LANE	29.0	2.5	72.5
WB-TR-28	296+60	290 WEST - ROCKFORD	6.0	6.0	36.0
EB-TR-26	314+80	EXIT 15A - 290 EAST 294 SOUTH TOLLWAY - CHICAGO INDIANA	2.0	2.0	4.0
WB-TR-31	321+05	EXIT 12 - 20 WEST YORK ROAD - IL 64 DETOUR	11.0	7.0	80.0
WB-TR-31	321+05	EXIT 12 - 20 WEST YORK ROAD - RIGHT COVER	2.0	2.0	4.0
WB-TR-30	321+05	290 WEST - ROCKFORD	2.0	2.0	4.0
WB-BM-32	327+80	IL 64 WEST - TRUCK ROUTE - KEEP RIGHT	15.5	2.0	31.0
EB-TR-29	335+40	EXIT 15A - 290 EAST 294 SOUTH TOLLWAY - CHICAGO INDIANA	2.0	2.0	4.0
EB-TR-30	335+40	EXIT 13A - IL 64 20 EAST 294 NORTH TOLLWAY - NORTH AVE - LAKE ST - MILWAUKEE	4.0	4.0	16.0
WB-GM-33	343+20	IL 64 WEST - TRUCK ROUTE - EXIT 12	15.5	2.0	31.0
WB-TR-37	354+50	EXIT 13B - IL 64 WEST - NORTH AVE	13.0	2.5	32.5
WB-TR-40	373+00	EXIT 13B - IL 64 WEST - NORTH AVE - 1/4 MILE	13.0	2.5	32.5
WB-CL-42	383+90	IL 64 WEST - THRU TRUCKS - USE EXIT 12	15.5	2.0	31.0
WB-TR-43	391+50	EXIT 13B - IL 64 WEST - NORTH AVE - 3/4 MILE	13.0	2.5	32.5
EB-TR-44	445+40	EXIT 17 - 12 20 45 - MANNHEIM RD - 1 MILE - EXIT ONLY	17.5	2.0	35.0
EB-CL-47	468+60	EXIT 17 - 12 20 45 - MANNHEIM RD - EXIT ONLY	17.5	2.0	35.0
WB-TR-56	474+80	294 NORTH ONLY	10.0	2.5	25.0
WB-TR-58	484+20	294 NORTH EXIT ONLY - RIGHT LANE	17.5	2.0	35.0
WB-CL-59	489+90	294 NORTH EXIT ONLY	17.5	2.0	35.0
N/A	N/A	290 2010 - REPAIR & - RESURFACING - THORNDALE TO DOWNTOWN - EXPECT DELAYS	17.0	9.0	306.0
N/A	409+50	LEFT LANE - NEXT EXIT - 20 WEST - LAKE ST - YORK RD RIGHT LANE - ALL - EXITS	21.2	10.5	222.2
TOTAL					1184.2

CONTRACT 60157
RUMBLE STRIP SCHEDULE

I-290 EASTBOUND AND WESTBOUND - INSIDE AND OUTSIDE SHOULDERS			
STATION TO STATION		RUMBLE STRIP LENGTH	SHOULDER SURFACE TYPE
START	END	(FOOT)	
267+40	272+10	470	HMA
272+10	295+00	2,290	HMA
295+00	336+00	4,100	HMA
336+00	347+60	1,160	HMA
347+60	350+00	240	HMA
350+00	372+00	2,200	HMA
372+00	452+00	8,000	HMA
452+00	474+00	2,200	HMA
474+00	480+50	650	HMA
TOTAL		21,310	

CONTRACT 60157
TEMPORARY INFORMATION SIGNING - STAGE 2

SIGN NO.	STATION	LEGEND/DESCRIPTION	PANEL		PANEL
			COVER DIMENSIONS		COVER AREA
			WIDTH (FT)	HEIGHT (FT)	(SQ FT)
WB-TR-28	296+60	290 WEST - ROCKFORD	29.0	2.5	72.5
WB-TR-29	296+60	EXIT 12 - 20 WEST YORK ROAD - LAKE ST - EXIT ONLY	2.0	2.0	6.0
EB-TR-26	314+80	EXIT 15A - 290 EAST 294 SOUTH TOLLWAY - CHICAGO INDIANA	2.0	2.0	4.0
WB-TR-40	373+00	IL 64 WEST 1/4 MILE	17.5	2.0	35.0
WB-TR-57	484+20	290 WEST - ROCKFORD	2.0	2.0	4.0
TOTAL					121.5

SIGN NO.	STATION	LEGEND/DESCRIPTION	PANEL		PANEL
			COVER DIMENSIONS		COVER AREA
			WIDTH (FT)	HEIGHT (FT)	(SQ FT)
EB-TR-26	314+80	EXIT 15A - 290 EAST 294 SOUTH TOLLWAY - CHICAGO INDIANA	2.0	2.0	4.0
EB-TR-29	335+40	EXIT 15A - 290 EAST 294 SOUTH TOLLWAY - CHICAGO INDIANA	2.0	2.0	4.0
WB-CL-59	489+90	EXIT 15B - 294 NORTH - TOLLWAY - MILWAUKEE - EXIT ONLY	14.0	2.5	35.0
TOTAL					43.0

CONTRACT 60157
TEMPORARY PAVEMENT MARKING AND TEMPORARY IMPACT ATTENUATOR SCHEDULE

STAGE	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS (SQ FT)	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH (FOOT)	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 6" (FOOT)	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8 INCH (FOOT)	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH (FOOT)	PAVEMENT MARKING REMOVAL (SQ FT)	EPOXY PAVEMENT MARKING - LINE 4 INCH	EPOXY PAVEMENT MARKING - LINE 5 INCH	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)
1	545	57,681	80,949	8,664	39,253	6,836	34,133			12			
2	0	53,539	9,936	13,717	44,548	6,552	15,152			2	2		11
3	0	93,265	24,153	3,127	28,794	7,008	0	66,000	6,600				2
TOTAL	545	204,484	115,038	25,508	112,594	20,396	49,285	66,000	6,600	12	2	2	13

FILE NAME #	DESIGNED - AJP	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#	DRAWN - TMB	REVISED -			290	2009-099BR	COOK/DUPAGE	309	14				
USER NAME = #USER#	CHECKED - JMM	REVISED -			SCALE: N.T.S. SHEET NO. 3 OF 3 SHEETS STA. TO STA.				CONTRACT NO. 60157				
PLOT DATE = #DATE#	DATE - 10/16/09	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								