SIGN DETAIL
1:75

EB-TR-43
STA. 445+40

SIGN NUMBER	name
WIDTH x HGHT.	17'-0" x 10'-6"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
M1_1	0	51.2	76	45	36
ARDOWN	0	14	12	32	22
ARDOWN	0	158	12	32	22

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)							LENGTH	SERIES/SIZE
E	A	S	T					ClearviewHwy-5-W
108.2	121	134.7	146.1				46.5	15,12
C	h	i	c	a	g	o		ClearviewHwy-5-W-R
53.1	70	85.8	93.6	107.2	122.5	138.6	97.8	16/13

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $LSER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING, LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 18 OF 58 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2009-099BR	COOK/DUPAGE	394	346
		CONTRACT NO. 60157		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT