SIGN DETAIL

1:75

EB-TR-45
STA. 445+40

FONT:
(1) ClearviewHwy-5-W-R
(2) ClearviewHwy-5-W

SIGN NUMBER	name
WIDTH x HGHT.	14'-0" x 10'-6"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
M1_1	0	18.3	49.5	45	36
ARMED	45	125.4	17.8	20	31.5

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

								LENGTH	SERIES/SIZE
E	X	I	T	1	5	A			ClearviewHwy-5-W
67.9	78.1	91.8	97.7	116.4	128.3	142.4		88.6	12,15
S	O	U	T	H					ClearviewHwy-5-W
75.3	90	105.5	118.3	130.6				64.4	15,12
T	O	L	L	W	A	Y			ClearviewHwy-5-W-R
75.3	84.5	96.8	105.2	112.6	127.1	137.5		70.9	10
l	n	d	i	a	n	a			ClearviewHwy-5-W-R
18.1	26.4	42	58.3	65.8	81.8	97		90.8	1613

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING,LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 20 OF 58 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2009-099BR	COOK/DUPAGE	394	348
		CONTRACT NO. 60157		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		