SIGN DETAIL
1:75

WB-TR-40
STA. 373+00

SIGN NUMBER	name
WIDTH x HGHT.	13'-6" x 12'-6"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
M1-1100A-2-22-100	0	30.5	65.5	39.3	36

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

																																								LENGTH	SERIES/SIZE
E	X	I	T	1	3	B																																				Clearview-Hwy-5-W
63.4	71.9	83.3	88.3	105.5	116.8	132.6																																		80.6	10,15
W	E	S	T																																							Clearview-Hwy-5-W
81.7	101.5	112.2	123.6																																					50.5	12
N	o	r	t	h		A	v	e																																	Clearview-Hwy-5-W-R
18.7	36.5	53.2	62.6	74.5	85.5	101	117.6	132.3																																125.3	1613
¼	M	I	L	E																																					Clearview-Hwy-5-W
50.7	77.5	90.7	96.6	105.6																																				61.3	12,10

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING, LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 34 OF 58 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2009-099BR	COOK/DUPAGE	394	362
		CONTRACT NO. 60157		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		