



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 18, 2026

SUBJECT FAP Route 348 (IL 43 (Waukegan Rd.))
Project NHPP-XQ53(404)
Section 2024-1049-RS
Cook County
Contract No. 62X88
Item No. 9, February 27, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added pages 134 & 135 to the Special Provisions.
4. Revised sheets 1, 2, 4, 6, 16, & 17 of the Plans.
5. Added sheet 72A to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

REBUILD EXISTING HANDHOLE.....	68
PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH (SPECIAL)	69
DRILLED SHAFTS.....	69
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....	80
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE)	82
COMPENSABLE DELAY COSTS (BDE).....	100
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	104
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	106
PAVEMENT MARKING (BDE)	107
PAVEMENT PATCHING (BDE).....	107
PERFORMANCE GRADED ASPHALT BINDER (BDE)	108
PREFORMED PLASTIC PAVEMENT MARKING (BDE).....	114
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)	115
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	115
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	117
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE).....	120
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	122
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	122
SUBMISSION OF BIDDERS LIST INFORMATION (BDE).....	123
SUBMISSION OF PAYROLL RECORDS (BDE).....	123
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	124
SURVEYING SERVICES (BDE).....	131
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	131
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	131
WORKING DAYS (BDE)	133
BOLLARD REMOVAL	134
REMOVE AND REINSTALL EXISTING BOLLARD	134
REMOVE AND REINSTALL EXISTING STEEL BENCH	135
REMOVE AND REINSTALL EXISTING TRASH RECEPTACLE	135

Revised 2/18/2026

BOLLARD REMOVAL

This item shall consist of the removal and satisfactory disposal of existing bollards as shown on the plans or as directed by the Engineer.

Description: The bollard posts shall be removed so that all material considered suitable by the Engineer for future use shall be salvaged. Posts having salvage value shall be removed without damage and those having no salvage value shall be pulled or cut off at least 6-inches below the ground surface. All holes shall be filled and tamped. Should the owner express a desire to retain any part of the bollard, the Contractor shall be responsible for returning the same to the owner at his/her own expense. The salvaged material shall be stored at locations and in a manner approved by the Engineer. Any of this material having salvage value and which has been damaged by the Contractor shall be replaced at his/her own expense with new material of the same kind.

Basis of Payment: This work shall be paid for at the contract unit price per EACH for BOLLARD REMOVAL, which price shall include all labor, equipment and materials to remove and dispose of the materials, and no additional compensation will be allowed.

REMOVE AND REINSTALL EXISTING BOLLARD

This work shall include the removal and reinstallation of the existing Decorative Cast Aluminum Bollard at locations impacted by the installation of new sidewalk curb ramps in accordance with the applicable portions of Section 424 of the Standard Specifications and as directed by the Engineer.

Description: Remove and Reinstall Existing Bollard shall include the complete removal and storage of the existing bollards and the reinstallation of bollards. The existing bollards shall be stored at locations and in a manner approved by the Engineer. Any damage to the existing bollards by the Contractor shall be restored or replaced at his/her own expense with new material of the same kind.

Basis of Payment: The work to remove and reinstall the existing bollards to the appropriate locations as determined by the Engineer shall be paid for at the contract unit price per EACH for REMOVE AND REINSTALL EXISTING BOLLARD, which price shall include all necessary labor, material and equipment necessary to complete the work.

REMOVE AND REINSTALL EXISTING STEEL BENCH

This work shall include the removal and reinstallation of the existing Decorative Steel Bench at locations impacted by the installation of new sidewalk curb ramps in accordance with the applicable portions of Section 424 of the Standard Specifications and as directed by the Engineer.

Description: Remove and Reinstall Existing Steel Bench shall include the complete removal and storage of the existing steel benches and the reinstallation of existing steel benches. The steel bench shall be stored at locations and in a manner approved by the Engineer. Any damage to the steel bench by the Contractor shall be restored or replaced at his/her own expense with new material of the same kind.

Basis of Payment: The work to remove and reinstall the existing steel benches to the appropriate locations as determined by the Engineer shall be paid for at the contract unit price per EACH for REMOVE AND REINSTALL EXISTING STEEL BENCH, which price shall include all necessary labor, material and equipment necessary to complete the work.

REMOVE AND REINSTALL EXISTING TRASH RECEPTACLE

This work shall include the removal and reinstallation of the existing Decorative Trash Receptacle at locations impacted by the installation of new sidewalk curb ramps in accordance with the applicable portions of Section 424 of the Standard Specifications and as directed by the Engineer.

Description: Remove and Reinstall Existing Trash Receptacle shall include the complete removal and storage of the existing trash receptacles and the reinstallation of trash receptacles. The existing trash receptacles shall be stored at locations and in a manner approved by the Engineer. Any damage to the existing trash receptacles by the Contractor shall be restored or replaced at his/her own expense with new material of the same kind.

Basis of Payment: The work to remove and reinstall the existing trash receptacles to the appropriate locations as determined by the Engineer shall be paid for at the contract unit price per EACH for REMOVE AND REINSTALL EXISTING TRASH RECEPTACLE which price shall include all necessary labor, material and equipment necessary to complete the work.