

MODEL: Typical Sections (Sheet) - 2
FILE NAME: c:\p\work\0601covarrubias\015889\0488\51-sh-SOO.dgn

80% FED 20% STATE				CONST.CODE BRIDGE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	072-0169
				0047
				URBAN
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6
70107005	PAVEMENT MARKING BLACKOUT TAPE, 5"	FOOT	2,277	2,277
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	2,013	2,013
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	3,192	3,192
70307125	TEMPORARY PAVEMENT MARKING - LINE 5" - TYPE IV TAPE	FOOT	3,192	3,192
70400100	TEMPORARY CONCRETE BARRIER	FOOT	650	650
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	625	625
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	800	800
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	800	800
* 78011025	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	800	800
* 78011035	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	800	800
X0324966	CONCRETE HEALER SEALER	SQ YD	1,265	1,265

*= SPECIALTY ITEM

	USER NAME = Gerardo.Covarrubias	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					6558	[(Z-D-SB)BR]BJR,BP	PEORIA	22	4
		CHECKED -	REVISED -					CONTRACT NO. 68J51				
	PLOT DATE = 12/3/2025	DATE -	REVISED -		SCALE:	SHEET 2	OF 3	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	

MODEL: Schedule (Sheet) - 1
FILE NAME: c:\p\work\dwg\dr\covarrubias\g1015889\0468\051-aht-schedule.dgn

SCHEDULE										
LOCATION					STONE RIPRAP, CLASS B3	FILTER FABRIC	CURB REMOVAL	CONCRETE CURB, TYPE B	GRADING AND SHAPING DITCHES	INLETS TO BE ADJUSTED
					28100125	28200200	44000300	60600605	21400100	60260100
IL 8				LT/RT	SQ YD	SQ YD	FOOT	FOOT	FOOT	EACH
STA	388+01	TO	388+21	RT	100					
STA	388+30	TO	388+35	RT			5	5		
STA	390+97	TO	391+04	RT			6.5	6.5		
STA	392+05	TO	392+70	LT	72.2	72.2				
STA	392+76	TO	392+81	LT			5	5		
STA	401+00			RT						1
STA	400+85	TO	401+25	RT					40	
TOTALS					172	72	17	17	40	1

SHORT TERM PAVEMENT MARKING									
LOCATION					PAVEMENT MARKING BLACKOUT TAPE, 5"		TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	SHORT TERM PAVEMENT MARKING REMOVAL	1
					70107005		70307120	70300150	
STAGE 1					SOLID	DOUBLE	SOLID	SOLID	
BLACKOUT TAPE									
STA.	TO	STA.	SIDE		FOOT	FOOT	FOOT	SQ FT	
390+98	TO	393+28	CENTER			460		192	
392+63	TO	399+33	LT		670			279	
398+68	TO	401+06	CENTER			476		198	
TEMPORARY PAVEMENT MARKING									
391+08	TO	400+46	RT/LT				939	313	
392+63	TO	399+32	LT				669	223	
STAGE 2									
BLACKOUT TAPE									
392+63	TO	399+34	RT		671			279	
TEMPORARY PAVEMENT MARKING									
391+64	TO	400+78	RT/LT				914	305	
392+63	TO	399+34	RT				671	224	
TOTALS					2277		3192	2013	

TEMPORARY CONCRETE BARRIER SCHEDULE						
LOCATION				TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	
				70400100	70400200	
STA.	TO	STA.	LT/RT	FOOT	FOOT	
STAGE 1						
392+74	TO	399+24	LT/RT	650		
STAGE 2						
392+86	TO	399+11	LT/RT		625	
TOTAL				650	625	

CONSTRUCTON LAYOUT	
Z0013798	
LOCATION	EACH
JOBSITE	1
TOTALS	1

TEMPORARY RUMBLE STRIPS	
70106700	
LOCATION	EACH
JOB SITE	6
TOTALS	6

RAILROAD PROTECTIVE LIABILITY INSURANCE	
Z0048665	
LOCATION	L SUM
JOB SITE	1
TOTALS	1

TEMPORARY IMPACT ATTENUATOR SCHEDULE				
LOCATION			IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE)), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3
STATION	OFFSET (FT)	LT/RT	70600250	70600350
STAGE 1			EACH	EACH
392+74	4.33	RT	1	
399+24	4.33	RT	1	
STAGE 2				
392+86	4.29	LT		1
399+11	4.29	LT		1
TOTAL			2	2

PAVEMENT MAKING								
LOCATION					MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	GROOVING FOR RECESSED PAVEMENT MARKING 5"	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	GROOVING FOR RECESSED PAVEMENT MARKING 7"
					78009004	78011025	78009006	78011035
					DOUBLE YELLOW	FT	WHITE	FT
IL 8					FT		FT	
STA	393+80	TO	397+80	LT			400	400
STA	394+00	TO	398+00	RT			400	400
STA	39400	TO	39800	CENTER	800	800		
TOTALS					800	800	800	800

MOBILIZATION	
67100100	
LOCATION	L SUM
JOBSITE	1
TOTALS	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	
70100405	
LOCATION	EACH
JOBSITE	1
TOTALS	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	
70100450	
LOCATION	L SUM
JOBSITE	1
TOTALS	1

TEMPORARY BRIDGE TRAFFIC SIGNALS	
70106500	
LOCATION	EACH
JOBSITE	1
TOTALS	1

	USER NAME = Gerardo.Covarrubias	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
	PLOT DATE = 12/3/2025	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6658	[(Z-D-SB)BR]BJR,BP	PEORIA	22	6
			CONTRACT NO. 68J51	
			ILLINOIS FED. AID PROJECT	