

MODEL: SQ02 [Sheet]
FILE NAME: c:\p\work\hrtz\hrtz\id0652852\0774435-sheets-SQ0.dgn

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				URBAN 90% FEDERAL 10% STATE I-57 0004	URBAN 80% FEDERAL 20% STATE IL 16 0004	URBAN 90% FEDERAL 10% STATE I-57 0010
CODE NO	ITEM	UNIT				
4200401	PORTLAND CEMENT CONCRETE PAVEMENT 9' (JOINTED)	SQ YD	25527	3267	22260	
4200521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	4814	4814		
4200540	PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	3923	2855	1068	
42001300	PROTECTIVE COAT	SQ YD	8539	4814	3725	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	59799		59799	
42400800	DETECTABLE WARNINGS	SQ FT	154 .5		154 .5	
44000100	PAVEMENT REMOVAL	SQ YD	52737	32156	20581	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	49975	24592	25383	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1760			1760
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	25		25	
44004000	PAVED DITCH REMOVAL	FOOT	417	417		
44004250	PAVED SHOULDER REMOVAL	SQ YD	70498	55509	14989	
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	188	188		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				URBAN 90% FEDERAL 10% STATE I-57 0004	URBAN 80% FEDERAL 20% STATE IL 16 0004	URBAN 90% FEDERAL 10% STATE I-57 0010
CODE NO	ITEM	UNIT				
44200612	CLASS A PATCHES, TYPE III, 13 INCH	SQ YD	22	22		
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	100	100		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	437	333	104	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	645		645	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	479		479	
44213000	PATCHING REINFORCEMENT	SQ YD	210	210		
44213200	SAW CUTS	FOOT	2164	2164		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	6003	4738	1265	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	902	568	334	
48203013	HOT-MIX ASPHALT SHOULDERS, 4"	SQ YD	496		496	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	10567	7705	2862	
48203061	HOT-MIX ASPHALT SHOULDERS, 16"	SQ YD	11846	11846		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	7349	5514	1835	
48300100	PORTLAND CEMENT CONCRETE SHOULDERS 6"	SQ YD	119	30	89	

* SPECIALTY ITEM

⚠️ REVISED 2-6-2026

REV - MS

	USER NAME = kaleb.hirtzel	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F A I RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
		DRAWN -	REVISED -					57	(15-22HB-4)BR (15-22)R	COLES	1086	5
		CHECKED -	REVISED -					CONTRACT NO. 74435				
	PLOT DATE = 7/16/2025	DATE -	REVISED -		SCALE:	SHEET 3	OF 15 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

MODEL: SCHEDULES OF QUANTITIES-23 [Sheet]
FILE NAME: c:\p\p\work\hrtz\kld\052852\0774435-sheets-Schedules.dgn

RESURFACING SCHEDULE STAGE 2			HOT-MIX ASPHALT SURFACE REMOVAL, 1-1/2"	HOT-MIX SURFRFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	LONGITUDINAL JOINT SEALANT	BITUMINOUS MATERIALS (TACK COAT)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL19.0, N90	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N90	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, SMA, 12.5, MIX "E", N80	MATERIAL TRANSFER DEVICE	HOT-MIX ASPHALT SHOULDERS	AGGREGATE WEDGE SHOULDERS, TYPE B
STATIONING		LENGTH													
FROM	TO	(FEET)													
NB I-57															
760+60.00	762+00.00	140.00	-	-	591.1	140.0	252.0	-	62.7	-	-	48.5	111.3	61.0	8.0
762+00.00	767+50.00	550.00	-	2322.2	-	550.0	990.0	-	246.4	-	-	190.7	437.1	239.6	31.3
767+50.00	778+17.86	1067.86	-	4508.7	-	1727.9	1922.1	-	478.4	-	-	370.2	848.6	132.9	30.4
778+17.86	778+48.30	30.44	-	94.7	-	30.4	54.8	-	13.6	-	-	10.6	24.2	4.5	0.9
778+48.30	779+28.30	80.00	-	213.3	-	80.0	192.0	-	43.7	-	-	27.7	71.5	-	-
779+28.30	781+35.00	206.70	-	551.2	-	206.7	25.6	227.8	92.6	-	-	71.7	164.3	-	-
781+35.00	782+43.00	108.00	-	-	-	-	-	-	-	-	-	-	-	-	-
782+43.00	784+83.94	240.94	-	-	-	-	-	-	-	-	-	-	-	-	-
784+83.94	785+05.94	22.00	-	-	-	-	-	-	-	-	-	-	-	-	-
785+05.94	787+24.37	218.43	-	-	-	-	-	-	-	-	-	-	-	-	-
787+24.37	787+39.37	15.00	-	-	-	-	-	-	-	-	-	-	-	-	-
787+39.37	787+54.37	15.00	-	-	-	-	-	-	-	-	-	-	-	-	-
787+54.37	787+69.37	15.00	-	-	-	-	-	-	-	-	-	-	-	-	-
787+69.37	789+61.37	192.00	-	-	-	-	-	-	-	-	-	-	-	-	-
789+61.37	789+76.37	15.00	-	-	-	-	-	-	-	-	-	-	-	-	-
789+76.37	789+91.37	15.00	-	-	-	-	-	-	-	-	-	-	-	-	-
789+91.37	790+06.37	15.00	-	-	-	-	-	-	-	-	-	-	-	-	-
790+06.37	790+87.24	80.87	-	-	-	-	-	-	-	-	-	-	-	-	-
790+87.24	791+22.00	34.76	-	-	-	-	-	-	-	-	-	-	-	-	-
791+22.00	794+22.30	300.30	-	-	-	-	-	-	-	-	-	-	-	-	-
794+22.30	795+68.00	145.70	-	-	-	-	-	-	-	-	-	-	-	-	-
795+68.00	798+52.77	284.77	-	759.4	-	284.8	31.5	294.3	127.6	-	-	98.7	226.3	-	-
798+52.77	798+90.40	37.63	-	100.3	-	37.6	90.3	-	19.7	-	-	13.0	32.7	-	-
798+90.40	800+74.10	183.70	-	571.5	-	183.7	330.7	-	82.3	-	-	63.7	146.0	-	-
800+74.10	801+36.00	61.90	261.4	-	-	1337.8	111.4	-	11.9	-	-	21.5	33.3	-	-
801+36.00	801+80.50	44.50	-	138.4	-	44.5	80.1	-	26.6	-	-	15.4	42.0	-	-
801+80.50	803+87.70	207.20	-	690.7	-	207.2	373.0	-	123.8	-	-	71.8	195.6	46.4	5.9
803+87.70	807+17.00	329.30	-	1097.7	-	329.3	790.3	141.1	147.5	-	-	114.2	261.7	61.5	9.4
807+17.00	809+53.00	236.00	-	-	-	-	-	-	-	-	-	-	-	-	-
809+53.00	810+53.60	100.60	-	335.3	-	100.6	241.4	34.3	45.1	-	-	34.9	79.9	18.8	102.1
810+53.60	811+23.47	69.87	-	232.9	-	69.9	125.8	-	31.3	-	-	24.2	55.5	34.7	2.0
811+23.47	811+45.47	22.00	-	73.3	-	22.0	39.6	-	9.9	-	-	7.6	17.5	20.6	-
811+45.47	812+39.36	93.89	-	313.0	-	93.9	169.0	-	42.1	-	-	32.5	74.6	14.8	-
812+39.36	813+50.00	110.64	-	-	515.0	110.6	199.2	-	-	-	-	38.4	38.4	-	-

 REVISED SHEET 2-6-2026

	USER NAME = kaleb.hirtzel	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					57	(15-22HB-4)BR (15-22)R	COLES	1086	56
		CHECKED -	REVISED -					CONTRACT NO. 74435				
	PLOT DATE = 8/19/2024	DATE -	REVISED -		SCALE:	SHEET 24	OF 50 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

MODEL: SCHEDULES OF QUANTITIES-24 [Sheet]
FILE NAME: c:\pdx_work\pdx\hrtzaki\dd562852\D774435-sheets-Schedules.dgn

RESURFACING SCHEDULE STAGE 2			HOT-MIX ASPHALT SURFACE REMOVAL, 1-1/2"	HOT-MIX SUFRFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	LONGITUDINAL JOINT SEALANT	BITUMINOUS MATERIALS (TACK COAT)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL19.0, N90	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N90	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, SMA, 12.5, MIX "E", N80	MATERIAL TRANSFER DEVICE	HOT-MIX ASPHALT SHOULDERS	AGGREGATE WEDGE SHOULDERS, TYPE B
STATIONING		LENGTH	SQ YD	SQ YD	SQ YD	FOOT	POUND	TON	TON	TON	TON	TON	TON	TON	TON
FROM	TO	(FEET)													
813+50.00	813+79.64	29.64	-	-	138.3	29.6	53.4	-	13.3	-	-	10.3	23.6	-	-
813+79.64	815+88.05	208.41	-	-	-	208.4	-	-	-	-	-	-	-	-	-
815+88.05	817+28.05	140.00	-	-	653.3	140.0	252.0	-	62.7	-	-	48.5	111.3	97.6	4.0
817+28.05	820+04.40	276.35	1228.2	-	-	276.3	497.4	-	123.8	-	-	95.8	219.6	220.1	7.9
820+04.40	820+24.40	20.00	88.9	-	-	20.0	36.0	-	9.0	-	-	6.9	15.9	17.9	1.1
820+24.40	833+60.50	1336.10	5641.3	-	-	1336.1	2405.0	-	598.6	-	-	463.2	1061.8	1163.9	76.1
833+60.50	835+80.79	220.29	979.1	-	-	220.3	396.5	-	98.7	-	-	76.4	175.1	301.6	12.5
835+80.79	836+02.79	22.00	97.8	-	-	22.0	39.6	-	9.9	-	-	7.6	17.5	32.9	0.6
836+02.79	838+65.29	262.50	1166.7	-	-	262.5	472.5	-	117.6	-	-	91.0	208.6	424.7	7.5
838+65.29	839+12.00	46.71	207.6	-	-	46.7	84.1	-	20.9	-	-	16.2	37.1	81.4	2.7
839+12.00	839+29.00	17.00	71.8	-	-	17.0	30.6	-	7.6	-	-	5.9	13.5	22.2	0.5
839+29.00	839+62.00	33.00	-	-	139.3	33.0	59.4	-	14.8	-	-	17.9	32.7	46.0	0.9
839+62.00	840+69.00	107.00	-	-	451.8	107.0	192.6	-	47.9	-	-	80.4	128.3	158.5	6.1
NB I-57 TOTALS:			9742.7	12002.8	2488.9	8275.9	10537.9	697.5	2729.8	0.0	0.0	2175.3	4905.1	4104.0	309.8
EX RAMP B															
74+30.50	78+16.70	386.20	1609.0		-	-	1086.1	-	270.3	-	180.2	-	-	120.2	11.0
78+16.70	79+57.00	140.30	-		467.7	-	315.7	-	78.6	-	52.4	-	-	61.1	8.0
EX RAMP B TOTALS:			1609.0	0.0	467.7	0.0	1401.8	0.0	348.9	0.0	232.6	0.0	0.0	181.3	19.0
EX RAMP H															
797+15.00	798+55.87	140.87	-		469.6	-	317.0	-	78.9	-	52.6	-	-	61.4	8.0
798+55.87	800+53.00	197.13	700.3		-	-	472.7	-	117.6	-	78.4	-	-	61.3	5.6
EX RAMP H TOTALS:			700.3	0.0	469.6	0.0	789.6	0.0	196.5	0.0	131.0	0.0	0.0	122.7	13.6
I-57 MEDIAN TURNAROUND															
839+03.00	839+51.00	48.00	90.2		-		60.9	15.1	-	10.1	-	-	-	-	1.8
I-57 MEDIAN TURNAROUND TOTALS:			90.2	0.0	0.0	0.0	60.9	15.1	0.0	10.1	0.0	0.0	0.0	0.0	1.8
EB IL 16															
114+91.00	115+64.50	73.50	-	-	-	-	-	-	-	-	-	-	-	-	11.6
EB IL 16 TOTALS:			0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	11.6
WB IL 16															
114+86.50	115+62.00	75.50	-	-	-	-	-	-	-	-	-	-	-	-	11.9
WB IL 16 TOTALS:			0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	11.9
STAGE 2 TOTALS:			12142.1	12002.8	3426.1	8275.9	12790.1	712.6	3275.2	10.1	363.6	2175.3	4905.1	3505.2	367.8

 REVISED SHEET 2-6-2026

	USER NAME = kaleb.hirtzel		DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES						F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			DRAWN -	REVISED -								57	(15-22HB-4)BR (15-22)R	COLES	1086	57
			CHECKED -	REVISED -								CONTRACT NO. 74435				
	PLOT DATE = 8/19/2024		DATE -	REVISED -		SCALE:	SHEET 25	OF 50	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				

MODEL: SCHEDULES OF QUANTITIES-28 [Sheet]
FILE NAME: c:\pdx_work\pdx\hrtzaki\dd852852\DT74435-sheets-Schedules.dgn

HMA SHOULDERS 8" SCHEDULE STAGE 3B			HOT-MIX ASPHALT SHOULDERS, 8"	SUBBASE GRANULAR MATERIAL, TYPE C	AGGREGATE SHOULDERS, TYPE B 6"
STATIONING		LENGTH			
FROM	TO	FEET	SQ YD	TON	SQ YD
EB IL 16					
95+96.0	99+64.0	368.0	408.9	-	81.8
99+64.0	102+06.0	242.0	-	-	53.8
127+76.0	128+62.0	86.0	95.5	-	19.1
128+62.0	128+00.0	STA. EQU.	-	-	-
128+00.0	135+93.5	793.5	881.7	-	176.3
EB IL 16 TOTALS:			1386.1	0.0	331.0
PR RAMP C					
4006+60.0	4013+99.9	739.9	822.1	99.9	328.8
4013+99.9	4016+39.9	240.0	266.7	32.4	106.7
4016+39.9	4017+41.0	101.1	112.3	13.7	44.9
4017+41.0	4018+26.5	85.5	-	-	-
4018+26.5	4018+55.0	28.5	-	-	-
4018+55.0	4019+95.3	140.3	-	-	-
4019+95.3	4020+08.9	13.6	-	-	-
PR RAMP C TOTALS:			1201.1	146.0	480.4
PR RAMP D					
5000+69.5	5002+28.0	158.5	-	-	-
5002+28.0	5002+38.3	10.3	-	-	-
5002+38.3	5004+44.5	206.2	229.1	27.8	91.6
5004+44.5	5006+74.5	230.0	255.6	31.1	102.2
5006+74.5	5009+18.7	244.2	271.3	33.0	108.5
5009+18.7	5011+75.9	257.2	285.8	34.7	114.3
PR RAMP D TOTALS:			1041.8	126.6	416.7
STAGE 3B TOTALS:			3629.0	272.6	1228.1

HMA SHOULDERS 8" SCHEDULE STAGE 3E			HOT-MIX ASPHALT SHOULDERS, 8"	SUBBASE GRANULAR MATERIAL, TYPE C	AGGREGATE SHOULDERS, TYPE B 6"
STATIONING		LENGTH			
FROM	TO	FEET	SQ YD	TON	SQ YD
WB IL 16					
94+46.5	102+63.4	816.9	907.7	-	181.5
WB IL 16 TOTALS:			907.7	0.0	181.5
PR RAMP A					
2006+59.7	2013+88.7	729.0	1053.0	128.0	162.0
2013+88.7	2014+16.7	28.0	31.1	3.8	12.4
2014+16.7	2016+56.7	240.0	266.7	32.4	106.7
2016+56.7	2017+50.0	93.3	103.7	12.6	41.5
PR RAMP A TOTALS:			1454.4	176.8	322.6
STAGE 3E TOTALS:			2362.1	176.8	504.1

HMA SHOULDERS 8" SCHEDULE STAGE 3F			HOT-MIX ASPHALT SHOULDERS, 8"	SUBBASE GRANULAR MATERIAL, TYPE C	AGGREGATE SHOULDERS, TYPE B 6"
STATIONING		LENGTH			
FROM	TO	FEET	SQ YD	TON	SQ YD
WB IL 16					
128+33.3	128+62.0	28.7	31.9	-	25.9
128+62.0	128+00.0	STA. EQU.	-	-	-
128+00.0	132+82.9	482.9	536.6	-	107.3
WB IL 16 TOTALS:			568.4	0.0	133.2
PR RAMP B					
3001+86.5	3002+88.0	101.5	112.8	13.7	45.1
3002+88.0	3004+37.2	149.2	165.8	20.1	66.3
3004+37.2	3006+77.2	240.0	266.7	32.4	106.7
3006+77.2	3007+33.0	55.8	62.0	7.5	24.8
3007+33.0	3007+45.0	12.0	16.0	1.9	5.3
3007+45.0	3007+80.0	35.0	54.4	6.6	15.6
3007+80.0	3008+05.0	25.0	37.5	4.6	11.1
3008+05.0	3011+97.7	392.7	567.2	68.9	174.1
PR RAMP B TOTALS:			1282.4	155.8	449.0
STAGE 3F TOTALS:			1850.8	155.8	582.1

HMA SHOULDERS 16" SCHEDULE STAGE 1			SUBBASE GRANULAR MATERIAL, TYPE C	HOT-MIX ASPHALT SHOULDERS, 16"	AGGREGATE SHOULDERS, TYPE B 6"
STATIONING		LENGTH			
FROM	TO	FEET	TON	SQ YD	SQ YD
SB I-57					
760+60.00	762+00.00	140.0	-	-	-
762+00.00	764+00.00	200.0	-	-	-
764+00.00	779+35.90	1535.9	-	-	-
779+35.90	779+45.89	10.0	7.9	17.8	2.2
779+45.89	781+59.85	214.0	169.9	380.4	95.1
781+59.85	782+67.06	107.2	-	190.6	47.6
782+67.06	786+57.46	390.4	-	694.0	173.5
786+57.46	787+26.44	69.0	-	145.6	-
787+26.44	787+41.44	15.0	-	-	-
787+41.44	787+71.44	30.0	-	-	-
787+71.44	789+63.44	192.0	-	-	-
789+63.44	789+93.44	30.0	-	-	-
789+93.44	790+08.44	15.0	-	-	-
790+08.44	791+90.98	182.5	-	446.2	
791+90.98	792+15.98	25.0	-	63.9	
792+15.98	792+50.98	35.0	-	93.3	
792+50.98	792+62.99	12.0	-	29.4	
792+62.99	793+98.00	135.0	-	240.0	60.0
793+98.00	795+57.47	159.5	-	283.5	70.9
795+57.47	799+15.14	357.7	284.3	635.9	159.0
799+15.14	799+41.48	26.3	20.9	46.8	5.9
799+41.48	801+75.29	233.8	-	155.9	52.0
801+75.29	801+81.25	6.0	-	-	-
801+81.25	807+06.00	524.8	-	-	-
807+06.00	809+42.00	236.0	-	419.6	-
809+42.00	810+00.00	58.0	-	-	-
810+00.00	812+39.46	239.5	-	-	-
812+39.46	813+79.46	140.0	-	-	-
813+79.46	815+87.97	208.5	-	-	-
815+87.97	817+27.97	140.0	-	-	-
817+27.97	820+20.00	292.0	-	-	-
820+20.00	839+03.00	1883.0	-	-	-
839+03.00	839+29.00	26.0	-	-	-
839+29.00	839+40.00	11.0	-	-	-
839+40.00	839+51.00	11.0	-	-	-
839+51.00	840+69.00	118.0	-	-	-
SB I-57 TOTALS:			483.0	3842.8	666.1

HMA SHOULDERS 16" SCHEDULE STAGE 1			SUBBASE GRANULAR MATERIAL, TYPE C	HOT-MIX ASPHALT SHOULDERS, 16"	AGGREGATE SHOULDERS, TYPE B 6"
STATIONING		LENGTH			
FROM	TO	FEET	TON	SQ YD	SQ YD
PR RAMP A					
2000+00.00	2002+66.77	266.8	-	276.8	-
2002+66.77	2002+99.52	32.8	-	-	-
2002+99.52	2003+99.38	99.9	-	-	-
2003+99.38	2006+59.71	260.3	121.4	384.2	-
PR RAMP A TOTALS:			121.4	661.0	0.0
PR RAMP D					
5011+75.93	5015+06.00	330.1	98.4	311.3	-
5015+06.00	5016+06.00	100.0	-	-	-
5016+06.00	5021+20.00	514.0	-	-	-
5021+20.00	5024+55.80	335.8	-	263.2	74.6
PR RAMP D TOTALS:			98.4	574.5	74.6
STAGE 1 TOTALS:			702.8	5078.3	740.8

 REVISED SHEET 2-6-2026

	USER NAME	= kaleb.hirtzel	DESIGNED	-	REVISED	-	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			DRAWN	-	REVISED	-					57	(15-22HB-4)BR (15-22)R	COLES	1086	61
			CHECKED	-	REVISED	-					CONTRACT NO. 74435				
	PLOT DATE	= 9/26/2025	DATE	-	REVISED	-		SCALE:	SHEET 29	OF 50 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

MODEL: SCHEDULES OF QUANTITIES-29 [Sheet]
FILE NAME: c:\pdx_work\hrt\hrtzaki\052852\074435-sheets-Schedules.dgn

HMA SHOULDERS 16" SCHEDULE STAGE 2			SUBBASE GRANULAR MATERIAL, TYPE C	HOT-MIX ASPHALT SHOULDERS, 16"	AGGREGATE SHOULDERS, TYPE B 6"			
STATIONING		LENGTH						
FROM	TO	FEET				TON	SQ YD	SQ YD
NB I-57								
760+60.00	762+00.00	-	-	-	-			
762+00.00	767+50.00	-	-	-	-			
767+50.00	778+17.86	-	-	-	-			
778+17.86	778+48.30	30.4	-	33.8	-			
778+48.30	779+28.30	80.0	-	142.2	35.6			
779+28.30	781+35.00	206.7	164.1	367.5	91.9			
781+35.00	782+43.00	108.0	-	192.0	48.0			
782+43.00	784+83.94	240.9	-	428.3	107.1			
784+83.94	784+95.94	12.0	-	29.3	-			
784+95.94	785+30.94	35.0	-	93.3	-			
785+30.94	785+55.94	25.0	-	63.9	-			
785+55.94	787+24.37	168.4	-	355.6	-			
787+24.37	787+39.37	-	-	-	-			
787+39.37	787+54.37	-	-	-	-			
787+54.37	787+71.37	-	-	-	-			
787+71.37	789+61.37	-	-	-	-			
789+61.37	789+76.37	-	-	-	-			
789+76.37	789+91.37	-	-	-	-			
789+91.37	790+06.37	-	-	-	-			
790+06.37	790+37.24	30.9	-	65.2	-			
790+37.24	790+62.24	25.0	-	52.8	-			
790+62.24	790+87.24	25.0	-	52.8	-			
790+87.24	791+09.24	22.0	-	39.1	6.1			
791+09.24	794+22.30	313.1	-	556.6	139.1			
794+22.30	795+68.00	145.7	-	259.0	64.8			
795+68.00	798+52.77	284.8	226.1	506.3	63.3			
798+52.77	798+90.40	37.6	-	66.9	8.4			
798+90.40	800+74.10	183.7	-	122.5	40.8			
800+74.10	801+36.00	61.9	-	41.3	13.8			
801+36.00	801+80.50	44.5	-	29.7	9.9			

HMA SHOULDERS 16" SCHEDULE STAGE 3					HOT-MIX ASPHALT SHOULDERS, 16"	AGGREGATE SHOULDERS, TYPE B 6"
ROUTE	STATIONING		LENGTH	SIDE		
	FROM	TO	FEET			
					SQ YD	SQ YD
STAGE 3B						
NB I-57	774+10.00	778+17.80	407.8	RT	453.1	90.6
SB I-57	776+82.30	779+35.90	253.6	LT	281.8	56.4
STAGE 3B TOTALS:					734.9	147.0
STAGE 3E						
SB I-57	799+15.10	799+41.50	26.4	LT	-	5.9
SB I-57	799+41.50	803+39.80	398.3	LT	442.6	88.5
STAGE 3E TOTALS:					442.6	94.4

HMA SHOULDERS 16" SCHEDULE STAGE 2			SUBBASE GRANULAR MATERIAL, TYPE C	HOT-MIX ASPHALT SHOULDERS, 16"	AGGREGATE SHOULDERS, TYPE B 6"
STATION		LENGTH			
FROM	TO	FEET	TON	SQ YD	SQ YD
801+80.50	803+87.70	-	-	-	-
803+87.70	807+17.00	-	-	-	-
807+17.00	809+53.00	236.0	-	419.6	52.4
809+53.00	810+53.60	-	-	-	-
810+53.60	812+39.64	-	-	-	-
812+39.64	813+50.00	-	-	-	-
813+50.00	813+79.64	-	-	-	-
813+79.64	815+88.05	-	-	-	-
815+88.05	817+28.05	-	-	-	-
817+28.05	820+04.40	-	-	-	-
820+04.40	820+24.40	-	-	-	-
820+24.40	833+60.50	-	-	-	-
833+60.50	835+80.79	-	-	-	-
835+80.79	836+02.79	-	-	-	-
836+02.79	838+65.29	-	-	-	-
838+65.29	839+12.00	-	-	-	-
839+12.00	839+29.00	-	-	-	-
839+29.00	839+62.00	-	-	-	-
839+62.00	840+69.00	-	-	-	-
NB I-57 TOTALS:			390.2	3917.5	681.1
PR RAMP B					
3011+97.74	3015+22.34	324.6	94.5	299.0	-
3015+22.34	3016+40.00	117.7	-	-	-
3016+40.00	3024+72.21	832.2	-	576.8	-
PR RAMP B TOTALS:			94.5	875.9	0.0
PR RAMP C					
4000+00.00	4003+00.00	300.0	-	210.0	66.7
4003+00.00	4004+00.00	100.0	-	-	-
4004+00.00	4006+60.00	260.0	121.3	383.9	-
PR RAMP C TOTALS:			121.3	593.9	66.7
STAGE 2 TOTALS:			606.0	5387.3	747.7

HMA SHOULDERS 16" SCHEDULE STAGE 3					HOT-MIX ASPHALT SHOULDERS, 16"	AGGREGATE SHOULDERS, TYPE B 6"
ROUTE	STATIONING		LENGTH	SIDE		
	FROM	TO	FEET			
					SQ YD	SQ YD
STAGE 3F						
NB I-57	798+52.80	798+90.40	37.6	RT	-	8.4
NB I-57	798+90.40	800+73.20	182.8	RT	203.1	40.6
STAGE 3F TOTALS:					203.1	49.0
STAGE 3 TOTALS:					1380.6	290.4

HMA SHOULDER REMOVAL & REPLACEMENT PRE-STAGE				PAVED SHOULDER REMOVAL	HOT-MIX ASPHALT BASE COURSE, 9"	HOT-MIX ASPHALT BASE COURSE, 12"
STATIONING		LENGTH	SIDE			
FROM	TO	FEET				
NB I-57						
735+75.00	772+19.50	3644.5	RT	2834.6	-	2834.6
774+55.50	786+50.00	1194.5	RT	929.1	-	929.1
783+40.00	787+47.50	407.5	LT	181.1	-	181.1
789+83.00	792+83.00	300.0	LT	133.3	-	133.3
791+88.00	799+79.00	791.0	RT	615.2	-	615.2
804+93.50	807+36.00	242.5	RT	188.6	-	188.6
809+36.00	813+80.00	444.0	RT	345.3	-	345.3
815+88.50	841+64.43	2575.9	RT	2003.5	-	2003.5
841+64.43	813+19.43	STA. EQUATION		-	-	-
813+19.43	844+00.00	3080.6	RT	2396.0	-	2396.0
NB I-57 TOTALS:				9626.8	0.0	9626.8
SB I-57						
747+50.00	769+78.50	2228.5	LT	1733.3	1733.3	-
776+48.00	779+36.00	288.0	LT	224.0	224.0	-
799+41.50	801+66.50	225.0	LT	175.0	175.0	-
804+55.00	807+22.50	267.5	LT	208.1	208.1	-
809+23.00	813+79.50	456.5	LT	355.1	355.1	-
815+88.50	841+64.43	2575.9	LT	2003.5	2003.5	-
841+64.43	813+19.43	STA. EQUATION		-	-	-
813+19.43	853+90.00	4070.6	LT	3166.0	3166.0	-
SB I-57 TOTALS:				7864.9	7864.9	0.0
EX WB IL 16						
105+39.00	111+50.00	611.0	LT	543.1	-	543.1
111+50.00	111+97.00	47.0	LT	23.5	-	23.5
EX WB IL 16 TOTALS:				566.6	0.0	566.6

HMA SHOULDER REMOVAL & REPLACEMENT PRE-STAGE				PAVED SHOULDER REMOVAL	HOT-MIX ASPHALT BASE COURSE, 9"	HOT-MIX ASPHALT BASE COURSE, 12"
STATIONING		LENGTH	SIDE			
FROM	TO	FEET			SQ YD	SQ YD
EX RAMP F						
17+50.50	18+85.00	134.5	RT	119.6	-	119.6
18+85.00	22+29.50	344.5	RT	382.8	-	382.8
19+50.50	20+63.00	112.5	LT	50.0	-	50.0
20+63.00	20+80.50	17.5	LT	3.9	-	3.9
EX RAMP F TOTALS:				556.2	0.0	556.2
EX RAMP H						
787+83.50	792+17.50	434.0	RT	482.2	-	482.2
789+78.00	789+95.00	17.0	LT	3.8	-	3.8
789+95.00	791+17.50	122.5	LT	54.4	-	54.4
EX RAMP H TOTALS:				540.4	0.0	540.4
EX RAMP B						
85+21.00	89+29.00	408.0	RT	453.3	-	453.3
86+81.00	88+04.00	123.0	LT	54.7	-	54.7
88+04.00	88+21.00	17.0	LT	3.8	-	3.8
EX RAMP B TOTALS:				511.8	0.0	511.8
EX RAMP D						
44+09.00	48+18.00	409.0	RT	454.4	-	454.4
45+76.00	45+95.50	19.5	LT	4.3	-	4.3
45+95.50	47+18.00	122.5	LT	54.4	-	54.4
EX RAMP D TOTALS:				513.2	0.0	513.2
PRE-STAGE TOTALS:				20179.9	7864.9	12315.0

 REVISED SHEET 2-6-2026

	USER NAME = kaleb.hirtzel		DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			DRAWN -	REVISED -						57	(15-22HB-4)BR (15-22)R	COLES	1086	62
			CHECKED -	REVISED -		CONTRACT NO. 74435								
	PLOT DATE = 9/26/2025		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								
SCALE:				SHEET 30 OF 50 SHEETS							STA. TO STA.			