

MODEL: SQ02 [Sheet]
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\DOT D-910257 PTB 214-047 On-Call\10257.03 I-64 Bridge Repairs\CADD\0.12\CADD Data\Sheets\0978B34-sht-SQ0.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE	CONSTR. CODE	CONSTR. CODE
				90% FED / 10% STATE	90% FED / 10% STATE	90% FED / 10% STATE	90% FED / 10% STATE
				BRIDGE	BRIDGE	BRIDGE	ROADWAY
				0059	0059	0059	0005
				S.N. 041-0087/0088	S.N. 041-0070/0071	S.N. 041-0081/0082	RURAL
44000400	GUTTER REMOVAL	FOOT	114				114
44004250	PAVED SHOULDER REMOVAL	SQ YD	377				377
48101200	AGGREGATE SHOULDERS, TYPE B	TON	29				29
48203100	HOT-MIX ASPHALT SHOULDERS	TON	510				510
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	549				549
50102400	CONCRETE REMOVAL	CU YD	154.8	76.1	42.9	35.8	
50104000	BRIDGE RAIL REMOVAL	FOOT	2201	857	768	576	
50157300	PROTECTIVE SHIELD	SQ YD	630		630		
50200100	STRUCTURE EXCAVATION	CU YD	243	243			
50300100	FLOOR DRAINS	EACH	92	56	16	20	
50300225	CONCRETE STRUCTURES	CU YD	75.7	67.2	8.5		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	169.1	92.8	38.1	38.2	
50300300	PROTECTIVE COAT	SQ YD	6501	2676	1946	1879	
50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	220.4	220.4			

1

REVISED 2-18-2026

REV - MS

design firm
no. 184001036

whks

engineers + planners + land surveyors

USER NAME = kfair	DESIGNED - LNJ	REVISED -
	DRAWN - LNJ	REVISED -
PLOT SCALE = 0.16666633 ' / in.	CHECKED - RKA	REVISED -
PLOT DATE = 12/3/2025	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
I-64 (FAI 64) DUAL BRIDGE REPAIRS

SCALE: 1"=50' SHEET 2 OF 8 SHEETS STA. TO STA.

FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	D9 BRIDGE OVERLAY 2026-1	JEFFERSON	141	5
CONTRACT NO. 78B34				
ILLINOIS FED. AID PROJECT				

MODEL: SCH-1 [Sheet]
FILE NAME: C:\SP\WHKS & CO\Jobs-Spring - Projects\DOT D-610257 PTB 214-047 On-Call\10257_03 I-64 Bridge Repairs\CADD\10_12\CADD Data\Sheets\0978B34-sh-schedule.dgn

REMOVAL SCHEDULE									
STRUCTURE	START	END		LENGTH	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	PAVED SHOULDER REMOVAL	GUTTER REMOVAL	EXCAVATING AND GRADING EXISTING SHOULDER
NUMBER	STATION	STATION	LT/RT	FOOT	SQ YD	SQ YD	SQ YD	FOOT	UNIT
041-0087 (WB)	2762+10.00	2764+08.36		198.36	18	264	96		
	BRIDGE								
	2766+23.28	2769+50.00		326.72	22	485	93		
041-0088 (EB)	2760+50.00	2763+74.14		324.14	21	486	92		
	BRIDGE								
	2765+91.64	2768+00.00		208.36	18	282	96		
041-0071 (WB)	2964+75.00	2966+55.77		180.77		316			
	BRIDGE								
	2968+47.96	2972+50.00		402.04		741			
041-0070 (EB)	2963+00.00	2967+19.02		419.02		759			
	BRIDGE								
	2969+18.47	2971+00.00		181.53		284			
041-0082 (WB)	3198+52.00	3202+68.78		416.78					
	BRIDGE								
	3204+33.27	3209+00.00		466.73		559			
041-0081 (EB)	3196+75.00	3202+82.19		607.19		664			
	BRIDGE								
	3204+48.06	3207+40.00		291.94		294			
CH 17	48+52.00	51+70.00	LT	318.00				57	3
	48+40.00	51+55.00	RT	315.00				57	3
TOTAL					79	5134	377	114	6

PAVEMENT SCHEDULE														
STRUCTURE	START	END		LENGTH	PAVEMENT CONNECTOR (PCC) FOR BRIDGE APPROACH SLAB	WELDED WIRE REINFORCEMENT	BITUMINOUS MATERIALS (TACK COAT)	HOT-MIX ASPHALT SHOULDERS	AGGREGATE SHOULDERS, TYPE B	SHOULDER RUMBLE STRIPS, 16 INCH	SUBBASE GRANULAR MATERIAL, TYPE C	PORTLAND CEMENT CONCRETE SHOULDERS 10"	CONCRETE GUTTER, TYPE A	CONCRETE GUTTER, TYPE A (SPECIAL)
NUMBER	STATION	STATION	LT/RT	FOOT	SQ YD	SQ YD	POUND	TON	TON	FOOT	TON	SQ YD	FOOT	FOOT
041-0087 (WB)	2762+10.00	2763+79.42		169.42	100	58	119	23		296				
	BRIDGE													
	2766+54.78	2769+50.00		295.22	100	62	229	42	2	546				
041-0088 (EB)	2760+50.00	2763+45.74		295.74	100	62	229	42	2	546				
	BRIDGE													
	2766+20.58	2768+00.00		179.42	100	58	127	24		316				
041-0071 (WB)	2964+75.00	2966+55.77		180.77			142	27		360				
	BRIDGE													
	2968+47.96	2972+50.00		402.04			334	63		826				
041-0070 (EB)	2963+00.00	2967+19.02		419.02			341	65		858				
	BRIDGE													
	2969+18.47	2971+00.00		181.53			128	25		312				
041-0082 (WB)	3198+52.00	3202+68.78		416.78			57	71	5					
	BRIDGE													
	3204+33.27	3209+00.00		466.73			252	47		470				
041-0081 (EB)	3196+75.00	3202+82.19		607.19			299	56		745				
	BRIDGE													
	3204+48.06	3207+40.00		291.94			133	25		334				
CH 17	48+52.00	51+70.00	LT	318.00					10		33	276	140	77
	48+40.00	51+55.00	RT	315.00					10		33	273	140	77
TOTAL					400	240	2390	510	29	5609	66	549	280	154

△ REVISED SHEET 2-18-2026

design firm
no. 184001036


engineers • planners • land surveyors

USER NAME = kfair	DESIGNED - LNJ	REVISED -
PLOT SCALE = 0.16666633" / in.	DRAWN - KNF	REVISED -
PLOT DATE = 12/3/2025	CHECKED - RKA	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
I-64 (FAI 64) DUAL BRIDGE REPAIRS			
SCALE: 1"=50'	SHEET 1	OF 3 SHEETS	STA. TO STA.

FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	D9 BRIDGE OVERLAY 2026-1	JEFFERSON	141	18
CONTRACT NO. 78B34				
ILLINOIS FED. AID PROJECT				