



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 5, 2026

SUBJECT FAP Route 347 (IL 38(Roosevelt Rd))
Project NHPP-XYPQ(496)
Section 2025-1089-RS
DuPage County
Contract No. 80B15

Item No. 064, February 27th, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents of the Special Provisions.
3. Added page 126 to the Special Provisions.
4. Revised sheets 4-5, 9, 13, and 25-28 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

WORK RESTRICTIONS	61
WORK ZONE TRAFFIC CONTROL AND PROTECTION (ILLINOIS TOLLWAY)	61
AGGREGATE SUBGRADE IMPROVEMENT (BDE).....	64
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....	67
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE)	68
COMPENSABLE DELAY COSTS (BDE)	85
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	88
FUEL COST ADJUSTMENT (BDE)	90
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	93
PAVEMENT MARKING (BDE)	94
PAVEMENT PATCHING (BDE)	95
PERFORMANCE GRADED ASPHALT BINDER (BDE)	96
PREFORMED PLASTIC PAVEMENT MARKING (BDE)	101
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)	102
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	102
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	104
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	107
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	109
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	109
SUBMISSION OF BIDDERS LIST INFORMATION (BDE).....	110
SUBMISSION OF PAYROLL RECORDS (BDE).....	110
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	111
SURVEYING SERVICES (BDE)	118
TRAINING SPECIAL PROVISIONS (BDE).....	118
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION	121
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	123
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	123
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	126



REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)



Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

IL 38 (Roosevelt Road) from the Intersection of Nicoll Way to the Intersection of Edson Avenue, Glen Ellyn and Lombard, DuPage County

- All excavation planned for ADA sidewalk improvements along both sides of IL 38 (Roosevelt Road) from the Intersection of Nicoll Way to the Intersection of Edson Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: **None**