

MODEL: Sheet
FILE NAME: I:\2025\2024\01 CDI - IDOT D9 - PTB 214-046 - WC4 - IL 14 over Fox River Slough in White County\CAD\Drawn\CA\Drawn\ID978B37-shit-S0001.dgn

COUNTY:	WHITE
ROUTE:	FAP 857 (IL 14)
FUNDING:	80% FED / 20% STATE
LOCATION:	RURAL
	BRIDGE
	0047
	S.N. 097-0032

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	8	8
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	144	144
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	214	214
40600990	TEMPORARY RAMP	SQ YD	36	36
40605022	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 9.5, MIX "D", N50	TON	115	115
42001300	PROTECTIVE COAT	SQ YD	16	16
48203100	HOT-MIX ASPHALT SHOULDERS	TON	7	7
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	260	260
50102400	CONCRETE REMOVAL	CU YD	4.5	4.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	5.6	5.6
50300300	PROTECTIVE COAT	SQ YD	16	16
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	610	610
50800515	BAR SPLICERS	EACH	16	16
52000110	PREFORMED JOINT STRIP SEAL	FOOT	34	34
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	15	15



* SPECIALTY ITEM

1 REVISED 2-6-2026

REV - MS

 KUHN & TRELLO CONSULTING ENGINEERS A Limited Liability Company 109 N. 21st Street, 2nd Floor Springfield, IL 62761 Phone: 217-679-0044 Professional Design Firm No. 184-006516	USER NAME = Ismailey	DESIGNED - JRS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - LJS	REVISED -					857	D9 BRIDGE OVERLAY 2026-3	WHITE	29	4
	PLOT DATE = 11/20/2025	CHECKED - JRS	REVISED -		SCALE:			SHEET 1 OF 3 SHEETS STA. TO STA.				
		DATE = 6/23/25	REVISED -					ILLINOIS FED. AID PROJECT				