



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 13, 2026

SUBJECT FAP Route 870 (IL 53/Columbine Ave)
Project NHPP-8X19(066)
Section 2025-2006-RS
DuPage County
Contract No. 80B25

Item No. 140, February 27th, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised pages i-ii of the Table of Contents of the Special Provisions.
3. Revised pages 3-6 of the Special Provisions.
4. Revised sheets 2, 4-5, 7-10, 10A, 13, and 28-29 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS (D1)	2
PUBLIC CONVENIENCE AND SAFETY (D1)	2
CONTRACTOR COOPERATION	2
STATUS OF UTILITIES (D-1)	3
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	5
COMPLETION DATE PLUS WORKING DAYS (D1)	6
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1)	7
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1).....	14
FRICTION AGGREGATE (D1).....	16
GRADING AND SHAPING SHOULDERS (D1)	19
MINERALIZED CARBON DIOXIDE CONCRETE (D-1)	19
CONSTRUCTION LAYOUT SPECIAL FOR RESURFACING WITH ADA AND STAND ALONE ADA (D1)20	
ADJUSTMENTS AND RECONSTRUCTIONS (D1).....	22
CURB OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (D1).....	22
CLEANING EXISTING DRAINAGE STRUCTURES (D1)	24
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (D1).....	25
ENGINEER’S FIELD OFFICE TYPE A (D1)	26
TRAFFIC CONTROL PLAN (D1)	27
TEMPORARY INFORMATION SIGNING	28
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)	29
TRAFFIC SIGNAL GENERAL REQUIREMENTS.....	30
ACCESSIBLE PEDESTRIAN SIGNALS.....	47
HANDHOLES.....	51
REBUILD EXISTING HANDHOLE.....	53
DETECTOR LOOP REPLACEMENT AND/OR INSTALLATION (ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS)	54
RADAR VEHICLE DETECTION SYSTEM	56
RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE)	58
UP MAINTENANCE CONSENT LETTER.....	59
UP RIGHT OF ENTRY INSTRUCTIONS TO THE CONTRACTOR	65
UP RIGHT OF ENTRY APPLICATION.....	66

UP EXHIBIT D OVERPASS/UNDERPASS COMMUTER LINES MINIMUM CONSTRUCTION REQUIREMENTS	67
UP EXHIBIT D OVERPASS/UNDERPASS FREIGHT LINES MINIMUM CONSTRUCTION REQUIREMENTS	77
AGGREGATE SUBGRADE IMPROVEMENT (BDE).....	84
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....	86
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE)	88
COMPENSABLE DELAY COSTS (BDE).....	105
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	109
EROSION CONTROL BLANKET (BDE).....	111
FUEL COST ADJUSTMENT (BDE)	113
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	116
PAVEMENT MARKING (BDE)	117
PAVEMENT PATCHING (BDE)	117
PERFORMANCE GRADED ASPHALT BINDER (BDE)	118
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)	124
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	124
SEEDING (BDE)	126
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	131
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE).....	135
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	136
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	137
SUBMISSION OF BIDDERS LIST INFORMATION (BDE).....	137
SUBMISSION OF PAYROLL RECORDS (BDE).....	138
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	139
SURVEYING SERVICES (BDE).....	145
TRAINING SPECIAL PROVISIONS (BDE).....	145
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION	148
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	150
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	151



STATUS OF UTILITIES (D-1)

Effective: June 1, 2016

Revised: April 1, 2025

Utility companies and/or municipal owners located within the construction limits of this project have provided the following information regarding their facilities and the proposed improvements. The tables below contain a description of specific conflicts to be resolved and/or facilities which will require some action on the part of the Department's contractor to proceed with work. Each table entry includes an identification of the action necessary and, if applicable, the estimated duration required for the resolution.

UTILITIES TO BE ADJUSTED. Conflicts noted below have been identified by following the suggested staging plan included in the contract. The company has been notified of all conflicts and will be required to obtain the necessary permits to complete their work; in some instances, resolution will be a function of the construction staging. The responsible agency must relocate, or complete new installations as noted below; this work has been deemed necessary to be complete for the Department's contractor to then work in the stage under which the item has been listed.

Pre-Stage

STAGE / LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	DURATION OF TIME

Stage 1

STAGE / LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	DURATION OF TIME

Stage 2

STAGE / LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	DURATION OF TIME

No conflicts to be resolved (*or if there are conflicts, they are to be listed as noted above*)

Pre-Stage: _____ Days Total Installation

Stage 1: _____ Days Total Installation

Stage 2: _____ Days Total Installation

The following contact information is what was used during the preparation of the plans as provided by the Agency/Company responsible for resolution of the conflict.

Agency/Company Responsible to Resolve Conflict	Name of contact	Phone	E-mail address

UTILITIES TO BE WATCHED AND PROTECTED. The areas of concern noted below have been identified by following the suggested staging plan included for the contract. The information provided

Revised 2-13-2026



is not a comprehensive list of all remaining utilities, but those which during coordination were identified as ones which might require the Department's contractor to take into consideration when making the determination of the means and methods that would be required to construct the proposed improvement. In some instances, the contractor will be responsible to notify the owner in advance of the work to take place so necessary staffing on the owner's part can be secured.

STAGE / LOCATION	TYPE	DESCRIPTION	OWNER
IL 53 (Columbine Ave). STA 26+88, 19' RT	10" Steel Gas Main	Watch and Protect.	Nicor Gas
IL 53 (Columbine Ave). STA 26+88, 21' LT	10" Steel Gas Main	Watch and Protect from proposed HMA Shoulder work (earth excavation)	Nicor Gas
IL 53 (Columbine Ave). STA 32+31, 53' RT	2" Steel Gas Main	Watch and Protect from proposed ADA curb ramp improvement (earth excavation)	Nicor Gas
IL 53 (Columbine Ave). STA 32+35, 60' RT	2" Steel Gas Main	Watch and Protect. In proximity of proposed ADA curb ramp improvement (earth excavation)	Nicor Gas
IL 53 (Columbine Ave). STA 88+74, 56' RT	2" Steel Gas Main	Watch and Protect.	Nicor Gas
IL 53 (Columbine Ave). STA 135+35, 33' LT	8" Steel Gas Main	Watch and Protect.	Nicor Gas
IL 53 (Columbine Ave). STA 135+51, 23' RT	8" Steel Gas Main	Watch and Protect.	Nicor Gas
IL 53 (Columbine Ave). STA 138+66, 25' LT	8" Steel Gas Main	Watch and Protect.	Nicor Gas
IL 53 (Columbine Ave). STA 144+00, 37.5' LT	8" Steel Gas Main	Watch and Protect.	Nicor Gas

No facilities requiring extra consideration (*or listed as noted above*)

The following contact information is what was used during the preparation of the plans as provided by the owner of the facility.

Agency/Company Responsible to Resolve Conflict	Name of contact	Phone	E-mail address
Nicor Gas	Karey Johnson	224-471-9356 331-231-6050	karejohn@southernco.com

The above represents the best information available to the Department and is included for the convenience of the bidder. The days required for conflict resolution should be considered in the bid

Revised 2-13-2026



as this information has also been factored into the timeline identified for the project when setting the completion date. The applicable portions of the Standard Specifications for Road and Bridge Construction shall apply.

Estimated duration of time provided above for the first conflicts identified will begin on the date of the executed contract regardless of the status of the utility relocations. The responsible agencies will be working toward resolving subsequent conflicts in conjunction with contractor activities in the number of days noted.

The estimated relocation duration must be part of the progress schedule submitted by the contractor. A utility kickoff meeting will be scheduled between the Department, the Department's contractor, and the utility companies when necessary.

The contractor is responsible for contacting JULIE (or DIGGER within the City of Chicago) prior to any excavation work. Please note that IDOT electrical facilities are not part of the one-call locating services, such as JULIE or DIGGER.

If the contract requires the services of an electrical contractor, it is the contractor's responsibility, at their own expense, to locate existing IDOT electrical facilities before commencing work. For contracts that do not require an electrical contractor, the contractor may request one free locate of IDOT electrical facilities by contacting the Department's Electrical Maintenance Contractor. Additional locate requests will be at the contractor's expense.

The Department's Electrical Maintenance Contractor must be notified at least 72 hours in advance of the work by calling 773-287-7600 or emailing dispatch@meade100.com to arrange for the locating of underground electrical facilities.

Please note, the marking of underground facilities does not absolve the contractor of their responsibility to repair or replace any facilities damaged during construction at their expense.

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either "uncontaminated soil", hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Revised 2-13-2026



Intersection of IL 59 (N Grand Avenue) and Devlin Road, Ingleside, Lake County

- All excavation planned at the northeast quadrant, north island, and southeast quadrant at the intersection of IL 59 (N Grand Avenue) and Devlin Road. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL 59 (N Grand Avenue) and IL 132 (W Grand Avenue), Lake Villa, Lake County

- All excavation planned at the northwest quadrant, northeast quadrant, southwest quadrant and southeast quadrant at the intersection of IL 59 (N Grand Avenue) and IL 132 (W Grand Avenue). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Work Zones. Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: **None.**

COMPLETION DATE PLUS WORKING DAYS (D1)

Effective: September 30, 1985

Revised: January 1, 2007

Revise Article 108.05 (b) of the Standard Specifications as follows:

"When a completion date plus working days is specified, the Contractor shall complete all contract items and safely open all roadways to traffic by 11:59 PM on **October, 31, 2026** except as specified herein.

The Contractor will be allowed to complete all clean-up work and punch list items within **10** working days after the completion date for opening the roadway to traffic. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the working days allowed for clean up work and punch list items. Temporary lane closures for this work may be allowed at the discretion of the Engineer.

Article 108.09 or the Special Provision for "Failure to Complete the Work on Time", if included in this contract, shall apply to both the completion date and the number of working days.

Revised 2-13-2026