

TEMPORARY CONCRETE BARRIER

STA 1389+58 TO 1395+08	550 FOOT
------------------------	----------

RELOCATE TEMPORARY CONCRETE BARRIER

STA 1389+58 TO 1395+08	550 FOOT
------------------------	----------

PCC BASE COURSE WIDENING 8"

LT STA 1389+36 TO 1395+31	264 S. Y.
---------------------------	-----------

PAVEMENT REMOVAL

STA 1390+59 TO 1394+08	962 S. Y.
------------------------	-----------

REMOVING INLETS

LT STA 1383+48	1 EACH
RT STA 1383+48	1 EACH

PIPE CULVERT REMOVAL

LT STA 1382+25 TO STA 1383+48	125 FEET
-------------------------------	----------

CONCRETE HEADWALL REMOVAL

LT STA 1382+25	1 EACH
----------------	--------

GUTTER REMOVAL

RT & LT STA 1383+06 TO 1394+08	2204 FEET
--------------------------------	-----------

CONCRETE GUTTER, TYPE A

RT & LT STA 1383+06 TO 1394+08	2204 FEET
--------------------------------	-----------

PAVEMENT MARKING REMOVAL

STA 1388+42 TO 1396+67	619 S. F.
------------------------	-----------

HMA BASE COURSE WIDENING, 13"

LT & RT STA 1383+06 TO 1390+59	502 S. Y.
--------------------------------	-----------

PLUG EXISTING PIPE

RT STA 1382+25 TO STA 1383+47	5.6 C. Y.
-------------------------------	-----------

PROTECTING OR RESETTING SURVEY MARKERS

P. I. STA 1392+78.88	1 EACH
----------------------	--------

STONE RIPRAP, CLASS A3

LT. STA 1382+15 TO 1382+25	12 S. Y.
LT. STA 1391+83 TO 1391+98	5 S. Y.
LT. STA 1392+78 TO 1393+06	8.5 S. Y.
RT. STA 1391+98 TO 1392+14	5 S. Y.
RT. STA 1392+92 TO 1393+20	8.5 S. Y.
TOTAL	39 S. Y.

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -
ct:\pw\work\p\dot\teasleyck\d0348300\07	4627-sh1-schedules.dgn	DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 12/19/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES			
SCALE:	SHEET	OF	SHEETS
	STA.	TO	STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2801	07 DRAINAGE REHAB 2014-1	EFFINGHAM, FAYETTE	22	7
CONTRACT NO. 74627			ILLINOIS FED. AID PROJECT	