

### MAILBOX TURNOUTS

STATION	• OFFSET		AGGREGATE SHOULDERS, TYPE A
			TON
21+52	RT	22.0'	8.5
28+89	RT	22.0'	15.3
28+91	RT	22.0'	--
85+90	RT	22.0'	1.3
85+92	RT	23.0'	--
86+84	LT	22.0'	6.6
89+12	LT	22.0'	6.5
98+59	LT	22.0'	6.8
101+98	RT	22.0'	4.1
102+86	RT	22.0'	3.4
103+72	LT	22.0'	4.3
106+02	LT	22.0'	9.5
106+05	LT	22.0'	--
106+08	LT	22.0'	--
URBAN TOTAL			23.8
RURAL TOTAL			42.5
PROJECT TOTAL			66.4

\* OFFSET TO MAILBOX POST

### RIP RAP SCHEDULE

LOCATION	STONE RIPRAP, CLASS A4	STONE DUMPED RIPRAP, CLASS A 4	STONE RIPRAP, CLASS A5	FILTER FABRIC
STATION TO STATION	SQ YD	SQ YD	SQ YD	SQ YD
<b>URBAN</b>				
22+08.75		28		
25+93.30		13.6		
25+98 TO 27+30 RT	123.4			123.4
SN 100-0080			645	645
SN 100-0081	495			495
URBAN TOTAL	619	42	645	1264
<b>RURAL</b>				
87+71.30 RT		23.2		
RURAL TOTAL	0	23	0	0
PROJECT TOTAL	619	65	645	1264

### PERIMETER EROSION BARRIER SCHEDULE

LOCATION	PERIMETER EROSION BARRIER
STATION TO STATION	FOOT
<b>URBAN</b>	
<b>MAINLINE</b>	
13+50 TO 16+00 RT	250
20+30 TO 21+00 LT	70
22+00 TO 30+50 LT	393
24+00 TO 25+93 RT	193
26+00 TO 26+50 RT	50
36+23 TO 37+50 RT	127
37+50 TO 40+01 LT	51
38+50 TO 39+50 RT	100
40+23 TO 52+00 LT	1177
40+83 TO 47+50 RT	667
49+50 TO 53+00 RT	284
53+65 TO 54+50 LT	85
54+00 TO 54+50 RT	50
<b>BANDYVILLE ROAD</b>	
9+00 TO 9+30 LT&RT	85
10+50 TO 12+15 LT	138
11+50 TO 12+23 RT	85
URBAN TOTAL	3805
<b>RURAL</b>	
<b>MAINLINE</b>	
*5+00 TO 8+00 LT&RT	600
*9+50 TO 9+70 LT&RT	40
66+00 TO 68+50 LT	250
71+50 TO 72+30 LT	80
81+50 TO 83+00 RT	150
87+22 TO 87+89 LT	67
88+00 TO 89+16 LT	116
89+55 TO 98+50 LT	216
98+72 TO 100+50 RT	178
107+00 TO 108+00 RT	100
RURAL TOTAL	1797
PROJECT TOTAL	5602

### GUARDRAIL SCHEDULE

LOCATION	SPBGR, TY A, 6' POSTS	TRAFFIC BARRIER TERMINAL TY 1, SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 6	GUARDRAIL MARKERS, TYPE B	GUARDRAIL REMOVAL	TERMINAL MARKER - DIRECT APPLIED	HMA SHOULDERS 8" ***
STATION TO STATION	FEET	EACH	EACH	EACH	FEET	EACH	SQ YD
<b>URBAN</b>							
SN 100-0080 (100-3008 EX)				12	383		
RT 32+40.50 TO 35+46.75	225.0	1	1			1	110.8
RT 36+06.5 TO 37+62.70	75.0	1	1			1	60.8
LT 33+48.00 TO 35+66.75	137.5	1	1			1	81.6
LT 36+24.25 TO 37+68.00	62.5	1	1			1	56.6
SN 100-0081 (100-3009 EX)				20	307		
RT 49+35.25 TO 52+41.50	225.0	1	1			1	110.8
RT 53+94.50 TO 56+13.25	137.5	1	1			1	81.6
LT 49+86.75 TO 52+05.50	137.5	1	1			1	81.6
LT 53+58.50 TO 58+52.25	412.5	1	1			1	173.3
URBAN TOTAL	1412.5	8	8	32	690	8	757
RURAL TOTAL	0.0	0	0	0	0	0	0
PROJECT TOTAL	1412.5	8	8	32	690	8	757

\*\*\* SEE SHOULDER SCHEDULE FOR ADDITIONAL QUANTITY