URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		80%FED 20%STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8	8					
~~25000400~~	~~NITROGEN FERTILIZER NUTRIENT~~	~~POUND~~	~~1~~	~~1~~					
~~25000500~~	~~PHOSPHORUS FERTILIZER NUTRIENT~~	~~POUND~~	~~1~~	~~1~~					
~~25000600~~	~~POTASSIUM FERTILIZER NUTRIENT~~	~~POUND~~	~~1~~	~~1~~					
25200110	SODDING, SALT TOLERANT	SQ YD	8	8					
25200200	SUPPLEMENTAL WATERING	UNIT	1	1					
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	6625	6625					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	405	405					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	42	42					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	825	825					
42001300	PROTECTIVE COAT	SQ YD	9	9					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	9815	9815					

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		80%FED 20%STATE 0005					
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	553	553					
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	104	104					
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	195	195					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	125	125					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	LSUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LSUM	1	1					
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	LSUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	LSUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1698	1698					
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	566	566					

FILE NAME = pw:\\ILDOT.EGIlinois.gov:PWIDOT\Documents\IDOT Office\District 1\Projects\D142546\C\ADOptr\Design\D142546 Bridge	USER NAME = kangrgod	DESIGNED -	REVISED -
			REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/24/2016	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3508	2016-042RS	COOK	20	3

CONTRACT NO. 62D07

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

1 Rev 2-14-17

SUMMARY OF QUANTITIES

URBAN

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80%FED 20%STATE 0005					
	70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	155	155					
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10109	10109					
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2607	2607					
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	184	184					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	101	101					
	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	849	849					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	155	155					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10109	10109					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2607	2607					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	184	184					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	101	101					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	75	75					

SUMMARY OF QUANTITIES

URBAN

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80%FED 20%STATE 0005					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50	50					
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2					
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	242	242					
*	89502378	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	2	2					
	~~X0327980~~	~~PAVEMENT MARKING REMOVAL - WATER BLASTING~~	~~SQ FT~~	~~5215~~	~~5215~~					
	X2020110	GRADING AND SHAPING SHOULDERS	UNIT	60	60					
□	X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	50	50					
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2					
	X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	5346	5346					
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50	50					
□	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5					
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					

FILE NAME = pw:\\IDOT\Office\District 1\Projects\D42546\CADData\Design\D42546_SUM.dgn	USER NAME = kangrgad	DESIGNED -	REVISED -
		CHECKED -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/24/2016	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3508	2016-042RS	COOK	20	4

CONTRACT NO. 62D07

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

* SPECIALTY ITEM □ NON.-PART (100 % STATE)

Rev 2-14-17