

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES		1000					CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES		1000				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	35	35						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17300	17300					
25200110	SODDING, SALT TOLERANT	SQ YD	35	35						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3330	3330					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	35	35						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1220	1220					
40600300	AGGREGATE (PRIME COAT)	TON	165	165						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	270	270					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	61	61						* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	363	363					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17300	17300					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	320	320						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3330	3330					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	280	280						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1220	1220					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3440	3440						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	270	270					
42001300	PROTECTIVE COAT	SQ YD	300	300						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	500	500					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	25	25						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	455	455					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	225	225						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	928	928					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	40900	40900						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	25	25						40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1690	1690					
44000600	SIDEWALK REMOVAL	SQ FT	225	225						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	50	50					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1130	1130						Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	2	2					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1650	1650															
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	740	740															
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	370	370															
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	525	525															
55039700	STORM SEWERS TO BE CLEANED	FOOT	2100	2100															
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	19	19															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4155	4155															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	363	363															

* Specialty Items