

***40600990 TEMPORARY RAMP**

STATION	L (FT)	W (FT)	AREA (SQ YDS)
57+51.50	25.3	5	14.1
72+65.00	25.3	5	14.1
73+39.50	25.3	5	14.1
273+03.31	32	5	17.8
275+32.31	32	5	17.8
353+21.35	215	5	119.4
TOTAL =			197.2
USE =			197.0

70300100 SHORT TERM PAVEMENT MARKING

NET LENGTH OF SECTION =	29246.59		
29246.59	x	0.1	(4'/40') = 2924.66
2924.659	x	2	(Apps) = 5849.32
USE =			5849.0

70301000 WORK ZONE PAVT MK REM

2924.66	ft	/	4.0	ft =	731.16
731.16	x	1.33	sq ft =	972.45	ft
USE =					973.0 ft

***PLAN NOTE:** TEMPORARY RAMPS SHALL BE USED AT LOCATIONS SHOWN IN THE PLANS
IT IS THE INTENTION TO USE TEMPORARY RAMPS FOR MAJOR SIDE ROADS
AND LOCATIONS WHERE BITUMINOUS SURFACE REMOVAL 1 1/2" IS CONSTRUCTED.
TEMPORARY RAMPS SHALL NOT BE USED AT MINOR TOWNSHIP ROADS, PRIVATE ENTRANCES,
AND COMMERCIAL ENTRANCES.

***78001110 PAINT PAVEMENT MARKING - LINE 4" (YELLOW)**

48101200 AGGREGATE SHOULDERS, TYPE B

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AVERAGE THICKNESS (INCHES)	48101200 AGG SHLD TYPE B (TONS)
LT 57+51.50		LT 72+65.00	1513.5	3	1.125	56.8
RT 57+51.50		RT 72+65.00	1513.5	3	1.125	56.8
LT 73+39.50		LT 249+46.15	17606.7	3	1.125	660.2
RT 73+39.50		RT 249+46.15	17606.7	3	1.125	660.2
LT 249+46.15		LT 257+01.15	755.0	3	1.125	28.3
RT 249+46.15		RT 257+01.15	755.0	3	1.125	28.3
LT 263+47.27		LT 273+03.10	955.8	3	1.125	35.8
RT 263+47.27		RT 273+03.10	955.8	3	1.125	35.8
LT 275+32.31		LT 286+22.53	1090.2	3	1.125	40.9
RT 275+32.31		RT 286+22.53	1090.2	3	1.125	40.9
LT 288+32.51		LT 305+74.63	1742.1	3	1.125	65.3
RT 288+32.51		RT 305+74.63	1742.1	3	1.125	65.3
LT 317+03.00		LT 327+51.15	1048.2	3	1.125	39.3
RT 317+03.00		RT 327+51.15	1048.2	3	1.125	39.3
LT 327+51.15		LT 350+30.01	2278.9	3	1.125	85.5
RT 327+51.15		RT 350+30.01	2278.9	3	1.125	85.5
LT 350+30.01		LT 352+75.35	245.3	3	1.125	9.2
TOTAL =						2033.5
USE =						2034.0

STATION	TO	STATION	FOOT
NB 57+51.00		NB 64+60.00	(NO PASSING ZONE) 709.0
NB 246+80.00		NB 254+10.00	(NO PASSING ZONE) 730.0
SB 255+60.00		SB 265+10.00	(NO PASSING ZONE) 950.0
NB 281+60.00		NB 290+70.00	(NO PASSING ZONE) 910.0
SB 291+00.00		SB 300+40.00	(NO PASSING ZONE) 940.0
NB 342+40.00		NB 348+00.00	(NO PASSING ZONE) 560.0
TOTAL =			4799.0

* ADDITIONAL STRIPING QUANTITIES NOT SHOWN IN SCHEDULE