

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				MIDWEST COURT		BRIDGE REPLACEMENT	
				90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE & 5% LOCAL	100% LOCAL
				ROADWAY	BRIDGE	BRIDGE RAILING	SIDEWALK
				0004 URBAN	0010 S.N. 010-1050	0010 URBAN	0021 URBAN
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	314		314		
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	218		218		
40604050	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N50	TON	167		167		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	167		167		
40604162	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	199		199		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	199		199		
42000211	PORTLAND CEMENT CONCRETE PAVEMENT 7 1/2" (JOINTED)	SQ YD	1,793	1,793			
42001300	PROTECTIVE COAT	SQ YD	1,943	1,943			
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	4,584.0	1,803.5			2780.5
44000100	PAVEMENT REMOVAL	SQ YD	3,845	2,654	1,191		
44000300	CURB REMOVAL	FOOT	365	365			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	805	805			
44000600	SIDEWALK REMOVAL	SQ FT	2,215	2,215			
44004250	PAVED SHOULDER REMOVAL	SQ YD	868		868		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	12		12		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		

* SPECIALTY ITEM

FILE NAME = D570B98-sht-500.dgn	USER NAME = bemery	DESIGNED - CWW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - CWW	REVISED -						57	(10-34HB)BR-1	CHAMPAIGN	147	6
	PLOT DATE = 5/6/2019 - 2:45:25 PM	CHECKED - BJE	REVISED -		SCALE: N.T.S.	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 70B98	
		DATE - 04/16/2019	REVISED -		ILLINOIS FED. AID PROJECT								