I000
100%
STATE

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
20200100	EARTH EXCAVATION	CU YD	7,555
28000400	PERIMETER EROSION BARRIER	FOOT	3,400
28100707	STONE DUMPED RIP RAP, CLASS A4	SQ YD	180
31100200	SUB-BASE GRANULAR MATERIAL, TYPE A	CU YD	5,565
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1,650
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	25
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	2,085
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,240
42001300	PROTECTIVE COAT	SQ YD	110
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	450
42400800	DETECTABLE WARNINGS	SQ FT	16
44000300	CURB REMOVAL	FOOT	150
44000600	SIDEWALK REMOVAL	SQ FT	450
60600605	CONCRETE CURB, TYPE B	FOOT	150
63500105	DELINEATORS	EACH	26
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
* 78001100	PAINT PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	63
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	2,210
X0300019	REMOVE AND REINSTALL PARKING BLOCKS	EACH	20
X0323378	CONCRETE PARKING BLOCKS	EACH	21
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	16,345

*SPECIALTY ITEM

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - PJM	REVISED -
		DRAWN - DVH	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - RGD	REVISED -
	PLOT DATE = $DATE$	DATE - 12-4-07	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 2 OF 16 SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PARK ROADS	CARROLL	16	2
		CONTRACT NO. 44983		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

IDNR PROJECT #1-08-001