

EARTH EXCAVATION	
LOCATION	CU YD
STA 39+15 TO STA 86+25	5,308
LOUIS'S POINT	665
OZZIE'S POINT	973
OAK POINT	469
CONTINGENCY	140
TOTAL	7,555

BITUMINOUS MATERIALS (PRIME COAT)	
LOCATION	TON
STA 39+15 TO STA 86+25	16.2
LOUIS'S POINT	2.3
OZZIE'S POINT	3.4
OAK POINT	1.7
CONTINGENCY	1.4
TOTAL	25

SIDEWALK REMOVAL	
LOCATION	SQ FT
OAK POINT - TRAIL	90
OAK POINT - RESTROOM	360
TOTAL	450

PERIMETER EROSION BARRIER	
LOCATION	FOOT
STA 39+15 TO STA 40+10 LT & RT	230
STA 50+00 TO STA 50+90 RT	100
STA 57+00 TO STA 59+00 LT & RT	400
STA 62+10 TO STA 63+10 LT	115
STA 66+95 TO STA 67+95 RT	115
STA 76+82 TO STA 77+86 RT	115
STA 79+18 TO STA 80+22 RT	115
STA 85+35 TO STA 86+25 LT & RT	190
LOUIS'S POINT	350
OZZIE'S POINT	1,030
OAK POINT	440
CONTINGENCY	200
TOTAL	3,400

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	
LOCATION	TON
STA 39+15 TO STA 86+25	1,403
LOUIS'S POINT	199
OZZIE'S POINT	296
OAK POINT	145
CONTINGENCY	42
TOTAL	2,085

CONCRETE CURB, TYPE B	
LOCATION	FOOT
LOUIS'S POINT	150
TOTAL	150

PROTECTIVE COAT	
LOCATION	SQ YD
OAK POINT - SIDEWALK	10
OAK POINT - RESTROOM	40
LOUIS'S POINT	60
TOTAL	110

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	
LOCATION	TON
STA 39+15 TO STA 86+25	828
LOUIS'S POINT	117
OZZIE'S POINT	174
OAK POINT	85
CONTINGENCY	36
TOTAL	1,240

DELINEATORS	
LOCATION	EACH
OZZIE'S POINT	17
OAK POINT	9
TOTAL	26

SUB-BASE GRANULAR MATERIAL, TYPE A	
LOCATION	CU YD
STA 39+15 TO STA STA 86+75	3,547
LOUIS'S POINT	502
OZZIE'S POINT	747
OAK POINT	365
CONTINGENCY	404
TOTAL	5,565

PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	
LOCATION	SQ FT
OAK POINT - TRAIL	90
OAK POINT - RESTROOM	360
TOTAL	450

PAVEMENT MARKINGS		
LOCATION	PAINT PAVEMENT MARKING - LINE, 4"	PAINT PAVEMENT MARKING LETTERS AND SYMBOLS
	FOOT	SQ FT
STA 39+15 TO STA 86+25	1,190	
LOUIS'S POINT	110	58
OZZIE'S POINT	380	
OAK POINT	530	5
TOTAL	2,210	63

AGGREGATE SURFACE COURSE, TYPE B	
LOCATION	TON
MESSMER ROAD	1,650
TOTAL	1,650

DETECTABLE WARNINGS	
LOCATION	SQ FT
OAK POINT - TRAIL	8
OAK POINT - RESTROOM	8
TOTAL	16

CONCRETE PARKING BLOCKS	
LOCATION	EACH
OAK POINT	21
TOTAL	21

STONE DUMPED RIPRAP, CLASS A4	
LOCATION	SQ YD
LOUIS'S POINT	180
TOTAL	180

CURB REMOVAL	
LOCATION	FOOT
LOUIS'S POINT	150
TOTAL	150

REMOVE AND REINSTALL PARKING BLOCKS	
LOCATION	EACH
LOUIS'S POINT	6
OZZIE'S POINT	14
TOTAL	20

GEOTECHNICAL REINFORCEMENT	
LOCATION	SQ YD
STA 39+15 TO STA 86+25	11,235
LOUIS'S POINT	1,595
OZZIE'S POINT	2,360
OAK POINT	1,155
TOTAL	16,345