LOCATION #2 - IL 149 GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURE	STEEL PLATE BEAM GUARDRAIL, SHORT RADIUS	TRAFFIC BARRIER TERMINAL TYPE 1B	TRAFFIC BARRIER TERMINAL TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TAN)	TERMINAL MARKERS DIRECT APPLIED	GUARDRAIL MARKERS
	FOOT	FOOT	EACH	FOOT	EACH	EACH	EACH	EACH	EACH
SN # - 028-0041									
RT 1109+36 TO 1112+61	325								
RT 1109+45					1			1	2
RT 1109+45 TO RT 1109+(66) ⚠				(37.5) ⚠					
RT 1109+(66) ⚠ TO RT 1110+41		(75) ⚠							2
RT 1110+41 TO RT 1110+53.5			12.5						
RT 1110+53.5 TO RT 1112+16		167.5							2
RT 1112+16 TO RT 1112+61						1			2
LT 1109+64 TO LT 1111+96	232								
LT 1108+76 TO LT 1109+26							1	1	2
LT 1109+26 TO LT 1111+51		225.0							3
LT 1111+51 TO LT 1111+96						1			2
LT 1113+07 TO LT 1115+56	249								
LT 1113+07 TO LT 1113+52						1			2
LT 1113+52 TO LT 1115+39.5		187.5							3
LT 1115+39.5 TO LT 1115+89.5							1	1	2
RT 1113+47 TO RT 1115+39	192								
RT 1113+47 TO RT 1113+92						1			2
RT 1113+92 TO RT 1120+17		625.0							8
RT 1120+17 TO RT 1120+67							1	1	2
LOCATION #2 TOTALS	998	(1280.0) ⚠	12.5	(37.5) ⚠	1	4	3	4	34

⚠ Rev. 2-19-08

FILE NAME = c:\projects\d903807\d903807pl.m32	USER NAME = russellcf	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GUARDRAIL SCHEDULE			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					•	D-9 SAFETY FY08-3	**	16	5
	PLOT SCALE = 50.00 ' / IN.	CHECKED -	REVISED -								CONTRACT NO. 78042	
	PLOT DATE = 11/21/2007	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		