

LOCATION #4 - US 45 GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A	STEEL PLATE BEAM GUARDRAIL, SHORT RADIUS	TRAFFIC BARRIER TERMINAL TYPE 1B	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TAN)	TERMINAL MARKERS DIRECT APPLIED	GUARDRAIL MARKERS	COMMENTS
	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	
SN# - Q64-0006								
RT 118+43 TO RT 118+93	50							
RT 118+05.5 TO RT 118+55.5					1	1	2	
RT 118+55.5 TO RT 118+93		37.5					1	
LT 119+68 TO LT 119+93	25							
LT 118+55.5 TO LT 119+05.5					1	1	2	
LT 119+05.5 TO LT 119+93		87.5					2	
RT 121+44 TO 121+69	25							
RT 121+56.5 TO RT 121+77.5			37.5	1		1	2	8.5' RADIUS
RT 121+77.5							2	
RT 121+44 TO RT 121+56.5		12.5		1		1	2	
RT 10+71 TO RT 10+96 (UNITY SCHOOL RD.)		100					2	50' RADIUS IN NE QUAD
RT 10+71 (UNITY SCH. RD.) TO LT 123+13 (US 45)					1	1	2	
LT 123+13 TO LT 123+63								
LOCATION #4 TOTALS	100	237.5	37.5	2	3	5	17	

FILE NAME =
c:\projects\903807\903807.plm32

USER NAME = russellof

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 50.00' / IN.

CHECKED -

REVISED -

PLOT DATE = 11/21/2007

DATE -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GUARDRAIL SCHEDULE

SCALE: SHEET NO. OF SHEETS STA. TO STA.

Rev. 2-19-08

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D-9	D-9 SAFETY FY08-3	**	16	7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 78042	