

85417

SCHEDULE FOR EARTHWORK

	20200100 EARTH EXCAVATION CY	20200910 GRADING AND SHAPING ROADWAY UNIT (LS)	20201006 GRADING AND SHAPING OF SHOULDERS UNIT (LS)	GRADING AND SHAPING OF DITCHES FOOT	FILL CY	CUT CY	EARTHWORK BALANCE CY
STATION							
46+60-71+50	890			245	94	721	-627
48+77-51+22		5	5				
51+33-52+16				83			
53+00-53+65				65			
60+45-61+56				111			
61+24-64+79				355			
TOTAL	890	5	5	859	94	721	-627

SCHEDULE FOR HOT-MIX ASPHALT

	BITUMINOUS MATERIALS (PRIME COAT)	LEVELING BINDER, (MACHINE METHOD) N50	HOT-MIX ASPHALT SURFACE COURSE MIX "C" N50
STATION - STATION	GAL	TON	TON
46+60-48+33	345	72	72
47+85-61+43	183	77	77
51+23-51+33	9	2	2
52+11-53+07	74	16	16
55+38-55+72	10	2	2
62+76-63+25	18	4	4
64+07-64+51	11	2	2
69+18-69+27	3	1	1
69+58-69+61	4	1	1
TOTAL	658	177	177

SCHEDULE FOR LANDSCAPING ITEMS

	TOPSOIL EXCAVATION AND PLACEMENT CY	SEEDING CLASS 2A ACRE	NITROGEN FERTILIZER NUTRIENT LB	PHOSPHORUS FERTILIZER NUTRIENT LB	POTASSIUM FERTILIZER NUTRIENT LB	MULCH METHOD 1 ACRE
STATION - STATION						
46+60-71+50	1,335.77	1.66	144.65	144.65	144.65	1.66
TOTAL	1,336	1.66	145	145	145	1.66

SCHEDULE FOR CONCRETE SHARED USE PATH AND CONCRETE SERVICE WALK

	10' WIDE 4" DEPTH	10' WIDE 6" DEPTH
STATION	SQ FT	SQ FT
47+82-47+93 LT	95	
47+47-48+20 RT	140	
48+33-51+21	2,914	
51+21-51+35		183
51+35-52+11	750	
52+11-52+92		1,038
52+92-55+38	2,446	
54+93-54+96 RT	15	
55+38-55+72		456
55+72-62+88	7,162	
61+54-61+59 RT		60
62+34-62+48 RT	60	
62+88-63+13		356
63+13-64+19	1,066	
64+19-64+39		195
64+39-69+21	4,813	
69+64-71+50	1,844	
70+86-71+11 RT	103	
71+11-71+19 RT	45	
TOTAL	21,453	2,288

SCHEDULE FOR EROSION CONTROL

	PERIMETER EROSION FT	INLET FILTERS EACH	TEMP. DITCH CHECKS EACH
STATION			
46+60-71+50		7	
56+59-61+29	470		
60+57-61+19 LT			2
61+90-64+56 RT			5
TOTAL	470	7	7

SCHEDULE FOR RIP-RAP

	RIP-RAP STONE RIP RAP CLASS A4 SY	FILTER FABRIC SY
STATION		
52+05-52+25 LT	24	24
60+41-60+63 RT	42	42
61+25-61+54 RT	44	44
TOTAL	110	110

SCHEDULE FOR BASE COURSE

STATION - STATION	LOCATION	AGGREGATE BASE COURSE TYPE A 6" TON	AGGREGATE BASE COURSE TYPE A 8" TON
46+60-71+50	CENTER	1,387	
47+20-48+53	LT		122
47+91-48+51	LT		14
48+77-52+46	LT		65
52+60-57+00	LT		107
57+00-61+43	LT		72
TOTAL:		1,387	308



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY

SUBMITTED: 12/13/2007
 PLOTTED: 12/13/2007
 CHECKED: 12/13/2007
 FILE NAME: I:\Projects\06-00042-00-BT\06-00042-00-BT.dwg
 PLOT SCALE: 1" = 200'