


SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY QUANTITIES	LIGHTING QUANTITIES
	25000110 SEEDING, CLASS 1A	ACRE	0.25	0.25	
*	40201000 AGGREGATE FOR TEMPORARY ACCESS	TON	155	155	
*	40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5	5	
*	42300200 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	12	12	
*	42300400 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	347	347	
*	42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	7,618	7,618	
*	42400800 DETECTABLE WARNINGS	SQ FT	151	151	
*	44000200 DRIVEWAY PAVEMENT REMOVAL	SQ YD	368	368	
*	44000500 COMBINATION CURB AND GUTTER REMOVAL	FOOT	886	886	
*	44000600 SIDEWALK REMOVAL	SQ FT	6,615	6,615	
*	44201785 CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	6	6	
*	44201789 CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	8	8	
*	60600605 CONCRETE CURB, TYPE B	FOOT	18	18	
	67100100 MOBILIZATION	L SUM	1	1	
*	78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	487	487	
*	78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	282	282	
	80400100 ELECTRIC SERVICE INSTALLATION	EACH	1		1
	81028350 UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	3,055		3,055
	81702110 ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	8,685		8,685
	81702120 ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	19,480		19,480
	81702130 ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	4,004		4,004
	81702140 ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	7,802		7,802
	81702150 ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	4,148		4,148
	84200500 REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	1		1
	X6064200 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	921	921	
	X7010216 TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
	X8140105 HANDHOLE (SPECIAL)	EACH	38		38
	X8360310 LIGHT POLE FOUNDATION, 30" DIAMETER, SPECIAL	FOOT	140		140
	XX007393 DECORATIVE LIGHT TYPE A	EACH	56		56
	XX007394 DECORATIVE LIGHT TYPE B	EACH	20		20
	X8040102 ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	1		1

* DENOTES SPECIALTY ITEM

1 2/20/2013

208 East Main Street, Suite 100
 Bellville, Illinois 62220
 618.233.5877 phone
 618.233.5977 fax
 www.kaskaskiaeng.com



LICENSE NO.
 184-004773
 PROFESSIONAL REGISTRATIONS
 Illinois Professional Design Firm
 Professional Engineering Group

PREPARED BY:

SUMMARY OF QUANTITIES

SEC 10-00085-01-LS
 NORTH MAIN STREET STREETScape
 CITY OF EDWARDSVILLE, ILLINOIS

SHEET TITLE:

PROJECT TITLE:

DESIGNED BY: LDC	3
DRAWN BY: SMS	
CHECKED BY: GEB	
DATE OF PRE-FINAL: 8/17/12	
DATE OF FINAL: 10/12/12	
SHEET NO. 3 OF 18 SHEETS	
PROJECT NUMBER 09-1074.01	