

80% FED
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				BRIDGE	BRIDGE	HIGHWAY LIGHTING
				0010	0047	0021
				060-0347	060-0244	060-0347
* 83010600	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. MAST ARM	EACH	6			6
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	28			28
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	4			4
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	6			6
X0322215	CLEANING BRIDGE SCUPPERS AND DOWNSPOUTS	EACH	4		4	
X0324028	GROUT FOR USE WITH RIPRAP	CU YD	15	15		
X5200101	REMOVE EXISTING JOINT	FOOT	156		156	
X2200020	FENCE REMOVAL AND REINSTALLATION	FOOT	73	73		
X5211615	HIGH LOAD MULTI-ROTATIONAL BEARINGS, DISC, GUIDED EXPANSION-300K	EACH	10	10		
X5211630	HIGH LOAD MULTI-ROTATIONAL BEARINGS, DISC, GUIDED EXPANSION-600K	EACH	5	5		
X5870015	BRIDGE DECK CONCRETE SEALER	SQ FT	15902		15902	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
Z0010400	CLEANING BRIDGE SEATS	SQ FT	743		743	
X7010218	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	EACH	1	1		
Z0041895	POLYMER CONCRETE	CU FT	8.7		8.7	
52000204	FINGER PLATE EXPANSION JOINT, 2"	FOOT	76	76		
Ø Z0076600	TRAINEES	HOUR	3500	3500		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	3500	3500		
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	7	7		



* SPECIALTY ITEM
Ø 0042

△ REVISED 2-26-2024

REV. - MS

MODEL: D:\m\h\ FILE NAME: 11313249_PTB_199_0218219_060_V006_IL_111_P4_H_Road_Plan_CAD_Sheet\11313249_PTB_199_0218219_060_V006.dgn



USER NAME = tkrupe	DESIGNED - TAK	REVISED -
	DRAWN - TAK	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED - BMR	REVISED -
PLOT DATE = 10/17/2023	DATE - 10/17/23	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS SHEET 8 OF 8 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
582	6-23B-I	MADISON	90	10
CONTRACT NO. 76H49			ILLINOIS FED. AID PROJECT	