

# DUPAGE AIRPORT AUTHORITY WEST CHICAGO, ILLINOIS CONSTRUCTION PLANS FOR DUPAGE AIRPORT

## REHABILITATE AIRFIELD PAVEMENTS/ISOLATED PAVEMENT REPLACEMENTS; RUNWAY 2L/20R AND 2R/20L, TAXIWAY C AND W

ILLINOIS PROJECT: DPA-5065  
SBGP PROJECT: 3-17-SBGP-TBD

JANUARY 12, 2024

DESIGN INFORMATION

APPROACH CATEGORY D  
TAXIWAY DESIGN GROUP 2B

### DUPAGE AIRPORT

TOWNSHIP: 40 NORTH      WAYNE TOWNSHIP  
RANGE: 9 EAST            (SECTIONS: 31)  
DUPAGE COUNTY




Know what's below.  
Call before you dig.

J.U.L.I.E.  
JOINT UTILITY LOCATING  
INFORMATION FOR EXCAVATORS  
www.Illinois1call.com

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE. SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS, OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION AND THE ONE-CALL NOTICE SYSTEM. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH UTILITY OR SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.


CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811.

PROJECT  
LOCATION



LOCATION MAP

PROJECT  
LOCATION



SITE PLAN



CRAWFORD, MURPHY & TILLY, INC.  
CONSULTING ENGINEERS  
License No. 184-000613

22004585-00



SUBMITTED BY *[Signature]*  
DATE 1/12/2024

DANIEL L. PAPE, P.E.  
DATE

DuPAGE Airport  
AUTHORITY

DuPage Airport

2700 INTERNATIONAL DRIVE  
SUITE 200  
WEST CHICAGO, IL 60185

APPROVED BY *[Signature]*  
DATE 1/12/2024

MARK DOLES  
EXECUTIVE DIRECTOR  
DATE



CONSULTANTS

**INDEX TO SHEETS**

1. COVER SHEET
2. INDEX TO SHEETS-SUMMARY OF QUANTITIES
3. SITE PLAN-CONTRACTOR'S ACCESS AND STORAGE
4. CONSTRUCTION SAFETY AND PHASING PLAN - 1
5. CONSTRUCTION SAFETY AND PHASING PLAN - 2
6. CONSTRUCTION SAFETY AND PHASING PLAN - 3
7. CONSTRUCTION SAFETY AND PHASING PLAN GENERAL NOTES - 1
8. CONSTRUCTION SAFETY AND PHASING PLAN GENERAL NOTES - 2
9. CONSTRUCTION SAFETY AND PHASING DETAILS
10. REHABILITATE RUNWAY 2L-20R - 1
11. REHABILITATE RUNWAY 2L-20R - 2
12. REHABILITATE TAXIWAY C - 1
13. REHABILITATE TAXIWAY C - 2
14. REHABILITATE TAXIWAY C-3 AND RUNWAY 2R-20L
15. REHABILITATE TAXIWAY W, L AND G
16. REHABILITATE FLIGHT CENTER APRON
17. PAVEMENT JOINTING DETAILS - 1
18. PAVEMENT JOINTING DETAILS - 2
19. TYPICAL SECTIONS
20. PAVEMENT MARKING DETAILS

**BORING/CORING INFORMATION**

<b>B-1</b> 1.5" ASPHALT SURFACE MIX 5.5" ASPHALT BINDER MIX 9.0" CONCRETE 26.4" CLAY, BROWN, HARD 60" SILTY CLAY, GRAY, VERY STIFF 18" CLAY LOAM, GRAY, HARD
<b>B-2</b> 8.5" CONCRETE 4.0" ASPHALT BINDER MIX 30" CLAY, BROWN AND GRAY, STIFF 60" SAND, BROWN, MEDIUM DENS 18" SILTY CLAY LOAM, GRAY, SOFT
<b>B-3</b> 9.0" CONCRETE 3.0" ASPHALT 60" SANDY CLAY WITH GRAVEL, GRAY, VERY STIFF TO HARD 30" SILTY CLAY LOAM, BROWN AND GRAY, SOFT TO MEDIUM STIFF 18" CLAYEY SAND AND GRAVEL, BROWN

DATA FROM GEOTECHNICAL INVESTIGATION REPORT COMPLETED IN JANUARY 2024

**SUMMARY OF QUANTITIES**

ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
<b>BASE BID</b>				
AR150510	ENGINEER'S FIELD OFFICE	L SUM	1	
AR150520	MOBILIZATION	L SUM	1	
AR152410	UNCLASSIFIED EXCAVATION	CU YD	128	
AR209604	CRUSHED AGG. BASE COURSE - 4"	SQ YD	1080	
AR401610	BITUMINOUS SURFACE COURSE	TON	185	
AR401650	BITUMINOUS PAVEMENT MILLING	SQ YD	1600	
AR403610	BITUMINOUS BASE COURSE	TON	185	
AR501508	8" PCC PAVEMENT	SQ YD	1045	
AR501530	PCC TEST BATCH	EACH	1	
AR501550	PCC PAVEMENT MILLING	SQ YD	35	
AR501900	REMOVE PCC PAVEMENT	SQ YD	1045	
AR603510	BITUMINOUS TACK COAT	GALLON	315	
AR620520	PAVEMENT MARKING - WATERBORNE	SQ FT	939	
AR620525	PAVEMENT MARKING - BLACK BORDER	SQ FT	737	
<b>ADDITIVE ALTERNATE NO. 1</b>				
AS152410	UNCLASSIFIED EXCAVATION	CU YD	35	
AS209604	CRUSHED AGG. BASE COURSE - 4"	SQ YD	310	
AS800046	8" PCC PAVEMENT - HIGH EARLY MIX	SQ YD	310	
AS501900	REMOVE PCC PAVEMENT	SQ YD	310	
AS620520	PAVEMENT MARKING - WATERBORNE	SQ FT	335	
AS620525	PAVEMENT MARKING - BLACK BORDER	SQ FT	70	
<b>ADDITIVE ALTERNATE NO. 2</b>				
AT501550	PCC PAVEMENT MILLING	SQ YD	350	
<b>ADDITIVE ALTERNATE NO. 3 - LOCAL ONLY FUNDING</b>				
AU152410	UNCLASSIFIED EXCAVATION	CU YD	10	
AU209604	CRUSHED AGG. BASE COURSE - 4"	SQ YD	85	
AU501550	PCC PAVEMENT MILLING	SQ YD	136	
AU800046	8" PCC PAVEMENT - HIGH EARLY MIX	SQ YD	85	
AU501900	REMOVE PCC PAVEMENT	SQ YD	85	
AU620520	PAVEMENT MARKING - WATERBORNE	SQ FT	66	
AU620525	PAVEMENT MARKING - BLACK BORDER	SQ FT	29	

100% FINAL  
JANUARY 12, 2024

REHAB AIRFIELD PAVEMENTS  
FED



OWNER

DUPAGE AIRPORT  
WEST CHICAGO, ILLINOIS

MARK | DATE | DESCRIPTION

AIP PROJ. NO.

DPA 5065

CMT PROJECT NO: 22004585.00

CAD DWG FILE: 22004585 - DPA - QUANTITIES.DWG

DESIGNED BY: AM

DRAWN BY: JRO

CHECKED BY: DKP

APPROVED BY: DLP

COPYRIGHT:

SHEET TITLE

INDEX TO  
SHEETS-SUMMARY  
OF QUANTITIES





CONSULTANTS

100% FINAL  
JANUARY 12, 2024  
REHAB AIRFIELD PAVEMENTS  
FED




OWNER

DUPAGE AIRPORT  
WEST CHICAGO, ILLINOIS

**LEGEND**

- CONTRACTOR'S STAGING AND STORAGE AREA
- PAVEMENT CLOSED TO AIR TRAFFIC
- LOW PROFILE BARRICADES
- CLOSED RUNWAY MARKER
- CLOSED TAXIWAY MARKER
- CONTRACTOR'S ACCESS/HAUL ROUTE
- AIRCRAFT MOVEMENT AREA
- TAXIWAY OBJECT FREE AREA (TOFA)
- RUNWAY SAFETY AREA (RSA)
- RUNWAY OBJECT FREE AREA (ROFA)
- FAA CRITICAL POINT



FAA CRITICAL POINT TABLE

POINT	LATITUDE	LONGITUDE	GROUND ELEVATION	OBSTRUCTION HEIGHT (FT)	ABOVE GROUND ELEVATION
1	41°54'08.76"	88°15'18.69"	754	25	779
2	41°54'07.78"	88°15'18.69"	754	25	779
3	41°54'07.78"	88°15'21.33"	754	25	779
4	41°54'08.77"	88°15'21.33"	754	25	779
5	41°53'56.06"	88°15'11.93"	752	25	777
6	41°54'10.39"	88°15'05.53"	752	25	777
7	41°54'20.58"	88°15'04.16"	753	25	778
8	41°54'39.90"	88°15'05.72"	754	25	779
9	41°54'46.00"	88°15'30.60"	750	25	775

EXISTING CRITICAL AIRCRAFT AND REQUIRED SAFETY AREAS

RUNWAY	2L/20R	2R/20L	10/28	15/33
APPROACH CATEGORY	D	C	B	B
DESIGN GROUP	III	II	II	II
DESIGN AIRCRAFT	BBJ	CHALLENGER 850	FALCON 900	KING AIR C90-1
WINGSPAN	117.4 FEET	69.6 FEET	63.4 FEET	50.2 FEET
TAIL HEIGHT	41.1 FEET	20.4 FEET	24.8 FEET	14.2 FEET
STRENGTH (MGTW)	171,000 LBS.	53,000 LBS.	45,500 LBS.	9,650 LBS.
LENGTH	BBJ	CHALLENGER 850	FALCON 900	KING AIR C90-1
(1) RUNWAY SAFETY AREA WIDTH (RSA)	500 (250' FROM C)	400 (200' FROM C)	150 (75' FROM C)	150 (75' FROM C)
(2) RUNWAY OBJECT FREE AREA WIDTH (ROFA)	800 (400' FROM C)	800 (400' FROM C)	500 (250' FROM C)	500 (250' FROM C)
TAXIWAY SAFETY AREA WIDTH (TSA)	118 (59' FROM C)	79 (39.5' FROM C)	79 (39.5' FROM C)	79 (39.5' FROM C)
(1)(2) TAXIWAY OBJECT FREE AREA WIDTH (TOFA)	186 (93' FROM C)	131 (65.5' FROM C)	131 (65.5' FROM C)	131 (65.5' FROM C)

- NO CONSTRUCTION WITHIN THESE LIMITS WILL BE ALLOWED WITHOUT THE RUNWAY AND / OR TAXIWAY BEING CLOSED.
- NO CONSTRUCTION EQUIPMENT SHALL BE PARKED / STORED WITHIN THE OBJECT FREE AREA(S) OF OPEN RUNWAYS AND / OR TAXIWAYS AND THE PARKED / STORED EQUIPMENT HEIGHT SHALL NOT PENETRATE THE PART 77 SURFACE(S).
- ADDITIVE ALTERNATE WORK ON THE FLIGHT CENTER APRON CAN BE COMPLETED DURING ANY PHASE.

WORK AREA	AIRFIELD IMPACT MATRIX LIMITS OF CLOSURE	WORK ITEMS
PHASE 1A	RUNWAY 2L/20R - OPEN	PCC PAVEMENT REPLACEMENT
	RUNWAY 2R/20L - OPEN	
	RUNWAY 10-28 - OPEN	
	RUNWAY 15-33 - OPEN	
	TAXIWAY W - CLOSED (BETWEEN TXY W1 AND TXY W2)	
TAXIWAY Y - CLOSED (BETWEEN FLIGHT CENTER APRON AND RWY 2L/20R)	ALL OTHER TAXIWAYS OPEN	

WORK AREA	AIRFIELD IMPACT MATRIX LIMITS OF CLOSURE	WORK ITEMS
PHASE 1B	RUNWAY 2L/20R - OPEN	PCC PAVEMENT REPLACEMENT & PCC MILLING
	RUNWAY 2R/20L - OPEN	
	RUNWAY 10-28 - OPEN	
	RUNWAY 15-33 - OPEN	
	TAXIWAY F - CLOSED (SOUTH OF RWY 10/28)	
	TAXIWAY G - CLOSED (WEST OF TXY W)	
TAXIWAY L - CLOSED	ALL OTHER TAXIWAYS OPEN	

NOTE: TAXIWAY F AND TAXIWAY G SHALL BE RE-OPENED TO AIRCRAFT TRAFFIC UPON COMPLETION OF THE PCC MILLING WORK ON TAXIWAY G

**PHASE 1 NOTES**

- THIS PHASE SHALL INCLUDE ALL BASE BID WORK WEST OF THE RUNWAY 2L/20R RUNWAY SAFETY AREA.
- IF ADDITIVE ALTERNATE NO. 2 IS AWARDED, THE PCC MILLING ON THE FLIGHT CENTER APRON IS RECOMMENDED TO BE COMPLETED DURING THIS PHASE.
- PHASE 1A AND PHASE 1B SHALL NOT BE WORKED ON CONCURRENTLY WITH EACH OTHER, AS THE FLIGHT CENTER APRON MUST MAINTAIN TWO AIRCRAFT ACCESS POINTS AT ALL TIMES. IF PHASE 1A AND PHASE 1B ARE TO BE COMPLETED CONSECUTIVELY, THE NEW PCC PAVEMENT OF THE FIRST AREA MUST FINISH CURING AND ACHIEVE ACCEPTABLE STRENGTH TEST RESULTS BEFORE WORK ON THE OTHER CAN BEGIN.
- UPON APPROVAL BY THE AIRPORT AND THE RESIDENT ENGINEER, WORK ON PHASE 1A AND/OR PHASE 1B MAY BE WORKED ON CONCURRENTLY WITH PHASE 2 OR PHASE 3.
- AFTER THE NEW PCC HAS BEEN POURED FOR THE PANEL REPLACEMENTS UNDER THIS PHASE, THE WORK AREAS SHALL REMAIN CLOSED TO AIRCRAFT TRAFFIC WHILE THE PCC MIX CURES. WHEN PCC STRENGTH TESTING PRODUCES ACCEPTABLE RESULTS, THESE AREAS MAY BE RE-OPENED TO AIRCRAFT TRAFFIC.
- WHEN THE CONTRACTOR'S EQUIPMENT, VEHICLES OR PERSONNEL NEED TO CROSS ACTIVE PAVEMENTS, THE CONTRACTOR WILL BE REQUIRED TO BE UNDER CONTROL BY A CROSSING GUARD OR ESCORT IN RADIO CONTACT WITH THE ATCT.

MARK DATE DESCRIPTION

AIP PROJ. NO.		
DPA 5065		
CMT PROJECT NO: 22004585.00		
CAD DWG FILE: 22004585 - DPA - CSPP PLAN - 1.DWG		
DESIGNED BY: AM		
DRAWN BY: JRO		
CHECKED BY: DKP		
APPROVED BY: DLP		
COPYRIGHT:		

**CONSTRUCTION  
SAFETY AND PHASING  
PLAN - 1**



CONSULTANTS

100% FINAL  
JANUARY 12, 2024  
REHAB AIRFIELD PAVEMENTS  
FED



OWNER

DUPAGE AIRPORT  
WEST CHICAGO, ILLINOIS

MARK | DATE | DESCRIPTION

AIP PROJ. NO.  
DPA 5065  
CMT PROJECT NO: 22004585.00  
CAD DWG FILE: 22004585 - DPA - CSPP PLAN - 2.DWG  
DESIGNED BY: AM  
DRAWN BY: JRO  
CHECKED BY: DKP  
APPROVED BY: DLP  
COPYRIGHT:

SHEET TITLE  
**CONSTRUCTION  
SAFETY AND PHASING  
PLAN - 2**

SHEET 5 OF 20


EXISTING CRITICAL AIRCRAFT AND REQUIRED SAFETY AREAS

RUNWAY	2L/20R	2R/20L	10/28	15/33
APPROACH CATEGORY	D	C	B	B
DESIGN GROUP	III	II	II	II
DESIGN AIRCRAFT	BBJ	CHALLENGER 850	FALCON 900	KING AIR C90-1
WINGSPAN	117.4 FEET	69.6 FEET	63.4 FEET	50.2 FEET
TAIL HEIGHT	41.1 FEET	20.4 FEET	24.8 FEET	14.2 FEET
STRENGTH (MGW)	171,000 LBS.	53,000 LBS.	45,500 LBS.	9,650 LBS.
LENGTH	BBJ	CHALLENGER 850	FALCON 900	KING AIR C90-1
(1) RUNWAY SAFETY AREA WIDTH (RSA)	500 (250' FROM Q)	400 (200' FROM Q)	150 (75' FROM Q)	150 (75' FROM Q)
(2) RUNWAY OBJECT FREE AREA WIDTH (ROFA)	800 (400' FROM Q)	800 (400' FROM Q)	500 (250' FROM Q)	500 (250' FROM Q)
TAXIWAY SAFETY AREA WIDTH (TSA)	118 (59' FROM Q)	79 (39.5' FROM Q)	79 (39.5' FROM Q)	79 (39.5' FROM Q)
(1)(2) TAXIWAY OBJECT FREE AREA WIDTH (TOFA)	186 (93' FROM Q)	131 (65.5' FROM Q)	131 (65.5' FROM Q)	131 (65.5' FROM Q)

- NO CONSTRUCTION WITHIN THESE LIMITS WILL BE ALLOWED WITHOUT THE RUNWAY AND / OR TAXIWAY BEING CLOSED.
- NO CONSTRUCTION EQUIPMENT SHALL BE PARKED / STORED WITHIN THE OBJECT FREE AREA(S) OF OPEN RUNWAYS AND / OR TAXIWAYS AND THE PARKED / STORED EQUIPMENT HEIGHT SHALL NOT PENETRATE THE PART 77 SURFACE(S).
- ADDITIVE ALTERNATE WORK ON THE FLIGHT CENTER APRON CAN BE COMPLETED DURING ANY PHASE.

LEGEND

- CONTRACTOR'S STAGING AND STORAGE AREA
- PAVEMENT CLOSED TO AIR TRAFFIC
- LOW PROFILE BARRICADES
- CLOSED RUNWAY MARKER
- CLOSED TAXIWAY MARKER
- CONTRACTOR'S ACCESS/HAUL ROUTE
- AIRCRAFT MOVEMENT AREA
- TOFA - TAXIWAY OBJECT FREE AREA (TOFA)
- RSA - RUNWAY SAFETY AREA (RSA)
- ROFA - RUNWAY OBJECT FREE AREA (ROFA)
- FAA CRITICAL POINT



PCC PANEL REPLACEMENTS UNDER ADDITIVE ALTERNATE NO. 3

WORK AREA	AIRFIELD IMPACT MATRIX LIMITS OF CLOSURE	WORK ITEMS
PHASE 2	RUNWAY 2L/20R - OPEN	PCC PAVEMENT REPLACEMENT, PCC MILLING AND BITUMINOUS MILL & OVERLAY
	RUNWAY 2R/20L - CLOSED	
	RUNWAY 10-28 - OPEN	
	RUNWAY 15-33 - OPEN	
	TAXIWAY Z - CLOSED (BETWEEN RWY 2R/20L AND RWY 2L/20R)	
	TAXIWAY C - CLOSED (BETWEEN TXY Z AND TXY G)	
TAXIWAY Y - CLOSED (BETWEEN RWY 2R/20L AND RWY 2L/20R)		
TAXIWAY T - CLOSED (BETWEEN RWY 2R/20L AND RWY 2L/20R)		
	ALL OTHER TAXIWAYS OPEN	

FAA CRITICAL POINT TABLE					
POINT	LATITUDE	LONGITUDE	GROUND ELEVATION	OBSTRUCTION HEIGHT (FT)	ABOVE GROUND ELEVATION
10	41°53'38.18"	88°15'09.48"	747	25	772
11	41°54'09.20"	88°14'59.12"	751	25	776
12	41°54'23.10"	88°14'54.47"	752	25	777
13	41°54'37.00"	88°14'44.83"	756	25	781
14	41°54'36.58"	88°14'39.50"	757	25	782
15	41°53'57.75"	88°14'45.84"	751	25	776
16	41°53'59.67"	88°14'45.20"	751	25	776
17	41°53'59.43"	88°14'43.91"	751	25	776
18	41°53'57.52"	88°14'44.55"	751	25	776

PHASE 2 NOTES

- THIS PHASE SHALL INCLUDE ALL WORK EAST OF THE RUNWAY 2L/20R RUNWAY SAFETY AREA.
- TO FACILITATE SAFE TRAVEL OPERATIONS FOR THE CONTRACTOR'S EQUIPMENT AND VEHICLES, RUNWAY 2R/20L SHALL REMAIN CLOSED DURING THIS PHASE EVEN IF ADDITIVE ALTERNATE NO. 3 IS NOT AWARDED.
- TO MINIMIZE CLOSURE TIME OF RUNWAY 2R/20L, HIGH EARLY STRENGTH PCC MIX WILL BE USED FOR THE PCC PANEL REPLACEMENTS ON RUNWAY 2R/20L (ADDITIVE ALTERNATE NO. 3).
- THE CONTRACTOR SHALL BE PERMITTED 4 CALENDAR DAYS TO COMPLETE THE WORK IN THIS PHASE AND RE-OPEN RUNWAY 2R/20L.
- AFTER THE NEW PCC HAS BEEN POURED FOR THE PANEL REPLACEMENTS UNDER THIS PHASE, THE WORK AREAS SHALL REMAIN CLOSED TO AIRCRAFT TRAFFIC WHILE THE PCC MIX CURES. WHEN PCC STRENGTH TESTING PRODUCES ACCEPTABLE RESULTS, THESE AREAS MAY BE RE-OPENED TO AIRCRAFT TRAFFIC.
- WHEN THE CONTRACTOR'S EQUIPMENT, VEHICLES OR PERSONNEL NEED TO CROSS ACTIVE PAVEMENTS, THE CONTRACTOR WILL BE REQUIRED TO BE UNDER CONTROL BY A CROSSING GUARD OR ESCORT IN RADIO CONTACT WITH THE ATCT.

Path: K:\dupage\22004585\_00\_RehabAirfieldPavements\FED\Draw Sheets\22004585 - dpa - cspp plan - 2.dwg  
Date: Wednesday, January 31, 2024 2:28:50 PM



**GENERAL**

1. THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL FOLLOW THE REQUIREMENTS OF THE AIRPORT'S APPROVED CONSTRUCTION SAFETY AND PHASING PLAN (CSPP), FAA AC 150/5370-2G OR LATEST EDITION, AND ALL AIRPORT SAFETY AND SECURITY REQUIREMENTS.
2. PRIOR TO THE NOTICE TO PROCEED, THE CONTRACTOR SHALL SUBMIT TO THE AIRPORT THROUGH THE RESIDENT ENGINEER, FOR APPROVAL A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) IN ACCORDANCE WITH FAA AC 150/5370-2G OR LATEST EDITION. NO CONSTRUCTION ACTIVITY SHALL BEGIN UNTIL THE AIRPORT HAS APPROVED THE SPCD.
3. THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER PERSONNEL AND MEETING OSHA REQUIREMENTS.
4. A MINIMUM OF 10 DAYS PRIOR TO THE NOTICE TO PROCEED THE CONTRACTOR SHALL PROVIDE A LIST OF SUBCONTRACTORS AND MATERIAL SUPPLIERS.
5. ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED ON THIS SHEET SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
6. THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE NEW IMPROVEMENTS WHILE MAINTAINING TENANT/AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED WITH THE APPROVAL OF THE ENGINEER IN CONSULTATION WITH THE AIRPORT DIRECTOR OF OPERATIONS. HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT DIRECTOR OF OPERATIONS.
7. DUE TO SEVERAL CONFLICTING EVENTS SCHEDULED FOR LATE JULY/EARLY AUGUST ON THE AIRFIELD, THE AIRPORT REQUESTS THAT CONSTRUCTION BEGIN IN LATE AUGUST OR LATER.

**1. COORDINATION**

1. PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ATTEND A PRE-CONSTRUCTION CONFERENCE WITH THE AIRPORT, RESIDENT ENGINEER, AND ILLINOIS DIVISION OF AERONAUTICS (IDA). THE COST OF PREPARING FOR AND ATTENDING THE PRE-CONSTRUCTION CONFERENCE SHALL BE INCIDENTAL TO THE CONTRACT.
2. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT A PROGRESS SCHEDULE TO BE APPROVED BY THE ENGINEER. THIS SCHEDULE SHALL SHOW START/ STOP DATES OF ALL PHASES. THE APPROVED PROGRESS SCHEDULE SHALL BE DISTRIBUTED TO ALL PARTIES 10 WORKING DAYS PRIOR TO START OF CONSTRUCTION. THE CONTRACTOR MAY BE REQUIRED TO SUBMIT A REVISED PROGRESS SCHEDULE TO ACCOMMODATE AIRPORT EVENTS OR CONTRACTOR'S LACK OF PROGRESS. SHOULD A REVISED SCHEDULE BE REQUIRED, THE REVISION SHALL BE COMPLETED AT NO ADDITIONAL COST TO THE CONTRACT.
3. DURING CONSTRUCTION THE CONTRACTOR SHALL ATTEND A WEEKLY COORDINATION MEETING WITH AIRPORT STAFF, FAA, RESIDENT ENGINEER AND OTHER APPROPRIATE STAKE HOLDERS TO DISCUSS PROJECT PROGRESS. AT A MINIMUM, PROJECT SCHEDULE AND GATE VISITOR LOGS SHALL BE DISCUSSED. REPRESENTATION BY THE PRIME CONTRACTOR IS MANDATORY. ALL COSTS ASSOCIATED WITH ATTENDING THE WEEKLY MEETING SHALL BE INCIDENTAL TO THE CONTRACT.

**2. PHASING**

1. TOTAL CONTRACT TIME SHALL BE 28 CALENDAR DAYS. SHOULD ALL THREE ADDITIVE ALTERNATES BE AWARDED, THE CONTRACT TIME SHALL BE 40 CALENDAR DAYS.
2. PHASING SHALL BE AS NOTED BELOW AND AS SHOWN ON THE CONSTRUCTION SAFETY AND PHASING PLANS.
3. TO CLOSE A RUNWAY OR TAXIWAY, THE CONTRACTOR SHALL PLACE RUNWAY AND TAXIWAY CLOSURE MARKERS AND BARRICADES AT THE LOCATIONS SPECIFIED. TO RE-OPEN THE RUNWAY OR TAXIWAY, THE CONTRACTOR SHALL CLEAN ANY DEBRIS OFF OF THE PAVEMENT AND REMOVE THE RUNWAY/TAXIWAY CLOSURE MARKERS. ALL WORK ASSOCIATED WITH CLOSING AND OPENING AIRFIELD PAVEMENTS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
4. CONTRACTOR SHALL COVER ALL AIRFIELD SIGNS AND LIGHTS ON CLOSED TAXIWAYS UNTIL THE TAXIWAY IS REOPENED FOR AIRCRAFT USE. THE METHOD AND MATERIALS USED TO COVER THE SIGNS AND LIGHTS SHALL MEET THE ENGINEER'S AND AIRPORT'S APPROVAL.
5. SEE CONTRACTOR ACCESS NOTES ON THIS SHEET FOR SITE ACCESS AND HAULING GUIDELINES.
6. PRIOR TO REOPENING A CLOSED RUNWAY OR TAXIWAY, THE ENTIRE RUNWAY SAFETY AREA (RSA), MEASURED 250 FEET FROM THE RUNWAY CENTERLINE, INCLUDING BEYOND THE RUNWAY END WITHIN THE EXTENDED RSA, AND THE ENTIRE TAXIWAY OBJECT FREE AREA (TOFA), MEASURED 85.5 FEET FROM GROUP III TAXIWAYS (I.E. TAXIWAY C AND G) MUST MEET FAA CRITERIA. FAA CRITERIA REQUIRES THAT THERE BE NO OPEN EXCAVATIONS OR TRENCHES IN THESE AREAS. THE MAXIMUM PAVEMENT DROP OFF SHALL BE 3 INCHES, AND ALL GRADES IN ANY DIRECTION BE LESS THAN 3 PERCENT. STEEL PLATES OR TEMPORARY WEDGING OF BASE COURSE MAY BE REQUIRED TO MEET CRITERIA. ALL NECESSARY TEMPORARY MEASURES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
7. NO MATERIAL OR EQUIPMENT SHALL BE STOCKPILED WITHIN AN RSA, ROFA OR OBSTACLE FREE ZONE (OFZ) OF AN ACTIVE RUNWAY, OR WITHIN THE TOFA OF AN ACTIVE TAXIWAY.

**8. WORK AREAS AND DESCRIPTIONS**

**MOBILIZATION**

SUBSTANTIALLY COMPLETE MOBILIZATION DURING THE MOBILIZATION TIME PERIOD.

**PHASE 1 AREA**

THIS WORK GENERALLY INCLUDES, BUT IS NOT LIMITED TO, REMOVAL AND REPLACEMENT OF CONCRETE PAVEMENT, ASPHALT TREATED PERMEABLE BASE COURSE, AGGREGATE BASE COURSE, PCC DIAMOND GRINDING MILLING, PAVEMENT MARKING WITHIN THE TOFA OF TAXIWAY W BETWEEN TAXIWAY W1 AND W2, TAXIWAY G BETWEEN TAXIWAY F AND W, AND TAXIWAY L.

**PHASE 2 AREA**

THIS WORK GENERALLY INCLUDES, BUT IS NOT LIMITED TO, REMOVAL AND REPLACEMENT OF CONCRETE PAVEMENT, ASPHALT TREATED PERMEABLE BASE COURSE, BITUMINOUS PAVEMENT MILL AND OVERLAY, PCC DIAMOND GRINDING, AND PAVEMENT MARKING WITHIN THE ROFA OF RUNWAY 2R/20L AND THE TOFA OF TAXIWAY C BETWEEN TAXIWAY Z AND TAXIWAY G.

**PHASE 3 AREA**

THIS WORK GENERALLY INCLUDES, BUT IS NOT LIMITED TO, REMOVAL AND REPLACEMENT OF CONCRETE PAVEMENT, ASPHALT TREATED PERMEABLE BASE COURSE AND PAVEMENT MARKING WITHIN THE ROFA OF RUNWAY 2L/20R.

**9. WORK AREA RESTRICTIONS**

**GENERAL (ALL WORK AREAS)**

ALL WORK ON THE AIRFIELD ARE LOCATED INSIDE THE AOA SECURITY FENCE, AND ARE SUBJECT TO THE LIMITATIONS DESCRIBED IN SPECIFICATIONS, PART 1 - GENERAL PROVISIONS.

WORK CONDUCTED UTILIZING EXTENDED AIRFIELD PAVEMENT CLOSURES AS INDICATED IN THE PLANS WILL ALLOW THE CONTRACTOR TO CONDUCT WORK 24 HOURS A DAY, 7 DAYS A WEEK. THE CLOSURE WILL ALLOW THE CONTRACTOR TO COMPLETE ALL WORK INSIDE THE RESPECTIVE RSA/TOFA, AND TO A DISTANCE OUTSIDE THESE AREAS AS TO NOT TO RE-ENCROACH THE RSA/TOFA WITH MANPOWER OR EQUIPMENT ONCE THE CLOSURE PERIOD IS CONCLUDED.

SIMULTANEOUS CLOSURES OF AIRFIELD PAVEMENTS TO COMPLETE WORK IN MORE THAN ONE WORK AREA AT A TIME WILL NOT BE ALLOWED UNLESS SPECIFICALLY STATED. ALL WORK WITHIN A WORK AREA MUST BE SUBSTANTIALLY COMPLETED AND ACCEPTED PRIOR TO CLOSING ANY OTHER AIRFIELD PAVEMENT FOR WORK IN REMAINING ASSOCIATED WORK AREAS.

CONTRACTOR SHALL NOTIFY THE AIRPORT 10 CALENDAR DAYS PRIOR TO BEGINNING CONSTRUCTION IN ANY WORK AREA AND TO REQUEST A RUNWAY OR TAXIWAY CLOSURE.

TOTAL COMBINED WORK FOR ALL WORK AREAS MUST OCCUR WITHIN THE TOTAL AMOUNT OF CALENDAR DAYS ALLOWED FOR THE ENTIRE PROJECT. HOWEVER, EXPEDITED CLOSURE PERIODS FOR CERTAIN WORK AREAS ARE NOTED BELOW.

**PHASE 1 AREA**

THIS PHASE WILL REQUIRE CLOSURES ON TAXIWAY W BETWEEN TAXIWAY W1 AND TAXIWAY W2, TAXIWAY Y BETWEEN RUNWAY 2L/20R AND THE FLIGHT CENTER APRON, TAXIWAY G BETWEEN TAXIWAY W AND RUNWAY 2L/20R, AND TAXIWAY L TO ITS EXTENTS.

TAXIWAY Y AND TAXIWAY L MAY NOT BE CLOSED AT THE SAME TIME.

RUNWAY 2R/20L, RUNWAY 2L/20R, RUNWAY 10-28, AND RUNWAY 15-33 SHALL REMAIN OPEN FOR THE DURATION OF PHASE 1. ALL OTHER TAXIWAYS SHALL REMAIN OPEN.

**PHASE 2 AREA**

AN EXTENDED CLOSURE OF RUNWAY 2R/20L IS REQUIRED TO COMPLETE WORK WITHIN THE ROFA OF RUNWAY 2R/20L, IN ADDITION TO CLOSURES ON TAXIWAY C BETWEEN TAXIWAY Z AND TAXIWAY G, AND TAXIWAYS T,Y, AND Z BETWEEN RUNWAY 2R/20L AND 2L/20R IN ORDER TO COMPLETE WORK WITHIN THE TOFA.

THE CLOSURE OF RUNWAY 2R/20L SHALL BE LIMITED TO A 4-CALENDAR DAY DURATION BEFORE RE-OPENING TO AIRCRAFT OPERATION AND MUST OCCUR WITHIN THE CONTRACT TIME ALLOWED FOR THE ENTIRE PROJECT.

RUNWAY 2L/20R, RUNWAY 10-28, AND RUNWAY 15-33 SHALL REMAIN OPEN FOR THE DURATION OF PHASE 2. ALL OTHER TAXIWAYS SHALL REMAIN OPEN.

**PHASE 3 AREA**

AN EXTENDED CLOSURE OF RUNWAY 2L/20R IS REQUIRED TO COMPLETE THE WORK WITHIN THE ROFA OF RUNWAY 2L/20R, IN ADDITION TO CLOSURES ON TAXIWAY W BETWEEN TAXIWAY Z AND TAXIWAY Y. CLOSURES OF PAVEMENT FOR PHASE 3 SHALL BE LIMITED TO A 6-CALENDAR DAY DURATION BEFORE RE-OPENING TO AIRCRAFT OPERATION AND MUST OCCUR WITHIN THE CONTRACT TIME ALLOWED FOR THE ENTIRE PROJECT.

RUNWAY 2R/20L, RUNWAY 10-28, AND RUNWAY 15-33 SHALL REMAIN OPEN FOR THE DURATION OF PHASE 1. ALL OTHER TAXIWAYS SHALL REMAIN OPEN.

**3. AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY**

1. ALL RUNWAYS, TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE PHASING PLAN.
2. THE ENGINEER AND AIRPORT DIRECTOR OF OPERATIONS OR HIS DESIGNATED REPRESENTATIVE SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING SEQUENCE AS IT RELATES TO PEDESTRIAN, VEHICULAR AND AIRCRAFT OPERATIONS. AIRCRAFT OPERATIONS HAVE THE RIGHT-OF-WAY ON THE AIRFIELD. VEHICULAR TRAFFIC AND CONTRACTOR ACTIVITIES SHALL YIELD TO AIRCRAFT OPERATIONS. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE EQUIPMENT AT ANY TIME TO ALLOW AN AIRCRAFT TO PASS, THE CONTRACTOR SHALL DO SO IMMEDIATELY AT NO EXTRA COST TO THE OWNER.

**4. NAVAIDS THAT COULD BE AFFECTED**

1. THE CONTRACTOR MUST COORDINATE WITH AIRPORT OPERATIONS/ENGINEER AND FAA A **MINIMUM OF 30 DAYS** IN ADVANCE FOR ANY WORK WITHIN A NAVAID CRITICAL AREA OR AFFECTING THE VISUAL, TRANSMITTED SIGNAL OR POWER SUPPLY OF A NAVAID. RUNWAY 20R FEATURES A FAA OWNED SET OF PAPI LIGHTS. IF ADDITIVE ALTERNATE NO. 1 IS AWARDED, THE CONTRACTOR MUST COORDINATE WITH THE FAA BEFORE THE RUNWAY CAN BE CLOSED FOR PHASE 3 OF THE PROJECT.
2. EDGE LIGHTS, THRESHOLD LIGHTS, VISUAL AIDS AND ALL ILS EQUIPMENT SHALL BE SHUT OFF FOR THE DURATION OF A CLOSURE PERIOD ON ANY ASSOCIATED PAVEMENTS. IF THE LIGHTING CIRCUIT MUST BE ON FOR OPEN PAVEMENT AREAS, CLOSED PAVEMENT AREA LIGHTS SHALL BE COVERED COMPLETELY.
3. EXCEPT WHERE NOTED IN THE PLANS, EXISTING COMMUNICATIONS EQUIPMENT AND NAVIGATIONAL AIDS (NAVAIDS) SHALL NOT BE DISTURBED BY THE CONTRACTOR AND SHALL BE PROTECTED FROM DAMAGE.
4. PRIOR TO BEGINNING SITE WORK, CONTRACTOR SHALL COORDINATE THROUGH AIRPORT OPERATIONS TO LOCATE, AND THE CONTRACTOR TO MARK ALL UNDERGROUND COMMUNICATIONS CABLES AND FACILITIES, WITHIN THE PROJECT AREA.
5. IF CONTRACTOR CAUSES INTERRUPTION OF POWER OR COMMUNICATIONS TO A NAVAID CONTRACTOR SHALL REPAIR WITHIN 24 HOURS AT THE CONTRACTOR'S COST. CONTRACTOR MUST COORDINATE REPAIR WITH AIRPORT OPERATIONS BEFORE ANY REPAIR IS MADE.
6. THE CONTRACTOR SHALL BE REQUIRED TO ESTABLISH A COORDINATION PLAN WITH THE AIRPORT DIRECTOR OF OPERATIONS OR HIS DESIGNATED REPRESENTATIVE, REGARDING DE-ENERGIZING AND ENERGIZING OF THE AIRFIELD LIGHTING CIRCUITS AT THE START AND END OF EACH CONSTRUCTION DAY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL AIRPORT OWNED UTILITIES AND SHALL BE DONE SO AT NO EXTRA COST TO THE CONTRACT.
7. ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER AIRPORT ELECTRICAL CABLES SHALL REMAIN IN SERVICE UNTIL REPLACED AS ACCEPTABLE TO THE RESIDENT ENGINEER AND AIRPORT FOR ALL PHASES. ALL TEMPORARY CABLING AND SPLICING NECESSARY TO KEEP THE CIRCUITS IN OPERATION SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
8. DURING CONSTRUCTION, CONTINUOUS ALL WEATHER ACCESS TO EXISTING NAVAIDS IN THE PROJECT AREA MUST BE MAINTAINED AT NO COST TO THE CONTRACT.



CONSULTANTS

100% FINAL  
JANUARY 12, 2024

REHAB AIRFIELD PAVEMENTS  
FED



OWNER

DUPAGE AIRPORT  
WEST CHICAGO, ILLINOIS

MARK | DATE | DESCRIPTION

AIP PROJ. NO.	
DPA 5065	
CMT PROJECT NO:	22004585.00
CAD DWG FILE:	22004585 - DPA - CSPP NOTES.DWG
DESIGNED BY:	AM
DRAWN BY:	JRO
CHECKED BY:	DKP
APPROVED BY:	DLP
COPYRIGHT:	

SHEET TITLE

CONSTRUCTION SAFETY  
AND PHASING PLAN  
GENERAL NOTES - 1

Path: K:\dupage\022004585\00\_RehabAirfieldPavements\FED\Draw Sheets\22004585 - dpa - cspp notes.dwg  
Date: Wednesday, January 31, 2024 2:34:38 PM

5. CONTRACTOR ACCESS

- 1. THE CONTRACTOR ACCESS ROAD AND STAGING AREAS SHALL BE AS SHOWN ON THE REFERENCED PLAN. THE CONTRACTOR SHALL MAINTAIN AND REPAIR THE CONSTRUCTION ACCESS ROAD AND STAGING AREA IN ITS ORIGINAL CONDITION AT NO ADDITIONAL COST TO THE CONTRACT. ALTERNATE STAGING AREAS AND ACCESS FOR THIS AREA WILL NOT BE ALLOWED.
2. THE ENTRANCE SHALL BE SIGNED ACCORDINGLY AS TO ALLOW ONLY CONSTRUCTION VEHICLE ACCESS AND WILL ONLY BE ACCESSIBLE DURING THE CONTRACTOR'S SCHEDULED WORK DAY. ALL SIGNAGE SHALL CONFORM TO THE CITY OF WEST CHICAGO AND IDOT CONSTRUCTION STANDARDS FOR VEHICLES ENTERING AND LEAVING THE SITE.
3. NOT USED.
4. CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND TEMPORARY EASEMENTS FOR THE PUBLIC ACCESS ROAD(S) SHOWN AND SHALL COMPLY WITH ALL REQUIREMENTS, LOAD RESTRICTIONS, & TRAFFIC CONTROL SIGNAGE REQUIRED BY THE CITY, COUNTY, TOWNSHIP, OR I.D.O.T.
5. THE CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS AND HAVE BEACON (FLASHING YELLOW) LIGHTS ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION.
6. NOT USED.
7. NOT USED.
8. THE CONTRACTOR'S MATERIAL AND EQUIPMENT, WHEN NOT IN USE, SHALL BE STORED IN THE CONTRACTOR'S STAGING AREA. ALL DELIVERIES, EQUIPMENT REFUELING, EQUIPMENT MAINTENANCE AND EQUIPMENT TRANSFERS SHALL TAKE PLACE WITHIN THE CONTRACTOR'S STAGING AREA.
9. DURING ADVERSE WEATHER THE CONTRACTOR SHALL MAINTAIN ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF THE CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK SITE.
10. THE CONTRACTOR WILL BE PERMITTED TO STORE EQUIPMENT AND MATERIALS ONLY AT THE LOCATIONS SHOWN. PARKED EQUIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE SURFACES DEFINED BY F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE. EXISTING TURF AREAS DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM/HER AT HIS/HER EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE AIRPORT.
11. ALL CONSTRUCTION TRAFFIC OPERATING ON, OR CROSSING RUNWAYS, TAXIWAYS AND APRONS OPEN TO AIRCRAFT TRAFFIC SHALL BE UNDER CONTROL BY A FLAGMAN OR ESCORT IN RADIO CONTACT WITH THE CONTROL TOWER. THE CONTRACTOR SHALL PROVIDE HIS OWN FLAGMAN.
12. IF NECESSARY, THE CONTRACTOR SHALL CONSTRUCT A HAUL ROUTE TO THE STAGING AREA WITHIN THE PROJECT LIMITS. HAUL ROUTE(S) SHALL BE INCIDENTAL TO THE COST OF MAINTENANCE OF TRAFFIC. ALL HAUL ROUTE(S) INCLUDING EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE ENGINEER AND AIRPORT DIRECTOR OF OPERATIONS. THE COST OF MAINTAINING, REPAIRING SEEDING /MULCHING OR CONSTRUCTING THESE HAUL ROUTE(S) SHALL BE INCIDENTAL TO THE COST OF THE CONTRACT.

- 13. ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A STAGING AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE ENGINEER AND AIRPORT OPERATION MANAGER. THE COST OF MAINTAINING, REPAIRING SEEDING /MULCHING OR CONSTRUCTING THESE PAVEMENTS / AREAS SHALL BE INCIDENTAL TO THE CONTRACT.
14. ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR SHALL BE PROPERLY TRAINED BY THE CONTRACTOR.
15. THE CONTRACTOR SHALL NOTIFY THE AIRPORT IF CONSTRUCTION ACTIVITY WILL REQUIRE THE BLOCKAGE OF EMERGENCY ACCESS TO THE AIRPORT.
16. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE DUST CONTROL AT ALL TIMES DURING THE PROJECT DURATION. A WATER TRUCK SHALL BE REQUIRED TO BE ON SITE DURING ALL CONSTRUCTION OPERATION WORKING HOURS. PAYMENT FOR DUST CONTROL SHALL BE INCIDENTAL TO THE CONTRACT.

6. WILDLIFE MANAGEMENT

- 1. THE CONTRACTOR SHALL NOTIFY THE AIRPORT OR THE RESIDENT ENGINEER IF ANY WILDLIFE IS SEEN ENTERING THE AIRPORT.
2. CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE CONTRACTOR IS NOT WORKING.
3. THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING FOOD SCRAPS IN APPROVED CONTRACTOR PROVIDED CONTAINERS.

7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

- 1. THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS (FOD) SEEN ON THE AIRFIELD PAVEMENTS.
2. THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES PRIOR TO DRIVING ON AIRFIELD PAVEMENTS.
3. THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE EXISTING PAVEMENT OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE ENGINEER. SHOULD THE CONTRACTOR TRACK ANY DEBRIS ONTO EXISTING PAVEMENTS, THIS DEBRIS SHALL BE REMOVED IMMEDIATELY WITH A PICK UP SWEEPER. A PICK UP SWEEPER SHALL BE REQUIRED TO BE ON SITE AND OPERATE DURING ALL CONSTRUCTION OPERATION WORKING HOURS, UNLESS WAIVED BY THE DEPUTY DIRECTOR OF OPERATIONS. THE CONTRACTOR SHALL PROVIDE WASTE RECEPTACLES THROUGHOUT THE WORK ZONE AND MAINTAIN SANITARY FACILITIES FOR EMPLOYEES TO USE. FACILITIES WITHIN THE HANGARS/AIRPORT BUILDINGS SHALL NOT BE USED.

8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT

- 1. THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA SHEETS (MSDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE.

9. NOTIFICATION OF CONSTRUCTION ACTIVITIES

- 1. THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT PERSON AND PHONE NUMBER. PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARRICADES.
2. THE CONTRACTOR SHALL GIVE A MINIMUM OF 10 DAYS NOTICE TO THE FAA AND AIRPORT PRIOR TO THE CLOSURE OF ANY RUNWAY SO THAT THE FAA MAY DEACTIVATE THE FAA - OWNED NAVAIDS.
3. THE CONTRACTOR SHALL GIVE A MINIMUM 30 DAYS NOTICE TO THE AIRPORT, AND PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, PRIOR TO CLOSING ANY RUNWAY OR TAXIWAY PAVEMENT SO THAT THE PROPER NOTAMS MAY BE ISSUED BY THE AIRPORT FOR COORDINATION WITH THE AIRPORT TENANTS.
4. FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT GREATER THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT THE TYPE OF EQUIPMENT, TOTAL HEIGHT, AND LOCATION WHERE THE EQUIPMENT WILL BE USED. THE AIRPORT WILL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY. NO EQUIPMENT WITH A HEIGHT GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS RECEIVED.
5. IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL NOTIFY THE AIRPORT DIRECTOR OF OPERATIONS AND THE RESIDENT ENGINEER.

10. INSPECTION REQUIREMENTS

- 1. THE CONTRACTOR SHALL INSPECT THE JOBISTE DAILY TO ENSURE COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX 3 OF FAA AC 150/5370-2G OR LATEST EDITION MAY BE USED TO AID IN THE INSPECTIONS.
2. THE CONTRACTOR SHALL REQUEST OPERATIONAL INSPECTION OF EACH PHASE WORK AREA PRIOR THE AREA BEING REOPENED. THE AIRPORT WILL DETERMINE IF THE WORK AREA IS ALLOWED TO BE OPENED.

11. UNDERGROUND UTILITIES

- 1. COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED. SEE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHAT SO EVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY/OWNER OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE OWNER AND THE ENGINEER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER AND THE ENGINEER.
2. SHOULD A UTILITY COMPANY OR GOVERNMENT AGENCY BE UNABLE TO LOCATE FACILITIES, THE CONTRACTOR SHALL LOCATE THESE FACILITIES. PAYMENT FOR THIS LOCATION SHALL BE INCIDENTAL TO THE IMPROVEMENTS REQUIRING THE LOCATIONS.
3. NOT USED.
4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY/OWNER OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE OWNER AND THE ENGINEER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER AND THE ENGINEER.

12. PENALTIES

- 1. NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT RULES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT IN FINES AS ALLOWED BY LAW.
2. BECAUSE OF THE CRITICAL LIMITATIONS WHICH THE CLOSURE OF A RUNWAY PLACES ON THE USERS OF THE AIRPORT, LIQUIDATED DAMAGES IN THE AMOUNT OF \$2,500 MAY BE DEDUCTED FROM THE MONIES OWED THE CONTRACTOR. FOR EACH HALF HOUR PAST 6:00 A.M. OVER THE CLOSURE PERIODS FOR THE PHASE 3 UNTIL THE SPECIFIED WORK IS COMPLETED AND THE ASSOCIATED RUNWAY IS OPENED TO AIRCRAFT OPERATIONS. DAMAGES MAY BE ASSESSED STARTING IMMEDIATELY AFTER EACH OF THE CLOSURE PERIODS WHEN EITHER RUNWAY IS NOT OPENED. THESE ASSESSED DAMAGES ARE IN ADDITION TO THE DEDUCTIONS FOR EACH DAY OF OVERRUN IN TOTAL CONTRACT TIME AS DEFINED IN SECTION 80, PROSECUTION AND PROGRESS, OF THE CONTRACT DOCUMENTS. SEE CONSTRUCTION ACTIVITY PLAN NOTES AND DETAILS FOR MORE INFORMATION ON RUNWAY AND TAXIWAY CLOSURES.
3. THE CONTRACTOR SHALL RESTRICT ALL CONSTRUCTION ACTIVITIES TO THE CONSTRUCTION AREA DETAILED IN THE CONSTRUCTION SAFETY AND PHASING PLAN. ANY UNAUTHORIZED MOVEMENTS, PEDESTRIAN OR VEHICULAR, BEYOND THE CONSTRUCTION LIMITS SHOWN SHALL BE CONSIDERED AND AIRFIELD INCURSION. AIRFIELD INCURSIONS, AT THE DISCRETION OF THE AIRPORT DIRECTOR OF AVIATION, MAY BE FINED UP TO \$1,000 PER INCIDENT. INCURSION FINES WILL BE ASSESSED IMMEDIATELY AND TAKEN FROM MONIES DUE THE CONTRACTOR ON THE NEXT CONSTRUCTION PAYMENT.

13. SPECIAL CONDITIONS

- 1. ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE CONTRACTOR. SEE THE COORDINATION NOTES FOR ADDITIONAL INFORMATION.

14. RUNWAY AND TAXIWAY VISUAL AIDS

- 1. ALL RUNWAYS, TAXIWAYS, AND APRONS SHALL BE KEPT OPEN TO AIRPORT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED IN THE CONSTRUCTION SAFETY AND PHASING PLAN.
2. IF ANY RUNWAY OR TAXIWAY CLOSURES ARE REQUESTED BY THE CONTRACTOR AND APPROVED BY THE AIRPORT, THE CONTRACTOR SHALL USE MARKING, LIGHTING AND SIGNS THAT FOLLOWING THE REQUIREMENTS OF FAA AC 150/5370-2G OR LATEST EDITION.

15. MARKING AND SIGNS FOR ACCESS ROUTES

- 1. BARRICADES AND SIGNS SHALL BE USED ALONG THE CONTRACTOR'S ACCESS ROUTE AS DETAILED ON THE CONSTRUCTION SAFETY AND PHASING PLAN.

16. HAZARD MARKING AND LIGHTING

- 1. THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS AND ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS, TEMPORARY STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT.
2. ALL CONSTRUCTION EQUIPMENT SHALL BE FLAGGED AND/OR LIGHTED IN ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2G AND 150/5210-5C OR LATEST EDITION AT ALL TIMES WHILE OPERATING ON AIRPORT PROPERTY. THE MAXIMUM EQUIPMENT HEIGHT IS 25'.
3. BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET OR AS DIRECTED BY THE ENGINEER.
4. THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED LIGHTS AND FLAG PLACEMENT.
5. PAYMENT FOR ALL AIRSIDE AND ROADWAY TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO, TEMPORARY CONSTRUCTION FENCING, BARRICADES, SIGNING, AIR OPERATIONS AREA (A.O.A.) LATH AND RIBBON, ETC. SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. BARRICADES USED ON THE AIRFIELD MUST BE INTERLOCKING LOW PROFILE BARRICADES. INTERLOCKING LOW PROFILE BARRICADES WITH STEADY BURN RED LIGHTS SHALL BE INTERLOCKED WITH NO GAPS BETWEEN BARRICADES. BARRICADES SHALL BE PLACED AS SHOWN ON THIS PLAN AND AS DIRECTED BY THE ENGINEER FOR WORK ADJACENT TO THE EXPEDITED WORK AREA. WHEN NOT IN USE, THESE BARRICADES SHALL BE STORED AT THE CONTRACTOR'S STAGING AREA OR OFF SITE. ACCESS TO THE ACTIVE RUNWAY AND TAXIWAY PAVEMENTS (TOWER CONTROLLED AREAS) SHALL BE SIGNED WITH STOP SIGNS MOUNTED ON THE CLOSEST BARRICADES (2 EACH, RIGHT AND LEFT) AT THE ENTRANCE. IN ADDITION TO THE STOP SIGNS, WARNING SIGNS (2 EACH, RIGHT AND LEFT) SHALL BE MOUNTED. WARNING SIGNS SHALL STATE "TOWER CONTROL AREA / UNAUTHORIZED ACCESS SUBJECT TO FINE." ALL NON AIRFIELD LOCATIONS REQUIRING BARRICADES SHALL BE TYPE II OR TYPE III BARRICADES AND SHALL CONFORM TO IDOT STANDARD DETAIL 701901-04.

17. WORK ZONE LIGHTING FOR NIGHTTIME CONSTRUCTION

- 1. WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL AREA LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTION.
2. LIGHTS SHALL CONSIST OF VEHICLE OR MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE. LIGHTING SHALL NOT INTERFERE WITH AIR OPERATIONS. ANY WORK BEING PERFORMED UNDER INSUFFICIENT ARTIFICIAL LIGHTING, IN THE RESIDENT ENGINEER'S JUDGEMENT, SHALL BE STOPPED UNTIL SUCH TIME AS ADDITIONAL LIGHTING IS PROVIDED. ALL WORK PERFORMED DURING THAT TIME WILL NOT BE ACCEPTABLE UNTIL PROPER INSPECTION AND TESTING CAN BE MADE.

18. PROTECTION

- 1. ALL WORK REQUIRED INSIDE OF A RUNWAY SAFETY AREA, WILL REQUIRE THE RUNWAY TO BE CLOSED.
2. ALL WORK REQUIRED ON AN ACTIVE TAXIWAY OR INSIDE OF AN ACTIVE TAXIWAY OBJECT FREE AREA, WILL REQUIRE THE TAXIWAY TO BE CLOSED.

19. OTHER LIMITATIONS ON CONSTRUCTION

- 1. IF, DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE AIRPORT, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL VEHICLES, PERSONNEL AND EQUIPMENT.
2. BROKEN CONCRETE, BROKEN ASPHALT, RUBBISH FROM DEMO, AND OTHER MISCELLANEOUS DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS OTHERWISE SPECIFIED.
3. THE CONTRACTOR WILL BE RESPONSIBLE FOR COORDINATING THE AIRSPACE FOR THE CONSTRUCTION EQUIPMENT THAT IS TALLER THAN THAT SPECIFIED ON THE PLANS WITH THE FAA. THIS PROCESS MAY TAKE UP TO 12 WEEKS TO COMPLETE.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEGGAR TESTING ALL EXISTING CIRCUITS PRIOR TO CONSTRUCTION AND FOLLOWING CONSTRUCTION AS SPECIFIED IN THE CONTRACT DOCUMENTS.



CONSULTANTS

100% FINAL
JANUARY 12, 2024
REHAB AIRFIELD PAVEMENTS
FED



OWNER

DUPAGE AIRPORT
WEST CHICAGO, ILLINOIS

MARK DATE DESCRIPTION

Table with project details: AIP PROJ. NO., DPA 5065, CMT PROJECT NO.: 22004585.00, CAD DWG FILE: 22004585 - DPA - CSPP NOTES.DWG, DESIGNED BY: AM, DRAWN BY: JRO, CHECKED BY: DKP, APPROVED BY: DLP, COPYRIGHT:

SHEET TITLE
CONSTRUCTION SAFETY
AND PHASING PLAN
GENERAL NOTES - 2







CONSULTANTS

100% FINAL  
JANUARY 12, 2024  
REHAB AIRFIELD PAVEMENTS  
FED




OWNER

DUPAGE AIRPORT  
WEST CHICAGO, ILLINOIS

MARK	DATE	DESCRIPTION

AIP PROJ. NO.	DPA 5065
CMT PROJECT NO:	22004585.00
CAD DWG FILE:	22004585 - DPA - REPAIR PLAN.DWG
DESIGNED BY:	AM
DRAWN BY:	JRO
CHECKED BY:	DKP
APPROVED BY:	DLP
COPYRIGHT:	



SHEET TITLE  
**REHABILITATE  
RUNWAY 2L-20R - 1**








Path: K:\dupage\A022004585-00\_RehabAirfieldPavements\FED\Draw\Shores\22004585 - dpa - repair plan.dwg  
Date: Wednesday, January 31, 2024 11:17:27 AM



Path: K:\dupage\A9\22004585\00\_RehabAirfieldPavements\FED\Draw\Shrines\22004585-dpa-repair-plan.dwg  
 Date: Wednesday, January 31, 2024 11:20:13 AM



SEE SHEET 9 FOR  
LEGEND AND NOTES



CONSULTANTS

100% FINAL  
 JANUARY 12, 2024  
 REHAB AIRFIELD PAVEMENTS  
 FED



OWNER

DUPAGE AIRPORT  
 WEST CHICAGO, ILLINOIS

MARK	DATE	DESCRIPTION
AIP PROJ. NO.		DPA 5065
CMT PROJECT NO.:		22004585.00
CAD DWG FILE:		22004585 - DPA - REPAIR PLAN.DWG
DESIGNED BY:		AM
DRAWN BY:		JRO
CHECKED BY:		DKP
APPROVED BY:		DLP
COPYRIGHT:		

SHEET TITLE  
**REHABILITATE  
 TAXIWAY C - 1**

AREA 9 - BASE BID

SHEET 12 OF 20

BASE BID







CONSULTANTS

100% FINAL  
JANUARY 12, 2024  
REHAB AIRFIELD PAVEMENTS  
FED



OWNER



DUPAGE AIRPORT  
WEST CHICAGO, ILLINOIS

MARK | DATE | DESCRIPTION

AIP PROJ. NO.	DPA 5065
CMT PROJECT NO:	22004585.00
CAD DWG FILE:	22004585 - DPA - REPAIR PLAN.DWG
DESIGNED BY:	AM
DRAWN BY:	JRO
CHECKED BY:	DKP
APPROVED BY:	DLP
COPYRIGHT:	

SHEET TITLE  
**REHABILITATE  
TAXIWAY W, L AND G**

SHEET 15 OF 20



Path: K:\dupage\AIP\22004585.00\_RehabAirfieldPavements\FED\Draw\Shrines\22004585 - dpa - repair plan.dwg  
Date: Wednesday, January 31, 2024 11:23:38 AM

AREA 11 - BASE BID

AREA 13 - BASE BID

BASE BID











