

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE			
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2	2			
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2			
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	7	7			
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	11	11			
60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	15	15			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	59	59			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	160	160			
60624600	CORRUGATED MEDIAN	SO FT	246	246			
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	168	168			
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	7	7			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
6700100	MOBILIZATION	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	8556	8556			
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	4621	4621			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	1038	1038			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41501	41501			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5913	5913			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	596	596			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1203	1203			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	827	827			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	4278	4278			

FILE NAME =	USER NAME = <i>bligramis</i>	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>		F.A.P. RTE. 350	SECTION 50 & 57RS-1	COUNTY	TOTAL SHEETS 80	SHEET NO. 5
OFFICE =	PROJECT =	CHECKED -	REVISED -				CONTRACT NO. 62C95				
PLOT SCALE = 1/8" = 1'-0"	DATE =	REVISED -	REVISED -				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
PLOT DATE = 12/15/2017	DATE =	REVISED -	REVISED -				SCALE: SHEET NO. OF SHEETS STA. TO STA.				