

steffenmk
12/3/2004
c:\projects\74047\d02804pa.dgn
SOQ

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	(4-2)RS-3	LAWRENCE	12	3
FED. ROAD DIST. NO. 7		BLINDS	FED. AID PROJECT NO.	

CONTRACT NO. 74047

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 80% FED 20% STATE		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	4	4		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3525	3525		
40600300	AGGREGATE (PRIME COAT)	TON	71	71		
40600990	TEMPORARY RAMP	SQ YD	40	40		
44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	5432	5432		
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	1620	1620		
44004250	PAVED SHOULDER REMOVAL	SQ YD	2116	2116		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	330	330		
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	98	98		
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	140	140		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	11	11		
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	139	139		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	837	837		
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	593	593		
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	2116	2116		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	3	3		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2	2		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3174	3174		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24672	24672		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	353	353		
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	24672	24672		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	134	134		
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	2370	2370		
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	3555	3555		
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	20	20		
X4409420	BITUMINOUS SURFACE REMOVAL 3 1/4"	SQ YD	21727	21727		
X4409425	BITUMINOUS SURFACE REMOVAL 4 1/4"	SQ YD	6480	6480		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY
OF
QUANTITIES**

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY