

PIPE UNDERDRAINS, 4"

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	**	189	26
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* X1-2,44(2,3,4)RS,BSMARTFY04-4				
** WILLIAMSON/JOHNSON				
CONTRACT NO.: 98758				

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL & REPLACEMENT 8"	STONE RIPRAP CLASS A2		COMMENTS
					INFO ONLY	PAY ITEM	
					LENGTH	TON	
FOOT	FOOT	FOOT	EACH	FOOT	FOOT	TON	
EB LANES							
RT (OUTSIDE SHOULDER)							
268 + 20 TO 277 + 90 (MP 12.5)	970				970		
268 + 20		16	1		9		
273 + 05		16	1		9		
290 + 40 TO 320 + 50 (MP 13.4)	3,010				3,010		
295 + 40		16	1		9		
300 + 40		16	1		9		
305 + 40		16	1		9		
310 + 40		16	1		9		
315 + 40		16	1		9		
320 + 50		16	1		9		
LT (MEDIAN SHOULDER)							
134 + 80 TO 148 + 00 (MP 2.0)	1,320				1,320		CONNECTS TO THE LAST UNDERDRAIN IN WILLIAMSON CO.
135 + 08		12	1		5		
140 + 08		12	1		5		
145 + 08		12	1		5		
148 + 00		12	1		5		
GAP STRUCTURE # 044 - 0029							
155 + 00 TO 159 + 80 (MP 2.3)	480				480		
155 + 00		12	1		5		
172 + 25 TO 219 + 00 (MP 3.4)	4,675				4,675		
172 + 25		12	1		5		
177 + 25		12	1		5		
182 + 25		12	1		5		
187 + 25		12	1		5		
192 + 25		12	1		5		
197 + 25		12	1		5		
202 + 25		12	1		5		
207 + 25		12	1		5		
212 + 25		12	1		5		
217 + 25		12	1		5		
228 + 50 TO 271 + 00 (MP 4.4)	4,250				4,250		
232 + 50		12	1		5		
236 + 50		12	1		5		
240 + 50		12	1		5		
244 + 50		24	2		5		
248 + 90		12	1		5		SAG LOCATION
253 + 30		12	1		5		
257 + 70		12	1		5		
262 + 10		12	1		5		
266 + 50		12	1		5		
294 + 00 TO 310 + 00 (MP 5.2)	1,600				1,600		
298 + 00		12	1		5		
302 + 00		12	1		5		
305 + 50		24	2		5		SAG LOCATION
319 + 00 TO 326 + 00 (MP 5.5)	700				700		
319 + 00		12	1		5		
322 + 50		12	1		5		
338 + 00 TO 360 + 00 (MP 6.1)	2,200				2,200		
338 + 00		12	1		5		
342 + 50		12	1		5		
351 + 50		12	1		5		STA 347+00 IS A CREST
356 + 00		12	1		5		
360 + 00		12	1		5		
370 + 00 TO 382 + 00 (MP 6.5)	1,200				1,200		
372 + 50		12	1		5		
375 + 00		24	2		5	100	8 SAG LOCATION
378 + 50		12	1		5		
390 + 00 TO 401 + 00 (MP 6.8)	1,100				1,100		
390 + 00		12	1		5		
394 + 00		12	1		5	90	8
398 + 00		12	1		5		

Tuesday, November 16, 2004 8:24:53:17 PM
c:\projects\1102102\enr02\1102\enr02.dwg LV:2-18-28-03