

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	**	189	31
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\* X1-2,44(2,3,4)RS,BSMARTFY04-4  
 \*\* WILLIAMSON/JOHNSON  
 CONTRACT NO.: 98758

## PIPE UNDERDRAINS, 4"

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL & REPLACEMENT 8"	STONE RIPRAP CLASS A2		COMMENTS				
					FOOT	FOOT		EACH	FOOT	INFO ONLY	PAY ITEM
										LENGTH	TON
<b>WB LANES</b>											
<b>LT (OUTSIDE SHOULDER)</b>											
518 + 00 TO 524 + 83.61 BK (MP 9.2)	684				684						
102 + 46.58 AH TO 117 + 00 (MP 9.5)	1,453				1,453						
523 + 00		16	1		9	180	15				
105 + 63		16	1		9						
110 + 63		13	1		9	160	13				
115 + 50		26	2		9	80	7				
							SAG LOCATION				
135 + 20 TO 153 + 85 (MP 10.2)	1,865				1,865						
135 + 20		16	1		9						
140 + 20		16	1		9						
145 + 20		16	1		9						
150 + 20		16	1		9						
172 + 20 TO 187 + 05.29 (MP 10.8)	1,485				1,485						
177 + 20		16	1		9						
182 + 20		16	1		9						
187 + 00		16	1		9						
GAP STRUCTURE # 044 - 0038											
188 + 16.72 TO 199 + 00 (MP 11.1)	1,083				1,083						
193 + 50		13	1		9	120	10				
199 + 00		16	1		9						
228 + 00 TO 264 + 00 (MP 12.3)	3,600				3,600						
233 + 00		13	1		9	70	6				
238 + 00		13	1		9	110	9				
243 + 00		16	1		9	120	10				
248 + 00		16	1		9						
253 + 00		16	1		9						
258 + 00		32	2		9						
261 + 00		16	1		9						
							SAG LOCATION				
269 + 00 TO 278 + 80 (MP 12.6)	980				980						
269 + 00		16	1		9						
274 + 00		16	1		9						
290 + 40 TO 296 + 50 (MP 12.9)	610				610						
293 + 45		16	1		9						
296 + 50		16	1		9						
308 + 00 TO 320 + 50 (MP 13.4)	1,250				1,250						
312 + 00		16	1		9						
316 + 00		16	1		9						
320 + 50		16	1		9						
<b>JOHNSON CO.</b>											
<b>GOREVILLE/TUNNEL HILL INTERCHANGE</b>											
<b>LT (INSIDE SHOULDER)</b>											
<b>RAMP A</b>											
0 + 12.4 TO 0 + 96.14	84				84						
		12	1		9						
<b>RAMP B</b>											
10 + 66 TO 11 + 61	95				95						
		12	1		9						
<b>RAMP C</b>											
0 + 12.4 TO 0 + 94.68	83				83						
		12	1		9						
<b>RAMP D</b>											
10 + 23 TO 11 + 15.20	93				93						
		12	1		9						
<b>JOHNSON CO. TOTALS</b>		<b>155,221</b>	<b>4,902</b>	<b>358</b>	<b>157,590</b>		<b>359</b>				
<b>PROJECT TOTALS</b>		<b>180,655</b>	<b>5,590</b>	<b>407</b>	<b>183,369</b>		<b>398</b>				

NOTE: AT SAG LOCATIONS, BOTH PIPE UNDERDRAINS 4" (SPECIAL) SHALL BE MEASURED FOR PAYMENT.

Tuesday, November 16, 2004 @ 2:41:15 PM  
 c:\paw\secta\022102\022102\secta\022102\022102.ctb L:\2-10-20-03