

POLYURETHANE MATERIAL

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	**	189	33
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* X1-2,442,3,4IRS,BSMARTFY04-4				
** WILLIAMSON/JOHNSON				
CONTRACT NO.: 98758				

LOCATION STA TO STA (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	LANE	PAVEMENT			CULVERTS	POLYURETHANE MATERIAL	REMARKS
		WIDTH	LENGTH	MAX DEPTH	DEPTH		
		FEET	FEET	INCHES	FEET		
		INFO. ONLY			INFO. ONLY	POUND	
FAI 24							
WILLIAMSON CO.							
F. A. I. 24/F. A. I. 57 INTERCHANGE							
RAMP AC							
57+50 TO 57+75 (MP 1.1)	DRIVING	12	25	1.44		282	SN #100-0060 APPROACH - UNDERSEALING
57+50 TO 57+75 (MP 1.1)	PASSING	12	25	1.44		282	SN #100-0060 APPROACH - UNDERSEALING
64+35 TO 64+71 (MP 1.2)	DRIVING	12	36	0.60		259	ROADWAY UNDERSEALING
LT 57+00 (MP 1.1)					1	200	CULVERT SEALING
RAMP CA							
17+20 TO 17+50	DRIVING	12	30	-		216	ROADWAY UNDERSEALING
RT 47+74 (MP 0.7)					1	200	CULVERT SEALING
WILLIAMSON CO. TOTALS						1,439	
JOHNSON CO.							
EB LANES							
147+11 TO 148+00 (MP 2.1)	DRIVING	12	89	1.92		1,666	SN #044-0029 APPROACH
147+11 TO 148+00 (MP 2.1)	PASSING	12	89	1.92		1,666	SN #044-0029 APPROACH
155+00 TO 155+75 (MP 2.2)	DRIVING	12	75	1.92		1,404	SN #044-0029 DEPARTURE
155+00 TO 155+75 (MP 2.2)	PASSING	12	75	1.68		1,404	SN #044-0029 DEPARTURE
158+93 TO 159+19 (MP 2.3)	DRIVING	12	26	-		158	ROADWAY UNDERSEALING
524+50 TO 524+80 (MP 9.2)		12	30	-		216	ROADWAY UNDERSEALING
LT 348+72 (MP 5.9)					21	2,100	CULVERT SEALING
LT 254+88 (MP 12.1)					10	1,500	CULVERT SEALING
LT 272+15 (MP 12.4)					16	1,600	CULVERT SEALING
MEDIAN							
146+00 (MP 2.0)					1	200	CULVERT SEALING
174+20 (MP 2.6)					17	1,700	CULVERT SEALING
182+80 (MP 2.7)					9	1,350	CULVERT SEALING
232+50 (MP 3.7)					3	600	CULVERT SEALING
WB LANES							
147+35 TO 148+00 (MP 2.1)	DRIVING	12	65	3.00		2,380	SN #044-0030 DEPARTURE
147+35 TO 148+00 (MP 2.1)	PASSING	12	65	3.00		2,380	SN #044-0030 DEPARTURE
211+70 TO 212+10 (MP 3.3)	DRIVING	12	40	-		288	ROADWAY UNDERSEALING
264+05 TO 265+10 (MP 4.3)	DRIVING	12	105	-		756	ROADWAY UNDERSEALING
108+80 TO 109+25 (MP 9.4)	DRIVING	12	45	-		324	ROADWAY UNDERSEALING
137+30 TO 138+09 (MP 9.9)	DRIVING	12	79	-		569	ROADWAY UNDERSEALING
183+24 TO 184+40 (MP 10.8)	DRIVING	12	116	-		835	ROADWAY UNDERSEALING
193+25 TO 193+60 (MP 10.9)	DRIVING	12	35	-		252	ROADWAY UNDERSEALING
194+16 TO 194+66 (MP 11.0)	DRIVING	12	50	1.44		432	ROADWAY
196+05 TO 196+70 (MP 11.0)	DRIVING	12	65	-		468	ROADWAY UNDERSEALING
228+17 TO 228+57 (MP 11.6)	DRIVING	12	40	-		288	ROADWAY UNDERSEALING
230+50 TO 231+02 (MP 11.6)	DRIVING	12	52	-		374	ROADWAY UNDERSEALING
234+63 TO 236+06 (MP 11.7)	DRIVING	12	143	-		1,030	ROADWAY UNDERSEALING
237+11 TO 237+37 (MP 11.8)	DRIVING	12	26	-		187	ROADWAY UNDERSEALING
237+62 TO 238+20 (MP 11.8)	DRIVING	12	58	1.20		418	ROADWAY
238+45 TO 239+00 (MP 11.8)	DRIVING	12	55	-		396	ROADWAY UNDERSEALING
241+38 TO 242+78 (MP 11.8)	DRIVING	12	140	-		1,008	ROADWAY UNDERSEALING
243+33 TO 244+56 (MP 11.9)	DRIVING	12	123	-		886	ROADWAY UNDERSEALING
245+50 TO 248+55 (MP 11.9)	DRIVING	12	305	-		3,331	ROADWAY UNDERSEALING
306+25 TO 306+76 (MP 13.1)	DRIVING	12	51	-		367	ROADWAY UNDERSEALING
310+67 TO 311+13 (MP 13.2)	DRIVING	12	46	-		331	ROADWAY UNDERSEALING
311+48 TO 311+87 (MP 13.2)	DRIVING	12	39	-		281	ROADWAY UNDERSEALING
312+05 TO 312+50 (MP 13.2)	DRIVING	12	45	-		324	ROADWAY UNDERSEALING
314+53 TO 314+70 (MP 13.2)	DRIVING	12	17	-		122	ROADWAY UNDERSEALING
JOHNSON CO. TOTALS						33,591	
PROJECT TOTAL						35,030	

Monday, November 29, 2004 @ 8:48:35 AM
c:\p\projects\98758\98758.dwg LV-2-18-20-63