

TRAFFIC BARRIER

LOCATION STATION TO STATION (MP IS THE LAST STATION UNLESS OTHERWISE NOTED)	S. P. B. G. R. REMOVAL	S. P. B. G. R. TYPE A	TRAFFIC BARRIER TYPE 1 TERMINAL SPECIAL (TANGENT)	TRAFFIC BARRIER TYPE 1 TERMINAL SPECIAL (FLARED)	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 5	TRAFFIC BARRIER TERMINAL, TYPE 6	REMARKS
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	
FAI 24								
WILLIAMSON CO.								
RAMP AC								
RT 55+54.00 TO 58+35.00 (MP 1.1)	100	212.5	1				1	
LT 54+83.85 TO 57+77.00 (MP 1.0)	102	225.0	1				1	
RAMP CB								
RT 23+97.00 TO 24+92.00	95	25.0	1				1	
LT 23+83.00 TO 24+87.00	104	25.0	1				1	
WILLIAMSON CO. TOTALS								
	401	487.5	4				4	
JOHNSON CO.								
EB LANES								
RT 144+74.00 TO 147+80.00 (MP 2.1)	102	237.5	1				1	
LT 145+11.00 TO 147+80.00 (MP 2.1)	181	200.0		1			1	
RT 155+15.00 TO 156+17.00 (MP 2.2)	102							REMOVING GUARDRAIL ONLY
RT 291+45.00 TO 308+52.00 (MP 5.1)	1,653	1,662.5	1		1			
RT 370+95.00 TO 375+52.00 (MP 6.4)	300	412.5	1		1			
RT 389+45.00 TO 395+59.50 (MP 6.8)	552	570.0	1		1			
RT 482+45.00 TO 490+09.50 (MP 8.6)	797	720.0	1		1			
RT 107+95.00 TO 116+08.50 (MP 9.5)	525	770.0	1		1			
RT 176+16.00 TO 186+09.00 (MP 10.8)	929	925.0	1				1	
LT 175+70.00 TO 186+14.00 (MP 10.8)	937	975.0	1				1	
RT 187+40.00 TO 196+10.00 (MP 11.0)	876	850.0			1	1		
LT 187+46.00 TO 197+14.00 (MP 11.0)	978	937.5			1	1		
RT 226+70.00 TO 238+84.50 (MP 11.8)	1,352	1,170.0	1		1			
LT 226+34.00 TO 242+10.50 (MP 11.8)	1,551	1,532.5	1		1			
WB LANES								
LT 142+15.00 TO 147+85.00 (MP 2.1)	727	550.0			1	1		
RT 155+10.00 TO 157+79.00 (MP 2.2)	181	200.0		1			1	
LT 155+10.00 TO 158+16.00 (MP 2.2)	103	237.5	1				1	
LT 299+46.00 TO 309+03.00 (MP 5.1)	749	912.5	1		1			
LT 1389+73.00 TO 1396+05.00 (MP 6.7)	389	587.5	1		1			
LT 523+08.00 TO 524+83.61 BK (MP 9.2)	1,603	1,725.0	1		1			COMBINING TWO SECTIONS INTO ONE
LT 102+46.58 AH TO 118+40.00 (MP 9.6)								
RT 188+22.00 TO 197+40.00 (MP 11.0)	817	850.0	1				1	
LT 188+27.00 TO 197+83.00 (MP 11.0)	787	887.5	1				1	
RT 230+95.00 TO 247+65.00 (MP 11.9)	1,659	1,625.0	1		1			
LT 232+39.00 TO 245+08.00 (MP 11.9)	1,650	1,225.0	1		1			
JOHNSON CO. TOTALS								
	19,500	19,762.5	18	2	15	3	8	
PROJECT TOTALS								
	19,901	20,250.0	22	2	15	3	12	

- NOTE:
1. STATION LIMITS ARE FOR THE ACTUAL LENGTH OF NEED AND DOES NOT INCLUDE THE EXTRA LENGTH FOR CRASH TERMINALS.
 2. STATION LIMITS ARE ALSO FOR THE PROPOSED LENGTH AND THE EXISTING GUARDRAIL TO BE REMOVED IS NEAR THESE LIMITS.
 3. THE EXISTING GUARDRAIL TO BE REMOVED ARE NEAR THESE LIMITS.