

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
24	*	**	189	51
STA.	TO STA.			
FED. ROAD DIST. NO. -	ILLINOIS	FED. AID PROJECT		

\* X1-2,44(2,3,4)RS.BSMARTFY04-4  
 \*\* WILLIAMSON/JOHNSON  
 CONTRACT NO.: 98758

## TREE REMOVAL

LOCATION STA TO STA (MP IS THE LAST STA. UNLESS OTHERWISE NOTED)	OFFSET FROM E.P. FEET	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TREE REMOVAL ACRES	REMARKS
		UNIT	UNIT	ACRE	
<b>FAI 24</b>					
WILLIAMSON CO.					
FAI-24/I-57 INTERCHANGE					
RAMP AC					
RT 54+00 (MP 1.1)	37	6			(CEDAR)
RT 54+08 (MP 1.1)	35	6			(CEDAR)
RT 54+12 (MP 1.1)	35	6			(CEDAR)
RT 55+31 (MP 1.1)	35	7			(CEDAR)
RT 55+37 (MP 1.1)	35	6			(CEDAR)
RAMP CB					
RT 23+12 (MP 0.7)	174	10			4' EAST OF EAST WING--TREAT STUMP WITH HERBICIDE
RT 23+46 (MP 0.7)	168	7			NEAR RAMP "CB", AND EAST OF PAVED DITCH, (CEDAR)
RT 23+12 (MP 0.7)	174	12			3' WEST OF WEST WING -TREAT STUMP WITH HERBICIDE
WB LANES					
LT 122+48 (MP 1.6)	160			18	(OAK)
LT 125+70 (MP 1.7)	130	6			NORTH WING-TREAT STUMP WITH HERBICIDE
LT 125+70 (MP 1.7)	94	6	6		2 TREES, 35' UP THE FORESLOPE FROM THE HEADWALL, (CEDAR)
LT 125+70 (MP 1.7)	54	8			70' UP THE FORESLOPE FROM THE HEADWALL, (CEDAR)
LT 134+31 (MP 1.8)	50 TO 160			0.05	SEE PLAN FOR TREE REMOVAL THROUGH THE EARTH EXCAVATION REGION 110' X 15', SKEWED AHEAD
<b>WILLIAMSON CO TOTAL</b>		<b>86</b>		<b>18</b>	<b>0.05</b>
<b>JOHNSON CO</b>					
EB LANES					
RT 141+85 (MP 1.9)	152	7	8		2-TREES, SOUTHWEST CORNER OF WINGWALL-TREAT STUMP WITH HERBICIDE
RT 141+85 (MP 1.9)	152	6			4' NORTH AND 4' WEST OF NORTH HEADWALL-TREAT STUMP WITH HERBICIDE
RT 141+85 (MP 1.9)	152	6	6	6	4 TREES, 25' UPSTREAM IN THE FLOWLINE
RT 141+96 (MP 2.0)	152	8			2' UP THE FORESLOPE FROM THE HEADWALL
RT 142+08 (MP 2.0)	144	8			5' NORTH AND 1' EAST OF HEADWALL-TREAT STUMP WITH HERBICIDE
RT 149+00 (MP 2.0)	139	9			3' (LEFT) UPSLOPE FROM PAVED DITCH (CEDAR)
RT 150+47 (MP 2.1)	140	6			2' (LEFT) UPSLOPE FROM PAVED DITCH (CEDAR)
RT 150+66 (MP 2.1)	142	8			UP FORESLOPE NEXT TO PAVED DITCH
RT 150+73 (MP 2.1)	154	7			RIGHT OF PAVED DITCH, UP BACKSLOPE
RT 151+50 TO 152+05 (MP 2.1)	172 TO 200			0.03	SEE PLAN FOR REMOVAL CENTERED ON PAVED DITCH
RT 154+44 (MP 2.1)	210	12			RIGHT OF PAVED DITCH (SYCAMORE)
RT 155+10 (MP 2.1)	210	7			LEFT OF PAVED DITCH
RT 155+40 (MP 2.2)	212	6			LEFT OF PAVED DITCH
RT 156+17 (MP 2.2)	218	8			LEFT OF PAVED DITCH
RT 156+73 (MP 2.2)	226	6			RIGHT OF PAVED DITCH
RT 156+80 (MP 2.2)	220	6			RIGHT OF PAVED DITCH
RT 169+11 (MP 2.4)	50	11			TREE REMOVAL AT BEGINNING OF PAVED DITCH
RT 183+80 (MP 2.8)	92	6			RIGHT OF PAVED DITCH (WHITE OAK)
RT 187+81 (MP 2.8)	70	6			REMOVE TREE 40' UP FROM END OF PAVED DITCH (NORTH SIDE OF P.D.)
RT 183+32 (MP 2.8)	32	6			3' WEST OF HEADWALL-TREAT STUMP WITH HERBICIDE
RT 183+46 (MP 2.8)	86	7			13' UPSTREAM FROM CENTER OF FLOWLINE
RT 183+60 (MP 2.8)	76	6	8		2 TREES, 6' FROM END OF THE SOUTH WING
RT 195+67 (MP 3.0)	44	7			REMOVE TREE 11' FROM END OF PAVED DITCH (NORTH SIDE OF P.D.)
RT 195+67 (MP 3.0)	70	10			AT BEGINNING OF PAVED DITCH (NORTH SIDE OF P.D.) TOP OF BACKSLOPE
RT 211+38 (MP 3.0)	112	10			1' UP THE BACKSLOPE RIGHT AT THE FENCE LINE
RT 211+92 (MP 3.0)	190	8			4' UP THE BACKSLOPE
RT 211+94 (MP 3.0)	190	8			2' UP THE BACKSLOPE
RT 291+30 (MP 4.8)	63	6	6		(PERSIMMON)
RT 303+40 (MP 5.0)	160	6	6		2 TREES, BEHIND EAST WINGWALL-TREAT STUMP WITH HERBICIDE
RT 322+82 (MP 5.4)	106	13			REMOVE TREE JUST RIGHT OF PAVED DITCH (ELM)
RT 349+00 (MP 5.9)	116	6			REMOVE TREE JUST RIGHT OF PAVED DITCH (CEDAR)
RT 365+87 (MP 6.2)	72	6			18' FROM BEGINNING OF PAVED DITCH
RT 365+87 (MP 6.2)	64	7			21' FROM BEGINNING OF PAVED DITCH
RT 373+65 (MP 6.3)	120	12			2' UP THE BACKSLOPE
RT 393+23 (MP 6.7)	120	13			REMOVE DEAD TREE LYING ACROSS THE EXISTING PAVED DITCH, 3 BROKEN PIECES SAME TREE
RT 393+23 (MP 6.7)	130	7			4' ON THE WEST SIDE OF THE PAVED DITCH - 10' UP FROM THE END OF THE PAVED DITCH
RT 393+23 (MP 6.7)	132	7			7' ON THE WEST SIDE OF THE PAVED DITCH - 20' UP FROM THE END OF THE PAVED DITCH
RT 394+14 (MP 6.7)	158	9			8' UP THE BACKSLOPE (CEDAR)
RT 394+60 (MP 6.7)	110	10			NEAR THE END OF THE NORTH WINGWALL-TREAT STUMP WITH HERBICIDE
RT 394+89 (MP 6.7)	110	7			NEAR THE END OF THE NORTH WINGWALL-TREAT STUMP WITH HERBICIDE
RT 394+90 (MP 6.7)	110	8			NEAR THE END OF THE NORTH WINGWALL-TREAT STUMP WITH HERBICIDE

Monday, December 15, 2008 5:48:55 PM  
 C:\projects\98758\98758.dwg L:\2-18-28-63