

TREE REMOVAL

LOCATION STA TO STA (MP IS THE LAST STA. UNLESS OTHERWISE NOTED)		OFFSET FROM E. P. FEET	TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT	TREE REMOVAL (OVER 15 UNITS DIAMETER) UNIT	TREE REMOVAL ACRES	REMARKS
EB LANES						
RT	394+95 (MP 6.7)	110	9			BEHIND HEADWALL NEAR THE NORTH WINGWALL-TREAT STUMP WITH HERBICIDE
RT	395+00 (MP 6.7)	110	6			BEHIND HEADWALL NEAR THE SOUTH WINGWALL-TREAT STUMP WITH HERBICIDE
RT	395+10 (MP 6.7)	110	8			NEAR THE END OF THE SOUTH WINGWALL-TREAT STUMP WITH HERBICIDE
RT	395+20 (MP 6.7)	156	8			4' UP THE BACKSLOPE (CEDAR)
RT	456+26 (MP 7.9)	100	10			ADJACENT TO PAVED DITCH
RT	482+30 (MP 8.4)	190	9			RT. OF PAVED DITCH, UP BACKSLOPE
RT	482+94 (MP 8.4)	144	6			RT. OF PAVED DITCH, UP BACKSLOPE
RT	483+80 TO 484+15 (MP 8.4)	160 TO 180			0.01	SEE PLAN FOR LIMITS 10' WIDE ALONG THE EDGE OF PAVED DITCH
RT	486+56 (MP 8.5)	154	6	8		SOUTH OF EAST WINGWALL
RT	488+06 (MP 8.5)	148	6			SOUTH OF HEADWALL-TREAT STUMP WITH HERBICIDE
RT	488+07 (MP 8.5)	148	11			SOUTH OF HEADWALL-TREAT STUMP WITH HERBICIDE
RT	488+08 (MP 8.5)	148	12			SOUTH OF HEADWALL-TREAT STUMP WITH HERBICIDE
RT	506+66 (MP 8.9)	48	8			JUST NORTH OF PAVED DITCH 13' UP FROM THE END
RT	506+68 (MP 8.9)	70	11			AT THE BEGINNING OF THE PAVED DITCH
RT	506+69 (MP 8.9)	67	8			3' FROM BEGINNING OF PAVED DITCH
RT	105+25 (MP 9.3)	76	6	6		2 TREES
RT	105+25 (MP 9.3)	86	6			
RT	115+35 (MP 9.5)	10 TO 150			0.13	SEE PLAN FOR TREE REMOVAL FROM GUARDRAIL DOWN TO TOE OF SLOPE
RT	178+12 (MP 10.6)	124			21	RIGHT OF PAVED DITCH, UP BACKSLOPE, (OAK)
RT	178+39 (MP 10.7)	130			20	RIGHT OF PAVED DITCH, UP BACKSLOPE
RT	178+54 (MP 10.7)	80	8			(CEDAR)
RT	178+60 (MP 10.7)	79	8			(CEDAR)
RT	178+60 (MP 10.7)	69	7			(CEDAR)
RT	181+50 (MP 10.7)	10 TO 123			0.06	SEE PLAN FOR REMOVAL CENTERED ON CULVERT
RT	185+00 (MP 10.8)	10 TO 134			0.10	SEE PLAN FOR REMOVAL CENTERED ON CULVERT
RT	187+60 (MP 10.8)	10 TO 165			0.10	SEE PLAN FOR REMOVAL CENTERED ON CULVERT SKEWED BACK
RT	193+05 (MP 10.9)	120			20	FALLEN TREE (PINE)
RT	226+33 (MP 11.5)	50	8			1' UP THE BACKSLOPE (WILLOW)
RT	226+77 (MP 11.6)	84	6			4' UP BACKSLOPE
RT	227+03 (MP 11.6)	110	9			3' UP BACKSLOPE
RT	231+50 (MP 11.6)	50 TO 120			0.08	SEE PLAN FOR REMOVAL 50' FROM EDGE OF PAVEMENT
RT	231+83 (MP 11.7)	142				19' PAST CULVERT; 6" REMOVAL TO BE INCLUDED WITH TREE REMOVAL, ACRES; RT STA 231+50
RT	231+83 (MP 11.7)	143				20' PAST CULVERT; 6" REMOVAL TO BE INCLUDED WITH TREE REMOVAL, ACRES; RT STA 231+50
RT	231+87 (MP 11.7)	124				15' PAST CULVERT; 10" REMOVAL TO BE INCLUDED WITH TREE REMOVAL, ACRES; RT STA 231+50
RT	231+89 (MP 11.7)	119				9' PAST CULVERT; 11" REMOVAL TO BE INCLUDED WITH TREE REMOVAL, ACRES; RT STA 231+50
RT	238+50 (MP 11.8)	81	8			FORESLOPE
RT	238+56 (MP 11.8)	71	8			FORESLOPE
RT	244+00 TO 245+89 (MP 11.9)	104 TO 150			0.09	SEE PLAN FOR REMOVAL CENTERED ON PAVED DITCH
RT	249+94 (MP 12.0)	124	11			1' UP THE BACKSLOPE
RT	250+26 (MP 12.0)	102	6	10		1' BEFORE HEADWALL-TREAT STUMP WITH HERBICIDE, (CEDAR)
RT	278+33 (MP 12.6)	76	9			43' FROM PAVED DITCH
RT	278+34 (MP 12.6)	68	7	7		2 TREES, 34' OFF OF PAVED DITCH
RT	270+66 (MP 12.4)	82	7			1' INSIDE CULVERT HEADWALL (CEDAR)
RT	283+70 (MP 12.6)	60	8	8		3 TREES, SOUTH SIDE OF PAVED DITCH
RT	283+70 (MP 12.6)	85	9	6		2 TREES, SOUTH SIDE OF PAVED DITCH
RT	300+92 (MP 13.0)	54	11			ALONG EDGE OF PAVED DITCH
RT	300+92 (MP 13.0)	82	8	11		ALONG EDGE OF PAVED DITCH
RT	300+94 (MP 13.0)	30	10	10		2 TREES, REMOVAL FOR CLEARZONE
RT	300+97 (MP 13.0)	34	7			
RT	301+00 (MP 13.0)	31	8			
RT	301+02 (MP 13.0)	33	6			
RT	301+04 (MP 13.0)	82	8			
RT	301+12 (MP 13.0)	46	7			
RT	314+80 TO 317+30 (MP 13.2)	128 TO 160			0.11	SEE PLAN FOR REMOVAL ALONG DITCH REGION
RT	317+68 (MP 13.3)	140	10			AT THE END OF PROPOSED EARTH EXCAVATION (ON THE NORTH SIDE)
RT	318+01 (MP 13.3)	120	6			NORTH END OF WINGWALL-TREAT STUMP WITH HERBICIDE
RT	318+60 TO 319+42 (MP 13.3)	120 TO 154			0.03	SEE PLAN FOR REMOVAL ALONG SOUTH PAVED DITCH

Monday, December 20, 2004 @ 4:49:08 PM
c:\prow\lects\1102102\1102102.dwg L:\2-18-28-63