

# RIPRAP

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	**	189	63
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* X1-2,44(2,3,4)RS,BSMARTFY04-4				
** WILLIAMSON/JOHNSON				
CONTRACT NO.: 98758				

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	STONE RIPRAP DITCH	STONE DUMPED RIPRAP CLASS A4	STONE DUMPED RIPRAP CLASS A4	STONE DUMPED RIPRAP CLASS A5	STONE RIPRAP CLASS A3	STONE RIPRAP CLASS A4	PAY ITEM	GABIONS				FILTER FABRIC FOR USE WITH RIPRAP (SEE NOTE 2)	RIPRAP SLURRY	REMARKS	
								INFORMATION ONLY (SEE NOTE 1)							
								AVERAGE		HEIGHT FT	EST. NO. OF CELLS				
LENGTH FT	WIDTH FT														
	TON	SQ YD	TON	TON	TON	TON	CU YD	FT	FT	FT		SQ YD	SQ YD		
<b>EB LANES</b>															
RT 392+50 TO 395+50 (MP 6.8)						48									BEHIND CONCRETE CURB
RT 393+68 TO 394+57 (MP 6.8)	47														
RT 395+34 TO 396+60 (MP 6.8)															
RT 395+14 TO 399+35 (MP 6.9)	246														
RT 473+21 TO 473+55 (MP 8.2)	26														
RT 481+48 TO 484+15 (MP 8.4)	155														
RT 486+43 (MP 8.5)							9	9	18	1.5	18	174.4		SEE SCOUR REPAIR DETAIL SHEET 161	
RT 487+50 (MP 8.5)						87									
RT 485+50 TO 490+00 (MP 8.6)						91						178.0		BEHIND CONCRETE CURB	
RT 490+00 (MP 8.6)						87									
RT 518+00 TO 520+70 (MP 9.2)	151														
RT 107+75 (MP 9.3)						28									
RT 113+92 (MP 9.4)				22											
RT 111+00 TO 116+00 (MP 9.5)						117								BEHIND CONCRETE CURB	
RT 115+35 (MP 9.5)						78						155.6			
RT 136+82 TO 141+25 (MP 9.9)	242														
RT 138+35 TO 139+53 (MP 9.9)						131									
RT 143+58 TO 155+03 (MP 10.2)	636														
RT 181+50 (MP 10.7)						56						111.0			
RT 180+50 TO 186+09 (MP 10.8)						119									
RT 180+55 TO 185+53 (MP 10.8)	306														
RT 184+00 (MP 10.8)	28											611.1		BEHIND CONCRETE CURB RIPRAP SLURRY	
RT 184+10 (MP 10.8)							4	6	6	3	4		55.6	DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS	
RT 185+00 (MP 10.8)						67						133.3			
RT 191+54 (MP 10.9)						47						94.4			
RT 187+40 TO 196+02 (MP 11.0)						138								BEHIND CONCRETE CURB	
RT 194+72 TO 197+98 (MP 11.0)	181														
RT 194+84 TO 195+20 (MP 11.0)						9									
RT 195+20 TO 195+47 (MP 11.0)						30									
RT 195+47 TO 196+19 (MP 11.0)						120									
RT 195+97 (MP 11.0)						42						83.3			
RT 225+98 TO 231+50 (MP 11.7)	332														
RT 231+25 (MP 11.7)						62						124.4			
RT 231+60 (MP 11.7)							4	6	6	3	4			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS	
RT 232+22 (MP 11.7)							6	6	9	3	6			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS	
RT 233+10 (MP 11.7)							8	6	12	3	8			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS	
RT 234+95 (MP 11.7)							4	6	6	3	4			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS	
RT 235+00 (MP 11.7)						17						33.3			
RT 229+75 TO 238+75 (MP 11.8)						179								BEHIND CONCRETE CURB	
RT 238+75 (MP 11.8)												111.0			
RT 238+63 TO 241+03 (MP 11.8)	134														
RT 249+55 TO 250+27 (MP 12.0)	52														
RT 269+39 TO 270+29 (MP 12.4)	53														
RT 270+70 TO 279+53 (MP 12.6)	498														
RT 283+73 (MP 12.6)			111											STONE RIPRAP DITCH OVER 5' DEEP, A4 RIPRAP	
RT 283+73 (MP 12.6)	31														
RT 292+20 TO 293+54 (MP 12.8)	74											149.0		RIPRAP SLURRY	
RT 301+00 (MP 13.0)	25														
LT 373+34 TO 373+91 (MP 6.4)	40														
LT 395+34 TO 396+60 (MP 6.8)	74												149.0		
LT 182+00 (MP 10.7)						50						100.0			
LT 180+00 TO 186+14 (MP 10.8)						110								BEHIND CONCRETE CURB	
LT 182+90 (MP 10.8)							9	9	9	3	9			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS	
LT 183+60 (MP 10.8)							8	6	12	3	8			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS	
LT 184+50 (MP 10.8)						61						122.0			
LT 186+10 (MP 10.8)						61						122.2			
LT 188+01 TO 189+64.5 (MP 10.9)	83														
LT 189+73 (MP 10.9)						75						150.0			

Monday, December 20, 2004 6:20:32 PM  
c:\pco\ec\13\102102\102102.dwg L:\2-15-2004