



When "A" is 3'-6" or less, the temporary concrete barrier shall be anchored to the slab as shown. No anchorage is required when "A" is greater than 3'-6".

NOTES

1. Drill 1 1/4" ϕ Holes through new overlay into slab for 1" ϕ x 13" dowel bars. Traffic side only as directed by Engineer. Repair hole with non-shrink epoxy grout as directed by Engineer. Cost of anchorage and repair included with Temporary Concrete Barrier.

* Dimension shown is minimum required embedment into concrete. If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.

SECTIONS THRU SLAB

DESIGNED - DF	REVISED -
USER NAME = Injeler	DRAWN - LAM
PLLOT SCALE = N15	CHECKED - BLU
PLLOT DATE = 1/20/2011 2:34:08 PM	DATE - 01/21/2011



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION
EASTBOUND I-80 OVER CENTER STREET RAMP CC
STRUCTURE NO. 099-0055

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99(2&3)RS-3	WILL	200	107
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	

SHEET NO. S-5 OF S-5 SHEETS