

SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY	71st STREET BRIDGE SN 016- 7721	WALLS SN 016- 7722 THRU SN016- 7726	TRAINEES	71st STREET LIFT STATION
					0004	0008	0040	0042	0043
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	143	143				
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18	18				
	20101000	TEMPORARY FENCE	FOOT	1,500	1,500				
	20101100	TREE TRUNK PROTECTION	EACH	30	30				
*	20101700	SUPPLEMENTAL WATERING	UNIT	110	110				
	20200100	EARTH EXCAVATION	CU YD	41,981	41,981				
	20800150	TRENCH BACKFILL	CU YD	9,698	9,238				460
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	14,134	13,154				980
*	21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	80	80				
	21301072	EXPLORATION TRENCH, 72" DEPTH	FOOT	80	80				
*	25000200	SEEDING, CLASS 2	ACRE	0.7	0.2				0.5
*	25100630	EROSION CONTROL BLANKET	SQ YD	10,892	10,892				
*	25200110	SODDING, SALT TOLERANT	SQ YD	10,892	10,892				
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	750	750				
	28000400	PERIMETER EROSION BARRIER	FOOT	6,050	5,850				200
	28000510	INLET FILTERS	EACH	80	80				
	31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	9,604	9,364				240
	31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	9,768	9,768				
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	240	240				
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,077	2,077				
	40600300	AGGREGATE (PRIME COAT)	TON	31	31				
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	48	48				
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	49	49				
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	457	457				
	40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ YD	2,738	2,738				
	42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	9,149	9,149				
	42001300	PROTECTIVE COAT	SQ YD	49,447	49,447				
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	5,446	5,446				
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	14,914	14,719				195
	42400800	DETECTABLE WARNINGS	SQ FT	116	116				
	44000100	PAVEMENT REMOVAL	SQ YD	13,341	13,126				215.0
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	4,080	4,080				
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3,509	3,509				
	44000300	CURB REMOVAL	FOOT	20	20				
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,750	3,750				
	44000600	SIDEWALK REMOVAL	SQ FT	11,918	11,918				
	44003100	MEDIAN REMOVAL	SQ FT	194	194				
	44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	86	86				

* DENOTES SPECIALTY ITEM

FILE NAME = P:\60155877\000\CAD\2011\Drawings\Sheets\Civil\60155877-000-500.dwg



USER NAME = merrj	DESIGNED - NJH	REVISED -
PLOT SCALE = 1.000' / IN.	DRAWN - NJH	REVISED -
PLOT DATE = 1/20/2011	CHECKED - TJW	REVISED -
	DATE - JANUARY 7, 2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1537	06-00050-00-GS	COOK	209	4
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 63556	
FED. AID PROJECT CRE-9003709				