

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				RECONSTRUCTION, CAPACITY ADDED 0003	SAFETY (TRAFFIC SIGNALS) 0021
* 20101000	TEMPORARY FENCE	FOOT	510	510	-
20200100	EARTH EXCAVATION	CU YD	2,888	2,888	-
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,698	2,698	-
* 20400800	FURNISHED EXCAVATION	CU YD	3,008	3,008	-
20800150	TRENCH BACKFILL	CU YD	257	257	-
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	5,565	5,565	-
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	15,623	15,623	-
25000200	SEEDING, CLASS 2	ACRE	3.26	3.26	-
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	296	296	-
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	296	296	-
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	296	296	-
25100630	EROSION CONTROL BLANKET	SQ YD	15,623	15,623	-
25200200	SUPPLEMENTAL WATERING	UNIT	97	97	-
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	326	326	-
28000305	TEMPORARY DITCH CHECKS	FOOT	434	434	-
28000400	PERIMETER EROSION BARRIER	FOOT	2,294	2,294	-
28000500	INLET AND PIPE PROTECTION	EACH	7	7	-
28000510	INLET FILTERS	EACH	21	21	-
* 28000720	MULCH, METHOD 2	ACRE	3.26	3.26	-
28100107	STONE RIPRAP, CLASS A4	SQ YD	49	49	-
28200200	FILTER FABRIC	SQ YD	49	49	-
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1,628	1,628	-
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	98	98	-
35400200	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 7"	SQ YD	70	70	-
* 35800100	PREPARATION OF BASE	SQ YD	2,621	2,621	-
35800200	AGGREGATE BASE REPAIR	TON	250	250	-
* 40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24	-
* 40600300	AGGREGATE (PRIME COAT)	TON	106	106	-

* INDICATES SPECIAL PROVISION
 Δ INDICATES SPECIALTY ITEM

Copyright © 2008 by BAXTER & WOODMAN, INC. All rights reserved. No part of this document may be reproduced without written permission from BAXTER & WOODMAN, INC. License No. 00021, Expires 7/30/2011. 11:07:51 AM, 8/6/2010



DESIGNED - DJS	REVISED -08-4-2010 IDOT REVIEW
DRAWN - UKB	REVISED -10-27-2010 IDOT REVIEW
CHECKED - RWL	REVISED -
DATE - 05-03-2010	FILE NAME -081068-QNTY.dgn

**CITY OF DeKALB, ILLINOIS
 PEACE ROAD
 IMPROVEMENTS**

SUMMARY OF QUANTITIES

SCALE: _____ STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-00-WR	DeKALB	64	4
CONTRACT NO. 87465				
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT M-5017 (043)				