

## SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				RECONSTRUCTION, CAPACITY ADDED 0003	SAFETY (TRAFFIC SIGNALS) 0021
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4	-
60260100	INLETS TO BE ADJUSTED	EACH	1	1	-
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3	3	-
60404950	FRAMES AND GRATES, TYPE 24	EACH	16	16	-
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2	-
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1	-
60500040	REMOVING MANHOLES	EACH	1	1	-
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4,600	4,600	-
Δ 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	938	938	-
Δ 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	-
Δ 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	-
Δ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	-
63200310	GUARDRAIL REMOVAL	FOOT	802	802	-
Δ 66400105	CHAIN LINK FENCE, 4'	FOOT	115	115	-
*Δ 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	315	315	-
*Δ 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1	-
*Δ 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3	-
67100100	MOBILIZATION	L SUM	1	1	-
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,347	1,347	-
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	836	836	-
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	70,388	70,388	-
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,650	3,650	-
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,058	1,058	-
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,131	1,131	-
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	603	603	-
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17,270	17,270	-
* 72000100	SIGN PANEL - TYPE 1	SQ FT	84	54	30

\* INDICATES SPECIAL PROVISION  
 Δ INDICATES SPECIALTY ITEM

COPYRIGHT © 2006 BY BAXTER A. WOODMAN, INC.  
 LICENSE NO. 04-00021, EXPIRES 4/30/2011  
 I:\Crystal\DeKalb\081068-INTY.dgn  
 11/01/2010 10:09 AM



DESIGNED - DJS	REVISED - 08-4-2010 IDOT REVIEW
DRAWN - UKB	REVISED - 10-27-2010 IDOT REVIEW
CHECKED - RWL	REVISED -
DATE - 05-03-2010	FILE NAME - 081068-INTY.dgn

**CITY OF DeKALB, ILLINOIS  
 PEACE ROAD  
 IMPROVEMENTS**

**SUMMARY OF QUANTITIES**

SCALE: STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-00-WR	DeKALB	64	6
CONTRACT NO. 87465				
FED. ROAD DIST. NO. 3   ILLINOIS   FED. AID PROJECT M-5017 (043)				