



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 16, 2010

SUBJECT: FAU 2802 & FAU 1532 (Sayre Ave. & 71st St.)
Project M-9003(388)
Section 09-00032-00-RS (Bedford Park)
Cook County
Contract No. 63410
Item 53
April 23, 2010 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Index of Special Provisions, page 14 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott Stitt
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by "P.E." in a smaller font.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

INDEX OF SPECIAL PROVISIONS

LOCATION OF PROJECT.....1

DESCRIPTION OF PROJECT.....1

MAINTENANCE OF ROADWAYS.....2

STATUS OF UTILITIES TO BE ADJUSTED.....3

TRAFFIC CONTROL PLAN.....4

TRAFFIC CONTROL AND PROTECTION (SPECIAL).....5

TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR.....6

COMBINATION CONCRETE CURB & GUTTER REMOVAL AND
REPLACEMENT.....6-7

FRAMES AND LIDS TO BE ADJUSTED (SPECIAL).....7-8

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT.....8

MANHOLES TO BE ADJUSTED (SPECIAL).....9

MORTAR EXISTING STRUCTURES.....9

PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING)
VARIABLE DEPTH.....9-10

INLETS, TYPE A, WITH SALVAGED FRAME AND GRATE.....10

CONSTRUCTION
STAKING.....10

TRAFFIC SIGNAL SPECIFICATIONS FOR DETECTOR REPLACEMENT
AND/ OR INSTALLATION ON ROADWAY GRINDING, RESURFACING &
PATCHING OPERATIONS.....11-14

CLASS B PATCHES

14

Replacement." All drilling of handholes, furnishing and installing unit duct, cable splicing, trench and backfill, removal of equipment, and pulling cable from conduit shall be included in this item.

Basis of Payment. Magnetic Detector Removal and Detector Loop Installation shall be paid for at the contract unit price per foot (meter) for DETECTOR LOOP, TYPE I, per each for INDUCTIVE LOOP DETECTOR, and foot (meter) for ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR.

CLASS B PATCHES, 11 INCH

DESCRIPTION. This work shall consist of the sawcutting and removal of existing pavement, necessary excavation and replacement with portland cement concrete patches of the type specified at designated locations.

GENERAL. All material, equipment, and construction requirements shall be in accordance with applicable articles of Section 442 of the Standard Specifications where these requirements refer to Class B patches and the plan details for Class B Patches.

Dowel bars will be sized and installed in accordance with the plan details

METHOD OF MEASUREMENT. Pavement removal and replacement for Class B Patches will be measured for payment in place, and the area computed in square yards.

BASIS OF PAYMENT. This work will be paid for at the contract unit price per square yard for CLASS B PATCHES, 11 INCH, of the type specified. The cost for furnishing and installation of dowel bars shall be included in the contract unit price for this item. The cost for sawcutting the existing pavement shall also be included in the contract unit price for this item.

Revised 4-16-10