CONTRACT NO. 60B57

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2843	2006-022 RS	COOK	22	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

D-91-376-06

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24					
40600300	AGGREGATE (PRIME COAT)	TON	123	123					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	568	568					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	227	227					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	58.8	58.8					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2580	2580					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	30	30					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	28027	28027					
44000600	SIDEWALK REMOVAL	SQ FT	30	30					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	61	61					
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	300	300					
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	85.3	85.3					
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	246.6	246.6					
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	106.3	106.3					
44213200	SAW CUTS	FOOT	432	432					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	8	8					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	92	92					
60404900	FRAMES AND GRATES, TYPE 12	EACH	3	3					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	14	14					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000					
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10170	10170					
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	319.4	319.4					
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14182	14182					
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2997	2997					
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1143	1143					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	327	327					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	319.4	319.4					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14182	14182					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2997	2997					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1143	1143					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	327	327					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	404	404					
*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	253	253					
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	1420	1420					
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8					
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1170	1170					
	X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	875	875					
	Z0017100	DOWEL BARS	EACH	168	168					
NP	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	100	100					
	Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	4	4					
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					

* SPECIALITY ITEMS
NP= Non-participating

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 2/5/2009

2/5/2009
c:\dgn_work\Bureau\plan\mdiv\ildems926x178th_cdev.dgn