

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	URBAN 100% FED. J000-2A	ROADWAY & DRAINAGE	TRAFFIC SIGNALS IL 59 @ U.S. ROUTE 30	TRAFFIC SIGNALS IL 59 @ LOCKPORT	ROADWAY LIGHTING	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS TEMPORARY INTERCONNECT	TRAFFIC SIGNALS EVP EQUIPMENT	WATER MAIN/ SANITARY SEWER	SIDEWALK
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	100		100								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	494		494								
20101100	TREE TRUNK PROTECTION	EACH	23		23								
20101200	TREE ROOT PRUNING	EACH	13		13								
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	8		8								
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	13		13								
20200100	EARTH EXCAVATION	CU YD	11851		11851								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	887		837							50	
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	837		837								
20800150	TRENCH BACKFILL	CU YD	2317		2317								
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3704		3704								
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	1357		1357								
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	200		200								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	64		64								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	64		64								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	64		64								
25100630	EROSION CONTROL BLANKET	SQ YD	3410		3410								
25200110	SODDING, SALT TOLERANT	SQ YD	5062		5062								
25200200	SUPPLEMENTAL WATERING	UNIT	52		52								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	707		707								
28000510	INLET FILTERS	EACH	123		123								
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	11943		6189								5754
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	277		277								
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1104		1104								
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	148		148								

FILE NAME =	USER NAME = #USER#	DESIGNED - JCM	REVISED -
\$FILEL\$		DRAWN - GLS	REVISED -
	PLOT SCALE = \$SCALE\$	CHECKED - JCM	REVISED -
	PLOT DATE = \$DATE\$	DATE - JANUARY 16, 2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 14 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	113 N-2	WILL	260	4
FED. ROAD DIST. NO. ILLINOIS			CONTRACT NO. 60E73	
			FAP 338 (IL RTE. 59)	